

# **NOTICE**

**All drawings located at the end of the document.**

# Resource Conservation and Recovery Act Post-Closure Care Permit Application

For U.S.D.O.E -Rocky Flats Plant  
Hazardous & Radioactive Mixed Wastes

CO7890010526

5 October 1988

Volume XV

**Prepared by:**

**ROCKWELL INTERNATIONAL**

**North American Aerospace Operations**

Reviewed for Classification/OUO/UCNI  
By: Janet Nesheim, Derivative Classifier  
DOE, EMCBC  
Date: 10-15-08  
Confirmed Unclassified, Not UCNI/Not OUO

**In Association with:**

**WESTON**  
MANAGERS DESIGNERS/CONSULTANTS




**Chen & Assoc, Inc**

**REVIEWED FOR CLASSIFICATION/UCNI**

By: [Signature]  
Date: 11/1/92

*Note: Pages extracted from  
draft "A Historical Summation  
of Environmental Incidents  
Affecting Soils At or Near the  
U.S. AEC Rocky Flats Plant," by  
J. B. Owen & L. M. Steward, are  
no longer OUO. Markings  
have been crossed off  
on individual pages.*



It is the policy of the Department of Energy that information is not to be released to the public unless it is required

Resource Conservation and Recovery Act  
Post-Closure Care  
Permit Application

For U S D O E -Rocky Flats Plant  
Hazardous & Radioactive Mixed Wastes


CO7890010526

*5 October 1988*

Volume XV



REVIEWED FOR CLASSIFICATION/UCM

By  4/1/92 PNP  
Date 4/1/92

RCRA POST-CLOSURE CARE PERMIT  
CONTENTS OF VOLUMES  
-----

SECTION -----	VOLUME -----
POST-CLOSURE CARE PERMIT Sections A through K	I II III IV
CLOSURE PLANS -----	
APPENDIX I-2 Solar Evaporation Ponds	V VI VII VIII
APPENDIX I-3 Present Landfill	IX X XI
APPENDIX I-4 West Spray Field	XII XIII
APPENDIX I-5 Original Process Waste Lines	XIV XV XVI
APPENDIX I-6 Container Storage Facilities	XVII
APPENDIX I-7 Building 443 No. 4 Fuel Oil Tank	XVIII
APPENDIX I-8 Hazardous Waste Storage Area, SWMU No. 203	XIX
APPENDIX I-9 Original Uranium Chip Roaster	XX
APPENDIX I-10 Building 444 Acid Dumpsters	XXI
APPENDIX I-11 Bench Scale Treatment Unit, No. 32	XXII
APPENDIX I-12 Acid Dumpsters and Solvent Dumpsters	XXIII



**ORIGINAL PROCESS WASTE LINES**

# **CLOSURE PLAN**

**U.S. DEPARTMENT OF ENERGY  
ROCKY FLATS PLANT  
GOLDEN, COLORADO**

**OCTOBER 3, 1988**

**ROCKWELL INTERNATIONAL  
NORTH AMERICAN AEROSPACE OPERATIONS  
ROCKY FLATS PLANT**

APPENDIX 2

ORIGINAL PROCESS WASTE LINES DATA SUMMARY SHEETS

2.1 Pipes

2.2 Tanks

APPENDIX 2 : ORIGINAL PROCESS WASTE LINES  
DATA SUMMARY SHEETS

The data summary sheets present all available data on the original process waste lines (OPWL) pipes and tanks. One summary sheet is provided for each pipe designation and one for each tank designation.

The data is presented in matrix form to allow comparison of information from several references. Across the top of the page are reference numbers which correspond to the references at the beginning of the respective section on pipes (2.1 Pipes) and tanks (2.2 Tanks). The information presented on each data sheet below the respective reference number was obtained from the corresponding reference.

## 2.1 PIPES

ORIGINAL PROCESS WASTE LINES

PIPES

----

SUMMARY DATA SHEETS

REFERENCES

- (1) ORIGINAL PROCESS WASTE LINE CLOSURE  
PLAN, Appendix A-5 of the Post-  
Closure Care Permit Application,  
November 26, 1986 Revision 0
- (2) CONCEPTUAL DESIGN REPORT,  
ENVIRONMENTAL IMPROVEMENT PROJECTS,  
Rockwell International, Rocky Flats Plant,  
Golden, Colorado, December, 1985
- (3) ROCKWELL INTERNATIONAL DRAWINGS,  
Specific drawing is indicated at  
each reference note
- (4) SURVEY OF THE STATUS OF THE EXISTING  
PROCESS WASTE LINES, Sunday, G ,  
September, 1976, Unnumbered Report
- (5) PROCESS WASTE LAYOUT,  
Drawing Number SK-410204-2,  
The Dow Chemical Company, March, 1971
- (6) REPORT OF AN INVESTIGATION ON A  
RECENT PROCESS WASTE PIPELINE LEAK,  
Rockwell International, October 24, 1980,  
ES 376-80 217
- (7) UNUSUAL OCCURENCE REPORT - VALVE  
VAULT #7 OVERFLOW, APRIL 4, 1983,  
Rockwell International, May 5, 1983,  
UOR NUMBER RFP 83 2-SAGE 83-1
- (8) A HISTORICAL SUMMATION OF ENVIRONMENTAL  
INCIDENTS AFFECTING SOILS AT OR NEAR  
THE U S AEC ROCKY FLATS PLANT, Dow Chemical,  
Undated (approximate date fall 1983),  
By J B. Owen and L M Steward (Draft)  
(DRAFT)

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (1) Reference: (2) Reference: (4) Reference: ( )

Pipe Designation: P-1  
Appendix 1 Map: E-2  
Building Area: 123  
SWMU Number: 121

Pipe Material: Polyethylene in steel

Description of Pipe Section: Western section of A-25

Pipe Diameter (in.): 3 inside 4  
Pipe Length (ft.): 180  
Line Volume (cubic feet):  
Date of Installation: 1968  
Date of Abandonment: June 1982  
Age (Years): 14  
Disposition: Abandoned

Waste Streams:

Reported Releases: Small amounts of low level lab wastes w/ nitrates; went to solar ponds  
Leak of 2.5 gal/hr at 37 psig found in 1971

Comments: \*Excludes portion beneath building



Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (4) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Pipe Designation: P-3  
Appendix 1 Map: E-2  
Building Area: 441  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Vitrified clay  
Eastern portion of  
A-25

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

4  
162  
1952  
June 1982  
30  
Decontaminated,  
removed and replaced  
with inspectable  
pipe  
Abandoned

Waste Streams:

Small amounts of low  
level lab waste with  
nitrites; went to  
solar ponds  
Leak of 2.5 gal/hr  
at 37 psig found in  
1971

Reported Releases:

None

Comments:

\*Does not include  
portion beneath  
building



## Pipes

Reference: (2)

**Reference: (4)**

Reference: ( )

Appendix 1 Map: E-2, E-3, E-4, E-5

E-2, E-3,

**Building Area:** 441 - 879

SWMU Number: 121

**Pipe Material:**

Description of Pipe Section:

Pipe Diameter (in.):

Pipe Length (ft.):

Line Volume (cubic feet):

**Date of Installation:**

Date of Abandonment:

Age (Years):

**Disposition:**

### Waste Streams:

**Reported Releases:**

Comments:

Pipes                      Pipes                      Pipes

Reference: (1)                      Reference: (2)                      Reference: (3)

Reference: ( )                      Reference: ( )                      Reference: ( )

DWGS 25838-X05 to X10  
DWGS 25838-DX1, D01 to D05

Pipe A-24	Pipe P-5

[illegible]

Process waste

**Yes; at P-4 & P-5**

\*Does not include  
portion beneath the  
building

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (1) Reference: (2) Reference: (3) Reference: (4)

Pipe Designation: P-6  
Appendix 1 Map: E-5, F-5  
Building Area: 881  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Reported Releases:

Comments:

Steel	Pipes A-19, A-22 and A-29	Stainless steel Portion of P-6 adjacent to T-24 and T-32	Steel From 881 to west of 884
3			
1300	820*		865
1957			1957
December 1980		After 7/2/76	
30			
Abandoned	Abandoned	Abandoned that portion adjacent to T24 and T32	
		Process waste	Laundry waste, process and lab waste; caustic 95% enriched U-235
Yes @ P-6 near Bldg. 881			
Yes @ P-4 and P-6			
Yes @ P-6, 9, 10 & 11			
	*Does not include pipe beneath Bldg. 881		

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipes	Reference: (3)	Reference: ( )	Reference: ( )

Original Process Waste Line  
Data Summary Sheet

Pipes	Reference: (1)	Reference: (2)	Reference: (3)
Pipe Designation: P-7			DWG 15507-4
Appendix 1 Map: F-5			
Building Area: 881 - 887			
SWMU Number: 121			
Pipe Material:	Stainless steel		Stainless steel
Description of Pipe Section:		Pipe A-30 or A-31	Exits south side of 881, connects 81 and 87
Pipe Diameter (in.): 4			4
Pipe Length (ft.): 440		A-30=75', A-31=75'*	
Line Volume (cubic feet):			
Date of Installation: 1952			
Date of Abandonment: December 1980			
Age (Years): 28			
Disposition: Abandoned			To be double contained under authorization #365556
Waste Streams:			Process waste
Reported Releases:	None		
Comments:		*Does not include pipe beneath Bldg. 881	

Original Process Waste Line  
Data Summary Sheet

Pipes

Pipe Designation: P-8  
Appendix 1 Map: F-5  
Building Area: 881 - 887  
SWMU Number: 121

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: (4) \_\_\_\_\_

DWGS 25609-X01 to  
-X09

Stainless steel

Cast iron  
Portion of P-8

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):

75' (A-30) &  
75' (A-31)

Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

1952  
December 1980  
28  
Decontaminated,  
removed and replaced  
with inspectable  
pipe

Abandoned portion  
beneath building and  
outside of building;  
removed piping above  
floor slab

Waste Streams:

Reported Releases:

Comments:

\*Does not include  
pipe beneath Bldg.  
881

## Pipes

Reference: (1)

Pipe Designation:	P-9
Appendix 1 Map:	E-5
Building Area:	883
STMU Number:	121

Steel

Pipe A-18

390\*

## Abandoned

[illegible]

Janitor water,  
process waste, and  
depleted uranium

Yes--0 p-9 and p-6

\*Does not include  
pipe beneath  
building

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: (4) \_\_\_\_\_

Pipe Designation: P-10  
Appendix 1 Map: E-5  
Building Area: 884 - 865  
SWMU Number: 121

DWGS 26378-X01 to  
-X05

Pipe Material: \_\_\_\_\_  
Description of Pipe Section: \_\_\_\_\_

Stainless steel  
P-10  
865

Stainless steel  
P-10

Pipe Diameter (in.): \_\_\_\_\_  
Pipe Length (ft.): \_\_\_\_\_  
Line Volume (cubic feet): \_\_\_\_\_  
Date of Installation: \_\_\_\_\_  
Date of Abandonment: \_\_\_\_\_  
Age (Years): \_\_\_\_\_  
Disposition: \_\_\_\_\_

3  
1190  
1968  
May 1982  
14

3  
550  
1968

Decontaminated,  
removed and replaced  
with inspectable  
pipe

All pipe beneath  
building capped and  
abandoned after  
8/21/81

Waste Streams:

Process waste  
Decontamination  
water contains  
uranium and pluton-  
ium from Bldg. 889

Reported Releases:

Yes-@ P-10 and P-6

Comments:

\*Does not include  
pipe beneath Bldg.  
865



## Pipes

**Pipe Material:**

Pipe Diameter (in.):  
 Pipe Length (ft.):  
 Line Volume (cubic feet):  
 Date of Installation:  
 Date of Abandonment:  
 Age (Years):  
 Disposition:

Reported Releases:

Comments:

Reference: ( )

ves-0 p-11 and p-6

In May 1971, was  
found to leak @ 2.7  
gal/hr @ 20 psig

---

---

---



Pipes  
Reference: (1) \_\_\_\_\_  
Reference: (2) \_\_\_\_\_  
Reference: (4) \_\_\_\_\_  
Reference: (8) \_\_\_\_\_

Pipe Material: \_\_\_\_\_  
Ribbed hose in \_\_\_\_\_  
Ribbed hose in \_\_\_\_\_

Pipe Diameter (in.):	3 inside 4	
Pipe Length (ft.):	523	
Line Volume (cubic feet):		
Date of Installation:	1975	
Date of Abandonment:	March 1984	
Age (Years):	9	
Disposition:	Abandoned	

Reported Releases:	Yes-0 intersection of P-13 and P-12	Yes-valve vault #7 leaked on 4/4/83
--------------------	--	--

Comments:	P-13 replaced P-12 which was destroyed by acid & steam (see data summary P-12)	Pipes P-13 and P-12 are the same length and immediately adjacent to each other, the only corresponding pipe is A-17
-----------	--	---

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (3) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Pipe Designation: P-13 (cont) DWG 15501-30  
Appendix 1 Map: D-5  
Building Area: 708  
SWMU Number: 121

Pipe Material:

Fiberglass inside  
fiberglass

Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

3 inside 4

Waste Streams:

Process waste

Reported Releases:

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1)      Reference: (2)      Reference: (4)      Reference: (8)

Pipe Designation: P-14  
Appendix 1 Map: C-5  
Building Area: 707  
SWMU Number: 121

Pipe Material:

Saran lined steel in  
VCP

Description of Pipe Section:

Saran lined steel in  
VCP  
P-14

Pipe Diameter (in.):

3 inside 10  
625

Pipe Length (ft.):

625

Line Volume (cubic feet):

Date of Installation:

1952

Date of Abandonment:

1968

Age (Years):

16

Disposition:

Decontaminated,  
removed and replaced  
with inspectable  
pipe

Abandoned

Abandoned-portions  
may have been  
removed for con-  
struction of Bldgs.  
707 and 777.

Waste Streams:

B441-low level lab  
waste w/98% depleted  
uranium.  
B444-process waste,  
depleted uranium.  
B123-low-level lab  
with nitrate.  
B881-laundry process  
and lab waste, 95%  
enriched U-235.  
B883-Janitor water  
process waste,  
caustic depleted U.  
Acid leaks @ P-14  
and P-12, P-13

Reported Releases:

"Some soil has been  
infiltrated in the  
immediate vicinity  
of the lines orig-  
inal location."

Original Process Waste Line  
Data Summary Sheet

Pipes

Pipe Designation: P-15  
Appendix 1 Map: C-5  
Building Area: 707  
SWMU Number: 121

Reference: (3)

DWG 15501-30

Reference: (4)

Reference: (2)

Reference: (1)

Pipe Material:

Stainless steel/  
saran lined pipe  
inside vitrified  
clay  
N&W sides of  
Bldg. 707

Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

3 and 3 inside 10  
740

3  
878

1968  
March 1984

16  
Abandoned

Waste Streams:

B123-Low level lab  
waste with nitrates.  
B444-Process waste,  
depleted uranium.  
B559-Plutonium lab  
waste.  
B889-Decontamination  
water w/Pu & U.  
B881-Laundry waste,  
process and lab  
waste, caustic, 95%  
enriched U-235.  
B883-Janitor water  
and process waste,  
depleted U.

Process waste

Reported Releases:

None

Comments:

## Pipes

Pipe Material:	Description of Pipe Section:

**Waste Streams:**

**Comments:**

Reference: (1)

Yes-@ P-16 & T-7

Pipes	Reference: (1)	Reference: (3)	Reference: (4)
-------	----------------	----------------	----------------

Pipes	Reference: (1)	Reference: (3)	Reference: (4)
-------	----------------	----------------	----------------

Reference: (3)

## Pipes

DWGS 25609-X01 to -X03 DWG 15501-20  
DWGS 24386-1 to -2

Pipe Material: \_\_\_\_\_  
 Pvmex (σ'glass) \_\_\_\_\_  
 Glass, glass/PVC, \_\_\_\_\_  
 Polyethylene/PVC \_\_\_\_\_  
 Glass \_\_\_\_\_

**Glass, glass/PVC,**

Pipe Material:

Description of Pipe Section:	P-17-abandoned beneath slab	P-17 (outside of building)

P-17--abandoned  
beneath slab

**Description of Pipe Section:**

4	4	3.4.4" PVC inside 6"	4	4
Pipe Diameter (in.):				

3.4.4" PVC inside 6"

Pipe Diameter (in.):

pipe length (ft.): 1130 160 135

---

Pipe Length (ft.):

Date of Installation:	1968
1968	

---

Date of Installation:

of drawing)

of drawing)

Age (Years): 14

100

Age (Years) ::

	Abandoned
	<u>Abandoned; removed</u>

Abandoned; removed

Disposition:

**Waste Streams:**

<u>Process waste from</u>	<u>B559-lab waste,</u>
<u>Process waste</u>	<u>Process waste</u>

Process waste from

### Waste Streams:

Reported Releases:	Yes @ P-17 under	
	Bldg. 559	

---

**Reported Releases:**

Comments: \_\_\_\_\_

10

Comments:



Pipes

Reference: (1) \_\_\_\_\_

Reference: (2) \_\_\_\_\_

Reference: (3) \_\_\_\_\_

Reference: (4) \_\_\_\_\_

Reference: (5) \_\_\_\_\_

Reference: ( )

Pipe Material: Rigid teflon Rigid teflon Rigid teflon

Pipe Diameter (in.) :
2.75
2.75
2.75
2.75

150

100

1968

July 1982

14

## Abandoned

11

None

**Comments:**

Pipes  
Reference: (1)  
Reference: (2)  
Reference: (3)  
Reference: (4)

**Comments:**

\*Does not include  
portion under  
Bldg. 707

None

16  
Abandoned

Original Process Waste Line  
Data Summary Sheet

Pipes

Pipe Designation: P-20  
Appendix 1 Map: B-5, C-5  
Building Area: 777  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Reported Releases:

Comments:

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

DWG 25845-X125  
-X085

Stainless steel

Portion of A-7  
running N-S

Stainless steel

P-20

3

499

480

3

455

1968

March 1984

1968

Abandoned

Abandoned

Bldgs. 123,444,559,  
707,865,883,889,881  
and 729

Yes-@ P-20,21, 25  
and 34

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) Reference: (2) Reference: (4) Reference: (3)

Pipe Designation: P-21  
Appendix 1 Map: B-5  
Building Area: 774  
SWMU Number: 121

DWG 15501-13

Pipe Material:  
Description of Pipe Section:

Stainless steel  
South 185' of F-2  
enters west side

Stainless steel

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

3  
386  
1952  
March 1984  
32  
Abandoned  
"To be abandoned  
when system is  
upgraded to an  
unspectable system  
in the future."

3  
291

1952

Waste Streams:

All buildings except  
B-771

Process waste

Reported Releases:

Yes-@ P-20, 21, 25  
and 34

Comments:

## Pipes

**Reference:** (3)

Reference: ( )

Appendix 1 Map: B-5

SWMU Number: 121

Description of Pipe Section:

Pipe Length (ft.):

**Date of Installation:**

Age (Years):

**Disposition:**

**Reported Releases:**

Comments:



Pipes	Reference: (1)	Reference: (2)	Reference: (4)	Reference: (3)

**DWG 15501-13**

Cast iron	Cast iron
P-24	

[illegible]

Janitor water and Process water

---

**Table 1**

Variable	Mean	SD	Range
Age	60.78	9.12	40–80
Gender			
Male	10		
Female	10		
Marital status			
Married	10		
Single	10		
Divorced	10		
Widowed	10		
Educational level			
Elementary school	10		
High school	10		
University	10		
Occupation			
Retired	10		
Unemployed	10		
Employed	10		
Income			
Less than \$10,000	10		
\$10,000–\$20,000	10		
More than \$20,000	10		

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (4) \_\_\_\_\_ Reference: (8) \_\_\_\_\_

Pipe Designation: P-25  
Appendix 1 Map: B-5  
Building Area: 774  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

SS/CI/Steel  
Southern portion of  
T-2  
Stainless steel  
P-25  
Line between Bldgs.  
771 and 774

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

3  
562  
1972  
May 1982  
10  
Abandoned  
Temporarily in use,  
to be abandoned

Waste Streams:

Bldg. 777  
Process waste

Reported Releases:

Yes-@ intersection  
of P-25 and P-28,  
P-35, 38, 43 & 44,  
also at P-21, P-24  
Yes-@ P-24 & 25, a  
leak at rate of 15  
gal/hr @ 20 psig,  
was found in 1977

Comments:

Yes-@ P-24 & 25, a  
leak at rate of 15  
gal/hr @ 20 psig,  
was found in 1971



Pipes	Reference: (3)	Reference: ( )	Reference: ( )
Pipe Designation: P-25 (cont)	DWG 15501-13		
Appendix 1 Map: B-5			
Building Area: 774			
SWMU Number: 121			
Pipe Material:	Cast iron and steel		
Description of Pipe Section:			
Pipe Diameter (in.):	3		
Pipe Length (ft.):	535		
Line Volume (cubic feet):			
Date of Installation:			
Date of Abandonment:			
Age (Years):			
Disposition:			
Waste Streams:	Process waste - forced		
Reported Releases:			
Comments:			

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (1) Reference: (2) Reference: (4) Reference: (3)

Pipe Designation: P-26 (two pipes)  
Appendix 1 Map: B-5, B-6  
Building Area: 774  
SWMU Number: 121

DWG 15501-13

Pipe Material:  
Description of Pipe Section:

Polyvinyl chloride

Pipe A-10

PVC  
Exists E774 to 207A

PVC

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

1.5 (each)

2750 (total)

1972

Late 1970s

Abandoned

635 (each)

1.5 (each)

1500 (total)

2-1 1/2" pipes

720 (each)

Abandoned

Waste Streams:

Process waste and  
process waste return

Reported Releases:

None

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes	Reference: (6)	Reference: ( )	Reference: ( )
Pipe Designation: P-26 (two pipes) cont.			
Appendix 1 Map: B-5, B-6			
Building Area: 774			
SWMU Number: 121			
Pipe Material:			
Description of Pipe Section:	Line between B774 and solar ponds		
Pipe Diameter (in.):	3		
Pipe Length (ft.):			
Line Volume (cubic feet):			
Date of Installation:			
Date of Abandonment:			
Age (Years):			
Disposition:			
Waste Streams:	Process waste		
Reported Releases:	Leak of radioactive liquid process waste occurred 7/21/80		
Comments:			

Original Process Waste Line  
Data Summary Sheet

Pipes	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)
Pipe Designation: P-27 (two pipes) Appendix 1 Map: B-5 Building Area: 774 SWMU Number: 121			DWG 15501-13	
Pipe Material: Description of Pipe Section:	Stainless steel	Pipes A-1 and F-1 and Part of F-2	Stainless steel P-27	Stainless steel
Pipe Diameter (in.): Pipe Length (ft.): Line Volume (cubic feet): Date of Installation: Date of Abandonment: Age (Years): Disposition:	3 185 (each) 1968 Active Active	195 (each)   A-1 is abandoned, F-1 and F-2 are to be abandoned when system is upgraded to inspectable system in the future	3 125 (each)   Process waste	  1968   Treated waste went to ponds
Waste Streams:				
Reported Releases:	Yes-@ intersection P-27 and P-28			
Comments:				

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (1) Reference: (2) Reference: (3) Reference: (4)

Pipe Designation: P-28 (two pipes)

Appendix 1 Map: B-5

Building Area: 774

SWMU Number: 121

DWG 15501-13

Pipe Material:

Description of Pipe Section:

Pipe Diameter (in.):

Pipe Length (ft.):

Line Volume (cubic feet):

Date of Installation:

Date of Abandonment:

Age (Years):

Disposition:

Waste Streams:

Reported Releases:

Comments:

Stainless steel

3

111 (each)

1972

Active

Active

A-1 is abandoned,  
F-2 is to be abandoned when system  
is upgraded to  
inspectable system  
in the future

Yes-0 intersection  
of P-28 with P-25  
and P-27

Pipes A-1 and F-2

115 (each)

Stainless steel

3

130 (each)

1972

Process waste

Stainless steel  
P-28

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Pipes	Reference: (5)	Reference: ( )	Reference: ( )
Pipes	Reference: (5)	Reference: ( )	Reference: ( )

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Pipe Designation: P-29  
Appendix 1 Map: B-5  
Building Area: 774  
SWMU Number: 121

DWG 15501-13

Pipe Material:  
Description of Pipe Section:

Stainless steel

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Stainless steel  
  
4  
197  
1952  
Active  
Active

4  
505

Waste Streams:

Process waste

Reported Releases:

None

Comments:

Bldg. 774 to solar  
pond 207C

Original Process Waste Line  
Data Summary Sheet

<u>Pipes</u>	<u>Reference: (1)</u>	<u>Reference: (2)</u>	<u>Reference: (3)</u>	<u>Reference: (4)</u>
Pipe Designation: P-30			DWG25845-X06S &	
Appendix 1 Map: B-5, C-5			X07S	
Building Area: 777				
SWMU Number: 121				
Pipe Material: Steel		Pipe A-7	Pipe P-30	
Description of Pipe Section:				
Pipe Diameter (in.): 4			2, 3, 4, 6	
Pipe Length (ft.): 667		70*	1,377	
Line Volume (cubic feet):				
Date of Installation:	1957			
Date of Abandonment:	October 1982			
Age (Years): 25				
Disposition: Decontaminated removed and replaced with inspectable pipe		Abandoned	Abandoned after 12-15-77	
			Process waste	
Waste Streams:				
Reported Releases:	None			
Comments:		*Does not include pipe length beneath building 776		



Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) Reference: (3) Reference: ( )

Pipe Designation: P-31  
Appendix 1 Map: B-5  
Building Area: 771 - 774  
SWMU Number: 121

DWG 26629-1

Pipe Material:  
Description of Pipe Section:

Steel

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

1  
167  
1952  
1972  
20  
Abandoned

P-31 located in  
pipe tunnel between  
B771 & B774

1, 4

DWGS indicate work  
to be done to remove  
the pipes in the  
tunnel

Waste Streams:

Process waste

Reported Releases:

None

Comments:

Pipe tunnel has been  
contaminated

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: (4) \_\_\_\_\_

Pipe Designation: P-32  
Appendix 1 Map: B-5,C-5  
Building Area: 777  
SWMU Number: 121

DWA 25845-X05S  
-X065 & -X12S

Pipe Material:  
Description of Pipe Section:

VCP/Steel/VCP  
Pipe A-8  
Steel/cast iron  
P-30  
Cast iron  
Existing N776 to  
776 tanks

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

6  
907  
1957  
Dec. 1982  
25  
Decontaminated,  
removed and replaced  
with inspectable  
pipe.  
Abandoned  
Portion Abandoned  
After 12-15-77  
Laundry waste  
Prior to 1969 was  
WW-level waste  
transferred to solar  
ponds; subsequent  
high plutonium waste

Waste Streams:

Laundry waste  
Prior to 1969 was  
WW-level waste  
transferred to solar  
ponds; subsequent  
high plutonium waste

Reported Releases:

None

Comments:

\* Does not include  
portion beneath  
Bldg. 776.

Pipes                      Pipes                      Pipes

Reference: (1)                      Reference: (3)                      Reference: ( )

Reference: ( )                      Reference: ( )                      Reference: ( )

Reference: ( )

Reference: ( )

Reference: (1)

Circumstance	Percentage of respondents (%)
If someone is attacking you	85
If someone is threatening you	75
If someone is harassing you	65
If someone is insulting you	55
If someone is annoying you	45

Steel

Steel ,

---

3

---

---

3

## Abandoned

100

## Process waste

---

---

---

None

---

100

1000

Original Process Waste Line  
Data Summary Sheet

<u>Pipes</u>	<u>Reference: (1)</u>	<u>Reference: (2)</u>	<u>Reference: (3)</u>	<u>Reference: ( )</u>
Pipe Designation: P-34				
Appendix 1 Map: B-5			DWG 15501-13	
Building Area: 774				
SWMU Number: 121				
Pipe Material: <u>Stainless steel</u>			<u>Steel</u>	
Description of Pipe Section:		<u>Pipe F-2</u>		
Pipe Diameter (in.): <u>3</u>			<u>3</u>	
Pipe Length (ft.): <u>127</u>		<u>130</u>	<u>305</u>	
Line Volume (cubic feet):				
Date of Installation: <u>1952</u>				
Date of Abandonment: <u>March 1984</u>				
Age (Years): <u>32</u>				
Disposition: <u>Abandoned</u>		<u>To be abandoned when</u>	<u>Abandoned</u>	
		<u>system is upgraded</u>		
		<u>to an inspectable</u>		
		<u>system in the future</u>		
			<u>Process waste</u>	
Waste Streams:				
Reported Releases:	<u>Yes-0 intersection</u>			
	<u>of P-33 and P-21</u>			
Comments:				

## Pipes

**Pipe Material:**  
**Description of Pipe Section:**

**Waste Streams:**

Reported Releases:

Comments:

R3eference:  
DWG 15501-13

Reference: (2)

Reference: (1)

Pipe A-2 or A-3  
(two pipes)

Pipe A-2 or A-3  
(two pipes)

Pipe A-2 or A-3  
(two pipes)

---

135

Abandoned

### Process waste

Yes-@ intersection  
of P-35 and P-25

Pipes  
Reference: (1)  
Pipes  
Reference: (2)  
Pipes  
Reference: (3)  
Pipes  
Reference: (4)

DWG 15501-13

Steel

Pipe A-2 or A-3 (two pipes)	3-ID-STL
	3-FW-STL
	(two pipes)
	3
135	
Abandoned	

---

---

Process waste

Yes-a intersection  
of p-35 and p-25

[illegible]

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Pipe Designation: P-36  
Appendix 1 Map: B-5, B-6  
Building Area: Pond 207  
SWMU Number: 121

DWG 15501-13

Pipe Material:  
Description of Pipe Section:

Stainless' steel/PVC

PVC

Pipe F-3

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

3  
599  
1965  
December 1982

530

3

To be abandoned when  
system is upgraded  
to an inspectable  
system in the future

Waste Streams:

Reported Releases:

Yes-Q intersection  
of P-36 with P-20,  
P-37, P-41 through  
P-44

Comments:

<u>Pipes</u>	<u>Reference:</u> (1)	<u>Reference:</u> (2)	<u>Reference:</u> (3)
Pipe Designation: P-37 Appendix 1 Map: B-5,B-6,C-6 Building Area: 730 - Pond 207 SWMU Number: 121	DWG 25845-X12S	DWG 15501-22	
Pipe Material: Description of Pipe Section:	Steel/PVC/VCP	Pipe 37, east/west pipe between B777 and B702	Stainless steel
Pipe Diameter (in.): Pipe Length (ft.): Line Volume (cubic feet): Date of Installation: Date of Abandonment: Age (Years): Disposition:	3 1449 1957 December 1982 25 Abandoned	3      Abandoned portion immediately adjacent to P-41 after 12/15/77	2-3"      
Waste Streams:		Process waste	Brine
Reported Releases:	Yes-@ intersection of P-37 with P-20, P-36 and P-38		
Comments:		DWG 25845-X12S does not show extension to solar pond 207A	Notes from Murray Maas indicate 3" stainless steel pipe used for return from R.O. to solar ponds



Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (4) Reference: (4) Reference: ( )

Pipe Designation: P-37 (cont)  
Appendix 1 Map: B-5, B-6, C-6  
Building Area: Pond 207  
SWMU Number: 121

Pipe Material: Steel  
Description of Pipe Section: 776 tanks to ponds  
Stainless steel  
776 tanks to valve  
pit north of tank  
207  
3  
402  
1957  
Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams: Process waste and  
process waste supply  
High volume-high  
activity (plutonium)

Reported Releases:

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (1) Reference: (2) Reference: (4) Reference: (3)

Pipe Designation: P-38  
Appendix 1 Map: B-5,B-6,C-6  
Building Area: Pond 207  
SWMU Number: 121

DWG 15501-22

Pipe Material: Vitrified clay/PVC  
Description of Pipe Section:

VCP  
Valve pit northeast  
of 207 to off site

VCP/PVC

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

10  
800  
1952  
December 1982  
30  
Abandoned  
A-4 is abandoned,  
T-5 is to be  
abandoned

10  
730

Waste Streams:

Process waste

Reported Releases:

Yes-@ intersection  
of P-38 with P-25  
and P-37

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: ( )

Reference: (4)

Reference: (2)

Reference: (1)

Pipe Designation: P-39  
Appendix 1 Map: C-6, C-7, C-8  
Building Area: 988 - Pond 207  
SWMU Number: 121

Pipe Material: Vitrified clay  
Description of Pipe Section:

Pipes T-5, A-27 and  
A-28

Vitrified clay  
Valve pit northeast  
of 207 to off site

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

6  
1817  
1957  
December 1982  
25  
Abandoned  
T-5 is temporarily  
in use, to be aban-  
doned; A-27 and A-28  
are abandoned

6  
2190

Waste Streams:

Reported Releases:

Yes-0 P-39 east end  
of pipe

Comments:

Pipes	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)
Pipes				

**DWG 15501-23**

Fiberglass	Portion of line under perimeter road to Pond B-2
------------	--

1617

Temporarily in use-  
to be abandoned

Process waste to  
Pond B-2

Small leak resulting  
from cable laying  
operation; line  
replaced

Pipe extending to  
Bldg. 990 and T-31  
indicated by Murray  
Maas; abandoned in  
place 1973

[illegible]

Pipes \_\_\_\_\_ Reference: (1) \_\_\_\_\_  
 Pipes \_\_\_\_\_ Reference: (2) \_\_\_\_\_  
 Pipes \_\_\_\_\_ Reference: (3) \_\_\_\_\_  
 Pipes \_\_\_\_\_ Reference: (4) \_\_\_\_\_

DWG 25845-X09S,  
-X10S and X12S  
and 15501-13

Stainless steel  
P-42

3  
164  
  
  
1957

Abandoned after  
12/15/77

## Process waste

Yes-- intersection  
of P-42 with P-36

*Does not include portion beneath building	Terminal end beneath Bldg. 779 plugged per detail "X01" DWG 25845-X05
--	--

Pipes	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)
Pipe Designation: P-43			DWG 25845-X12S &	
Appendix 1 Map: B-5			DWG 15501-13	
Building Area: 703				
SWMU Number: 121				
Pipe Material: Steel		Pipe T-4	Steel	
Description of Pipe Section:			East of Bldg. 703	
Pipe Diameter (in.):	3		3	
Pipe Length (ft.):	103		105	
Line Volume (cubic feet):				
Date of Installation:	1952			
Date of Abandonment:	December 1982			
Age (Years):	30			
Disposition:	Abandoned	Temporarily in use; to be abandoned		
Waste Streams:				
Reported Releases:	Yes @ intersection of P-43 with P-25 and P-36			
Comments:			DWG -X12S indicates to be abandoned after 12/15/77	

Pipes	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)
Pipe Designation: P-44			DWG 25845-X12S &	
Appendix 1 Map: B-5			DWG 15501-13	
Building Area: 703				
SWMU Number: 121				
Pipe Material: Steel		Pipe F-4	East of Bldg. 203	
Description of Pipe Section:				
Pipe Diameter (in.): 3				
Pipe Length (ft.): 92		70	75	
Line Volume (cubic feet):				
Date of Installation:	1952			
Date of Abandonment:	December 1982			
Age (Years): 30				
Disposition: Abandoned		To be abandoned when system is upgraded to an inspectable system in the future		
Waste Streams:				
Reported Releases:	Yes-Ø Intersection of P-44 with P-25 and P-36			
Comments:			DWG -X12S indicates line to be abandoned 12/15/77	





Pipes  
Reference: (2)  
Reference: (3)  
Reference: ( )  
Reference: ( )

**DWG 15501-13**

## Steel

135

## Abandoned

### Waste Streams:

None

**Comments:**

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (2) Reference: (3) Reference: ( )

Pipe Designation: P-47  
Appendix 1 Map: B-6  
Building Area: Ponds 207  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Reported Releases:

Comments:

DWG 15501-14

Cement-asbestos

3  
130

Pipe T-7 between  
ponds 207-C and  
207-A

125

Temporarily in use;  
to be abandoned

None

DWG indicates  
secondary reverse  
osmosis pipe

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (2) Reference: (3) Reference: ( )

Pipe Designation: P-48  
Appendix 1 Map: B-6  
Building Area: Ponds 207  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Reported Releases:

Comments:

DWG 15501-14

Pipe F-5 between  
ponds 207-C and  
207-A

193

To be abandoned when  
system is upgraded  
to an inspectable  
system in the future

Process waste

None

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (2) Reference: (3) Reference: ( ) Reference: ( )

Pipe Designation: P-49  
Appendix 1 Map: B-6  
Building Area: Ponds 207  
SWMU Number: 121

Pipe Material: Cast iron  
Description of Pipe Section: Pipe F-6 between  
ponds 207-C and  
207-A

Pipe Diameter (in.): 8  
Pipe Length (ft.): 85  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition: To be abandoned when  
system is upgraded  
to an inspectable  
system in the future

Waste Streams: Process waste (Pond  
207A) and forced  
process waste (Pond  
207C)

Reported Releases:

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: ( )

Reference: ( )

Reference: (3)

Reference: (2)

Pipe Designation: P-50  
Appendix 1 Map: B-6  
Building Area: Ponds 207  
SWMU Number: 121

DWG 15501-14

Pipe Material:

Description of Pipe Section:

Reference: ( )

Reference: ( )

Reference: (3)

Reference: (2)

Pipe Diameter (in.):

Pipe Length (ft.):

Line Volume (cubic feet):

Date of Installation:

Date of Abandonment:

Age (Years):

Disposition:

Pipe between pond  
207-A and 207-B  
north  
8  
85

Pipe between pond  
207-A and 207-B  
north  
8  
85

Pipe between pond  
207-A and 207-B  
north  
8  
85

Pipe F-7 between  
ponds 207-A and  
207-B north  
105

To be abandoned when  
system is upgraded  
to an inspectable  
system in the future

Waste Streams:

Reference: ( )

Reference: ( )

Reference: (3)

Reference: (2)

Reported Releases:

Reference: ( )

Reference: ( )

Reference: (3)

Reference: (2)

Comments:

Reference: ( )

Reference: ( )

Reference: (3)

Reference: (2)

Process waste (pond  
207B north) and  
forced process waste  
(pond 207A)

Process waste (pond  
207B north) and  
forced process waste  
(pond 207A)

None

Original Process Waste Line  
Data Summary Sheet

Pipes	Reference: ( )	Reference: (3)	Reference: ( )	Reference: ( )
Pipe Designation: P-51		DWG 25845-X16 &		
Appendix 1 Map: C-5		DWG 25845-X05S		
Building Area: 778				
SWMU Number: 121				
Pipe Material:		Black iron		
Description of Pipe Section:		Beneath Bldg. 778		
Pipe Diameter (in.):		4.6		
Pipe Length (ft.):		170		
Line Volume (cubic feet):				
Date of Installation:		1957		
Date of Abandonment:		1978		
Age (Years):		21		
Disposition:		Abandoned after		
		5/11/78 (portion		
		above floor slab was		
		removed)		
Waste Streams:		Laundry waste		
Reported Releases:		None		
Comments:		Drains and wall pen.		
		plugged with expan-		
		sive cement		

Pipes	Reference: (3)	Reference: (3)	Reference: ( )
Pipe Designation: P-52 Appendix 1 Map: E-3 Building Area: 443 SMWU Number: 121	DWGS 25838-DX1, and -D01 to -D05	DWG 25838-X04	
Pipe Material: Description of Pipe Section:	Beneath Bldg. 443		
Pipe Diameter (in.):			
Pipe Length (ft.):	280		
Line Volume (cubic feet):			
Date of Installation:			
Date of Abandonment:			
Age (Years):			
Disposition:	DWGS indicate pipes were decontaminated and abandoned in place or removed after 8/10/78	DWG indicates F.D. plugged and aban- doned in place	
Waste Streams:	Process waste	Process waste	
Reported Releases:	None		
Comments:			



Original Process Waste Line  
Data Summary Sheet

Pipes

Reference: (4)      Reference: (3)      Reference: ( )      Reference: ( )

Pipe Designation: P-53  
Appendix 1 Map: F-5  
Building Area: 881  
SWMU Number: 121

DWG 15501-54

Pipe Material:  
Description of Pipe Section:

Stainless steel  
Exits south side of  
B881; connects to  
81 and 87  
2  
78  
1952  
Abandoned under  
authorization  
#365556  
Laundry waste,  
process and lab  
waste, caustic 95%  
enriched uranium-235  
from Bldg. 881  
DWG 15507-4 Detail 1

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Nitrate drain

Reported Releases:

Comments:

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (4) Reference: ( ) Reference: ( )

Pipe Designation: P-54  
Appendix 1 Map: F-5  
Building Area: 881  
SWMU Number: 121

Pipe Material:  
Description of Pipe Section:

Pipe Diameter (in.):  
Pipe Length (ft.):  
Line Volume (cubic feet):  
Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

Waste Streams:

Reported Releases:

Comments:

Stainless steel  
Exits south side of  
B881, connects 81  
and 87  
3  
140  
1952  
To be double con-  
tained, authoriza-  
tion #365556  
Laundry waste;  
process and lab  
waste; caustics, 95%  
enriched U-235 from  
Bldg. 881  
DWG 15507-1 Detail 1



Pipes  
Reference: (4)  
Reference: ( )  
Reference: ( )  
Reference: ( )

**Appendix 1 Map: B-5**

**SWMU Number:** 121

**Description of Pipe Section:** Tunnel between B771

Pipe Length (ft.):

167 (each)

Date of Installation: \_\_\_\_\_

Age (Years) :

Waste Streams:

Janitor waste and

water with plutonium;

was low level and

**Reported Releases:**

None; lines were in a

contained and

**Comments:**

Original Process Waste Line  
Data Summary Sheet

Pipes Reference: (4) Reference: ( ) Reference: ( )

Pipe Designation: P-57  
Appendix 1 Map: E-2  
Building Area: 122, 123  
SWMU Number: 121

Pipe Material: Cast iron  
Description of Pipe Section: Line between 122  
and 123

Pipe Diameter (in.): 4  
Pipe Length (ft.): 20  
Line Volume (cubic feet): 1952  
Date of Installation:   
Date of Abandonment:   
Age (Years):   
Disposition:

Waste Streams:

Reported Releases: Yes-2.5 gal/hr @  
37 psig

Comments:

## 2.2 TANKS

ORIGINAL PROCESS WASTE LINES

TANKS

-----

SUMMARY DATA SHEETS

REFERENCES

- (1) ORIGINAL PROCESS WASTE LINE CLOSURE  
PLAN, Appendix A-5 of the Post-  
Closure Care Permit Application,  
November 26, 1986, Revision 0
- (2) CONCEPTUAL DESIGN REPORT,  
ENVIRONMENTAL IMPROVEMENT PROJECTS,  
Rockwell International, Rocky Flats Plant,  
Golden Colorado, December, 1985.
- (3) ROCKWELL INTERNATIONAL DRAWINGS,  
Specific drawings are indicated at  
each reference note
- (4) SURVEY OF THE STATUS OF THE EXISTING  
PROCESS WASTE LINES, Sunday, G ,  
Rockwell International, September, 1976,  
(unnumbered report)
- (5) UNDERGROUND STORAGE TANK REPORT,  
Rockwell International, May 1986
- (6) TANK LIST, Rockwell International,  
Mr Bob James, 1988
- (7) RCRA Part B Operating Permit  
Application, U.S DOE Rocky Flats  
Plant, Hazardous and Radioactive Mixed  
Wastes, 15 December 1987, Revision No 1,  
C07890010526

Tanks

Reference: (1) \_\_\_\_\_ Reference: (5) \_\_\_\_\_ Reference: (6) \_\_\_\_\_

Number of Tanks:	1
Tank Material:	Stainless steel
Description of Tank:	AG-1
	Underground
	Stainless steel
	1
	Stainless steel
	1

Date of Installation:					
Date of Abandonment:	January 1984			January 1984	1955
Age (Years):	33			33	29
Disposition:	Removed			Removed	Removed

Reported Releases:

**Comments:**



Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (1) Reference: (5) Reference: (6) Reference: ( )

Tank Designation: T-2  
Appendix 1 Map: E-2  
Rocky Flats Number: 36  
SWMU Number: 121  
Building Number: 441

Number of Tanks:	1	1	1
Tank Material:	Concrete	Concrete	Concrete
Description of Tank:	SU/UG (open/closed top sump/underground)		
Tank Diameter (in.):			
Tank Height (ft.):			
Tank Volume (gallons):	3000	3000	3000
Date of Installation:			
Date of Abandonment:	June 1982	June 1982	June 1982
Age (Years):	36	36	35
Disposition:	Active-converted to the new process waste or the fire water deluge collection systems	Active	Converted to plenum deluge
Waste Streams:			
		Rad., Bldg. 123 process wastes	
Reported Releases:	None		
Comments:			

Tanks  
Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (3) \_\_\_\_\_  
Reference: (4) \_\_\_\_\_ Reference: (5) \_\_\_\_\_ Reference: (6) \_\_\_\_\_

Number of Tanks:	1	1
Tank Material:	Concrete	Concrete
Description of Tank:	UG	Buried; Tank T-F South of

Date of Installation:					
Date of Abandonment:	June 1982				
Age (Years):	36			36	
Disposition:	Abandoned		To be removed		Old process waste

[illegible][illegible]

Comments:

Tanks

Reference: (1)	Reference: (5)	Reference: (6)	Reference: ( )
----------------	----------------	----------------	----------------

Number of Tanks:	2
Tank Material:	Concrete
Description of Tank:	SU

Date of Installation:			
Date of Abandonment:	April 1982	April 1982	1962
Age (Years) :	26		
Disposition:	Abandoned	Abandoned, cleaned	old process waste

**Reported Releases:**

Comments:



Original Process Waste Line  
Data Summary Sheet

Tanks

Reference: (6)      Reference: ( )      Reference: ( )

Tank Designation: T-5 (cont)  
Appendix 1 Map: E-3  
Rocky Flats Number: 81-85  
SWMU Number: 121  
Building Number: 444

Number of Tanks:  
Tank Material:  
Description of Tank:

5  
Steel

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

4000

Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

1952

Old process waste  
tank currently under  
closure

Waste Streams.

Reported Releases:

Comments:

Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: (4)	Reference: (5)	Reference: (6)
Tank Designation: T-6				
Appendix 1 Map: E-3				
Rocky Flats Number: 86,87				
SWMU Number: 121				
Building Number: 444				
Number of Tanks:	2		4	2
Tank Material:	Concrete	Concrete w/floor drain		Concrete
Description of Tank:	UG (underground)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	400	500	500 to 3500	400
Date of Installation:				1952
Date of Abandonment:	April 1981		April 1981	
Age (Years):	36	36	36	
Disposition:	Active-converted to the new process waste or the fire water deluge collection systems	To be made doubly contained Auth. #385050	Active-cleaned and painted in April 1981	Old process waste tank currently under closure
Waste Streams:			Rad.	
Reported Releases:	None			
Comments:				

Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (1) Reference: (3) Reference: (6) Reference: ( )

Tank Designation: T-7  
Appendix 1 Map: C-4  
Rocky Flats Number: 88  
SWMU Number: 121  
Building Number: 528

Number of Tanks: 1  
Tank Material: Concrete  
Description of Tank: Buried  
(above grade in depressed sump)

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

Date of Installation:  
Date of Abandonment: July 1982  
Age (Years):  
Disposition: Abandoned

Old process waste tank currently under closure

Removed piping inside tank after 6/17/76

Waste Streams:

Reported Releases:

Yes - @ Intersection of T-7 and P-16

Comments:

## Tanks

Number of Tanks:  
Tank Material:  
Description of Tank:

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

**Waste Streams:**

Reported Releases:

Comments:

## Tanks

Reference: (1)Reference: (2)

Reference: (5)

Reference: (6)

**Number of Tanks:**

**Tank Material:**

Description of Tank:

2/

## Concrete

**NS**

(open top sump)

Tank Diameter (in.):

Tank Height (ft.):

Tank Volume (gallons):

25,000

**Date of Abandonment:**

**Age (Years):**

**Disposition:**

May 1984

36

Active-converted

to the new process

the fish products  
waste system or the

firewater deluxe

collection system

**Waste Streams:**

Reported Releases:

Yes - @ intersection  
of T-8 with P-22,  
P-23 and P-24

Comments:



Tanks	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)

DWG 25845-X06S

2

22,500 (25'x15'x10')

To be decontaminated

Laundry waste and  
process waste

1000

100

---

## Tanks

Reference: (5)

Reference: (6)

Reference: ( )

Reference: ( )

Tank Designation: T-9 (continued)

Appendix 1 Map: B-5

Rocky Flats Number: 40,41

SWMU Number: 118.1

Building Number. 730

### Number of Tanks:

**Tank Material:**

Description of Tank:

**Tank Diameter (in.):**

Tank Height (ft.):

Tank Volume (gallons):

**Date of Installation:**

**Date of Abandonment:**

Age (Years):

**Disposition:**

**Waste Streams:**

**Reported Releases:**

Comments:

Tanks	Reference: (1)	Reference: (2)	Reference: (3)	Reference: (4)
				DWG:

Number of Tanks:	2
Tank Material:	Concrete
Description of Tank:	UG (underground)
	2
	Concrete
	Buried 26 ft. deep
	N. of Bldg. 776

Date of Installation:		
Date of Abandonment:	December 1982	
Age (Years):	33	
Disposition:	Abandoned	To be decontaminated

**Reported Releases:**

**Comments:**

**Tanks**                      Reference: (6)                      Reference: ( )                      Reference: ( )

Appendix 1 Map: B-5

SWMU Number: 139.1

**Number of Tanks:**

Description of Tank:

Tank Height (ft.):

**Date of Installation:**

Age (Years):

### Waste Streams:

**Reported Releases:**

**Comments:**



<u>Tanks</u>	<u>Reference: (6)</u>	<u>Reference: (7)</u>	<u>Reference: ( )</u>	<u>Reference: ( )</u>
Tank Designation:	T-11 (cont)			
Appendix 1 Map:	C-5			
Rocky Flats Number:	45,46			
SWMU Number:	121			
Building Area:	731			
	.			
Number of Tanks:	2	1		
Tank Material:	Concrete	Concrete		
Description of Tank:		Secondary containment for process waste		
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	2000	23113		
		25.8' X 12' X 10'		
Date of Installation:	1960			
Date of Abandonment:	July 1982			
Age (Years):	28			
Disposition:				
Waste Streams:	Contents: double containment	Laundry room waste		
Reported Releases:				
Comments:		Part B		
		Secondary containment		
		Reference 2011		

Tanks	Reference: (1)	Reference: (6)
	Reference: ( )	Reference: ( )

Number of Tanks:	2
Tank Material:	Concrete
Description of Tank:	UG

Date of Installation:		
Date of Abandonment:	May 1984	
Age (Years):	36	
Disposition:	Abandoned	Old process waste

**Reported Releases:**

**Comments:**

Tanks	Reference: (1)	Reference: (2)	Reference: (6)	Reference: ( )
Tank Designation: T-13				
Appendix 1 Map: B-5				
Rocky Flats Number: 91				
SWMU Number: 121				
Building Number: 774				
Number of Tanks:	1		1	
Tank Material:	Concrete		Concrete	
Description of Tank:	SU (open top sump)	Tank T-B Underground		
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	Approx. 600	7,000	600	
Date of Installation:			1952	
Date of Abandonment:	1972			
Age (Years):	36			
Disposition:	Abandoned	To be removed	Old process waste tank currently under closure	
Waste Streams:				
Reported Releases:	None			
Comments:				



## Tanks

Tank Designation:	T-14
Appendix 1 Map:	B-5
Rocky Flats Number:	50
SWMU Number:	121
Building Number:	774

Number of Tanks:  
Tank Material:  
Description of Tank:

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

**Waste Streams:**

**Reported Releases:**

**Comments:**

Reference: (1) \_\_\_\_\_

Reference: (4) \_\_\_\_\_

Reference: (5) \_\_\_\_\_

Reference: (3) \_\_\_\_\_

DWG 26629-1

<u>1</u>	<u>Concrete</u>	<u>UG</u>	<u>(underground)</u>	<u>30,000</u>	<u>July 1982</u>	<u>36</u>	<u>Filled with gravel</u>	<u>and capped</u>	<u>Yes - @ in area of</u>	<u>of tanks T-14, T-15</u>	<u>T-16 and T-17</u>
<u>1</u>				<u>30,000</u>	<u>July 1982</u>						
<u>1</u>				<u>33,000</u>	<u>July 1982</u>		<u>Filled with gravel</u>	<u>and capped</u>			
<u>1</u>				<u>30,000</u>							

Original Process Waste Line  
Data Summary Sheet

Tanks

Reference: (6)      Reference: ( )      Reference: ( )

Tank Designation: T-14 (cont)

Appendix 1 Map: B-5

Rocky Flats Number: 50

SWMU Number: 121

Building Area: 774

Number of Tanks:

Tank Material:

Description of Tank:

Tank Diameter (in.):

Tank Height (ft.):

Tank Volume (gallons):

Date of Installation:

Date of Abandonment:

Age (Years):

Disposition:

Waste Streams:

Reported Releases:

Comments:

1  
Concrete

30,000

1953

Gravel filled with  
concrete cap 7/82

Contents: radio-  
nuclides



Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (1) Reference: (2) Reference: (4) Reference: (5)

Tank Designation: T-16  
Appendix 1 Map: B-5  
Rocky Flats Number: 94, 95  
SWMU Number: 121  
Building Number: 774

Number of Tanks:	2		2	
Tank Material:	Concrete			
Description of Tank:	UG (underground)	Tank T-C, Buried		
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	14,000	14,000 (each)	14,000	14,000
Date of Installation:				
Date of Abandonment:	1970			
Age (Years):	36			
Disposition:	Abandoned	To be removed after inspectable system is installed		
Waste Streams:				
Reported Releases:	Yes - in area of tanks T-14, T-15, T-16 and T-17			
Comments:		In Ref. 2, tank T-C also includes 1-3000 gal. buried tank		

Original Process Waste Line  
Data Summary Sheet

Tanks \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: (6) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Tank Designation: T-16 cont DWG 26629-1  
Appendix 1 Map: B-5  
Rocky Flats Number: 94,95  
SWMU Number: 121  
Building Number: 774

Number of Tanks: 2 \_\_\_\_\_

Tank Material: \_\_\_\_\_

Description of Tank: \_\_\_\_\_  
Appear as concrete  
concrete vaults

Tank Diameter (in.): \_\_\_\_\_

Tank Height (ft.): \_\_\_\_\_

Tank Volume (gallons): 14,000 \_\_\_\_\_

Date of Installation: 1952 \_\_\_\_\_

Date of Abandonment: 1970 \_\_\_\_\_

Age (Years): 36 \_\_\_\_\_

Disposition: Abandoned \_\_\_\_\_

Waste Streams: \_\_\_\_\_

Reported Releases: \_\_\_\_\_

Comments: \_\_\_\_\_

Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (1)                      Reference: (5)                      Reference: (3)                      Reference: (6)                     

Tank Designation: T-17  
Appendix 1 Map: B-5  
Rocky Flats Number: 96-99  
SWMU Number: 121  
Building Number: 774

DWG 26629-1

Number of Tanks:	4	2	4
Tank Material:	Concrete		Concrete
Description of Tank:	UG (underground)	Horizontal cylindrical tanks	
Tank Diameter (in.):			
Tank Height (ft.):			
Tank Volume (gallons):	7,500		7500
Date of Installation:			1969
Date of Abandonment:	1970		1970
Age (Years):	34		19
Disposition:	Removed		Removed
Waste Streams:			
Reported Releases:	Yes - in area of tanks T-14, T-15, T-16 and T-17		
Comments:			

Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (1) Reference: (3) Reference: (6) Reference: ( )

Tank Designation: T-18  
Appendix 1 Map: C-5  
Rocky Flats Number: 100  
SWMU Number: 121  
Building Number: 778

DW6 25845-X16

Number of Tanks:	1		
Tank Material:	Concrete		
Description of Tank:	UG (underground)	North side of bldg. @ grid coord. A-5W	
Tank Diameter (in.):			
Tank Height (ft.):			
Tank Volume (gallons):			
Date of Installation:			
Date of Abandonment:	October 1982		October 1982
Age (Years):			
Disposition:			Removed
Waste Streams:		Laundry waste	
Reported Releases:	None		
Comments:		Laundry waste lift station	

Original Process Waste Line  
Data Summary Sheet

Tanks

Reference: (1) \_\_\_\_\_ Reference: (4) \_\_\_\_\_ Reference: (5) \_\_\_\_\_ Reference: (6) \_\_\_\_\_

Tank Designation: T-19  
Appendix 1 Map: C-5  
Rocky Flats Number: 101,102  
SMU Number: 121  
Building Number: 779

Number of Tanks: 2  
Tank Material: Concrete  
Description of Tank: UG (underground)

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons): 1,000 (5'x9'x7.5')

Date of Installation:  
Date of Abandonment: December 1982  
Age (Years): 24  
Disposition: Abandoned  
To be doubly contained  
Auth. #375030

Waste Streams.

Reported Releases:

Comments:

2 Concrete  
1,000  
December 1982  
15  
Abandoned, cleaned and painted in December 1982  
1964  
December 1982  
24  
Decontaminated and converted to non-UST

2 Concrete  
1,000  
December 1982  
24  
Abandoned  
None





## Tanks

Number of Tanks:	Tank Material:	Description of Tank:
1	Steel	1000 Gallon
2	Aluminum	500 Gallon
3	Concrete	2000 Gallon
4	Steel	1500 Gallon
5	Aluminum	750 Gallon
6	Concrete	3000 Gallon
7	Steel	1200 Gallon
8	Aluminum	600 Gallon
9	Concrete	2500 Gallon
10	Steel	1800 Gallon
11	Aluminum	900 Gallon
12	Concrete	3500 Gallon
13	Steel	2200 Gallon
14	Aluminum	1100 Gallon
15	Concrete	4000 Gallon
16	Steel	2800 Gallon
17	Aluminum	1400 Gallon
18	Concrete	4500 Gallon
19	Steel	3200 Gallon
20	Aluminum	1600 Gallon
21	Concrete	5000 Gallon
22	Steel	3800 Gallon
23	Aluminum	1900 Gallon
24	Concrete	5500 Gallon
25	Steel	4200 Gallon
26	Aluminum	2100 Gallon
27	Concrete	6000 Gallon
28	Steel	4800 Gallon
29	Aluminum	2400 Gallon
30	Concrete	6500 Gallon
31	Steel	5200 Gallon
32	Aluminum	2600 Gallon
33	Concrete	7000 Gallon
34	Steel	5800 Gallon
35	Aluminum	2800 Gallon
36	Concrete	7500 Gallon
37	Steel	6200 Gallon
38	Aluminum	3000 Gallon
39	Concrete	8000 Gallon
40	Steel	6800 Gallon
41	Aluminum	3200 Gallon
42	Concrete	8500 Gallon
43	Steel	7200 Gallon
44	Aluminum	3400 Gallon
45	Concrete	9000 Gallon
46	Steel	7800 Gallon
47	Aluminum	3600 Gallon
48	Concrete	9500 Gallon
49	Steel	8200 Gallon
50	Aluminum	3800 Gallon
51	Concrete	10000 Gallon
52	Steel	8800 Gallon
53	Aluminum	4000 Gallon
54	Concrete	10500 Gallon
55	Steel	9200 Gallon
56	Aluminum	4200 Gallon
57	Concrete	11000 Gallon
58	Steel	9800 Gallon
59	Aluminum	4400 Gallon
60	Concrete	11500 Gallon
61	Steel	10200 Gallon
62	Aluminum	4600 Gallon
63	Concrete	12000 Gallon
64	Steel	10800 Gallon
65	Aluminum	4800 Gallon
66	Concrete	12500 Gallon
67	Steel	11200 Gallon
68	Aluminum	5000 Gallon
69	Concrete	13000 Gallon
70	Steel	11800 Gallon
71	Aluminum	5200 Gallon
72	Concrete	13500 Gallon
73	Steel	12200 Gallon
74	Aluminum	5400 Gallon
75	Concrete	14000 Gallon
76	Steel	12800 Gallon
77	Aluminum	5600 Gallon
78	Concrete	14500 Gallon
79	Steel	13200 Gallon
80	Aluminum	5800 Gallon
81	Concrete	15000 Gallon
82	Steel	13800 Gallon
83	Aluminum	6000 Gallon
84	Concrete	15500 Gallon
85	Steel	14200 Gallon
86	Aluminum	6200 Gallon
87	Concrete	16000 Gallon
88	Steel	14800 Gallon
89	Aluminum	6400 Gallon
90	Concrete	16500 Gallon
91	Steel	15200 Gallon
92	Aluminum	6600 Gallon
93	Concrete	17000 Gallon
94	Steel	15800 Gallon
95	Aluminum	6800 Gallon
96	Concrete	17500 Gallon
97	Steel	16200 Gallon
98	Aluminum	7000 Gallon
99	Concrete	18000 Gallon
100	Steel	16800 Gallon
101	Aluminum	7200 Gallon
102	Concrete	18500 Gallon
103	Steel	17200 Gallon
104	Aluminum	7400 Gallon
105	Concrete	19000 Gallon
106	Steel	17800 Gallon
107	Aluminum	7600 Gallon
108	Concrete	19500 Gallon
109	Steel	18200 Gallon
110	Aluminum	7800 Gallon
111	Concrete	20000 Gallon
112	Steel	18800 Gallon
113	Aluminum	8000 Gallon
114	Concrete	20500 Gallon
115	Steel	19200 Gallon
116	Aluminum	8200 Gallon
117	Concrete	

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

**Waste Streams:**

Reported Releases:

**Comments:**

Reference: ( )

Reference: ( ) \_\_\_\_\_

Reference: (6)\_\_\_\_\_

Reference: (1)\_\_\_\_\_

[illegible]

Original Process Waste Line  
Data Summary Sheet

Tanks

Reference: (1) \_\_\_\_\_ Reference: (5) \_\_\_\_\_ Reference: (6) \_\_\_\_\_ Reference: ( ) \_\_\_\_\_

Tank Designation: T-22  
Appendix 1 Map: E-5  
Rocky Flats Number: 58  
SWMU Number: 164.2  
Building Number: 828

Number of Tanks:  
Tank Material:  
Description of Tank:

2  
Stainless steel  
AG2  
(above grade in  
depressed sump)

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons):

250

Date of Installation:  
Date of Abandonment:  
Age (Years):  
Disposition:

1978  
25  
Abandoned

Waste Streams:

Uranium wastes  
Radionuclides (to be  
verified)

Reported Releases:

None

Comments:

Possibly removed  
from ground

Original Process Waste Line  
Data Summary Sheet

Tanks

Reference: (1) \_\_\_\_\_ Reference: (3) \_\_\_\_\_ Reference: (4) \_\_\_\_\_ Reference: (5) \_\_\_\_\_

DWG 26378-X01

Tank Designation: T-23  
Appendix 1 Map: E-5  
Rocky Flats Number: 59,60  
SWMU Number: 121  
Building Number: 865

Number of Tanks: 2  
Tank Material: Concrete  
Description of Tank: UG (underground)  
  
Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons): 3,000

Date of Installation:  
Date of Abandonment:  
Age (Years): 9  
Disposition: Abandoned

May 1982  
9  
Abandoned, cleaned  
and painted in May  
1982

Waste Streams:

Removed piping and  
pumps at least after  
8/21/81

To be double  
contained

Process waste

Reported Releases:

None

Comments:

Tanks

Reference: (6)

Reference: ( )

Reference: ( )

Number of Tanks:	2
Tank Material:	Concrete
Description of Tank:	Underground

[illegible]

Reported Releases:

Under RCRA closure

Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: (4)	Reference: (5)	Reference: (3)
Tank Designation: T-24				DWG 25609-X09
Appendix 1 Map: F-5				
Rocky Flats Number: 105-111				
SWMU Number: 121				
Building Number: 887				
Number of Tanks:	7	7	7	7
Tank Material:	Stainless steel	Stainless steel	Stainless steel	
Description of Tank:	AG2 (above grade in depressed sump)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	2,700	2,700	2,000	
Date of Installation:				
Date of Abandonment:	December 1980		December 1980	
Age (Years):	36	36	36	"To remain"; Drawing date 6/17/76
Disposition:	Active-converted to the new process waste system or the firewater deluge collection system		Active	
Waste Streams:				Process waste
Reported Releases:	None			
Comments:				



Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: (4)	Reference: (5)	Reference: (6)
Tank Designation: T-25				
Appendix 1 Map: E-5				
Rocky Flats Number: 112,113				
SWMJ Number: 121				
Building Area: 883				
Number of Tanks:	2	1	1	2
Tank Material:	Steel	Welded stainless steel	Steel	Steel
Description of Tank:	AG2			
	(above grade in depressed sump)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	750	750	750	750
Date of Installation:				1952
Date of Abandonment:	August 1984		August 1984	August 1984
Age (Years):	23	23	14	36
Disposition:	Active-converted to the new process waste system or the firewater deluge collection system		Active	Converted to new system
Waste Streams:				
Reported Releases:	None			
Comments:				



<u>Tanks</u>	<u>Reference: (1)</u>	<u>Reference: ( )</u>	<u>Reference: ( )</u>	<u>Reference: ( )</u>
Tank Designation:	T-25 (cont)			
Appendix 1 Map:	E-5			
Rocky Flats Number:	112-113			
SWMU Number:	121			
Building Number:	883			
Number of Tanks:	2			
Tank Material:	Steel			
Description of Tank:				
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	750			
Date of Installation:	1956			
Date of Abandonment:				
Age (Years):	32			
Disposition:				
Waste Streams:	Waste water, pH>10			
Reported Releases:				
Comments:	Part B Ref. No.			
	40.30 & 40.31			

## Tanks

Reference: (1) \_\_\_\_\_

Reference: (4) \_\_\_\_\_

Reference: (6) \_\_\_\_\_

Reference: ( ) \_\_\_\_\_

Tank Designation:	T-27
Appendix 1 Map:	E-5
Rocky Flats Number:	117
SWMU Number:	121
Building Number:	886

**Number of Tanks:**

**Tank Material:**

Description of Tank:

Tank Diameter (in.):

Tank Height (ft.):

Tank Volume (gallons):

**Date of Installation:**

**Date of Abandonment:**

Age (Years):

Disposition:

**Waste Streams:**

**Reported Releases:**

**Comments:**

1 Steel  
AG1 (aboveground)

---

300

1978

## Abandoned

None

1  
Steel  
Above ground; 18'  
west of Bldg. 886

300

1978

## Abandoned

7

300

1978

## Abandoned

Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: (3)	Reference: (4)	Reference: (5)
Tank Designation: T-28				
Appendix 1 Map: E-5				
Rocky Flats Number: 62,63				
SWMU Number: 121				
Building Number: 889				
Number of Tanks:	2			2
Tank Material:	Concrete		Concrete/carbolene Lining	Concrete
Description of Tank:	UG (Underground)	Underground	Underground (15' deep)	Underground
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):	1,000		1,000 (5'x7'x4.25')	1,000
Date of Installation:				
Date of Abandonment:	May 1983			May 1983
Age (Years):	23			14
Disposition:	Abandoned	Removed piping and plumbing inside tanks after 8/21/81	To be doubly contained under Auth. #385050	Not cleaned
Waste Streams:				
Reported Releases:	None			
Comments:				

Original Process Waste Line  
Data Summary Sheet

Tanks                      Reference: (6)                      Reference: ( )                      Reference: ( )

Tank Designation: T-28 (cont)  
Appendix 1 Map: E-5  
Rocky Flats Number: 62,63  
SWMU Number: 121  
Building Number: 889

Number of Tanks: 2  
Tank Material: Concrete  
Description of Tank: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Tank Diameter (in.): \_\_\_\_\_  
Tank Height (ft.): \_\_\_\_\_  
Tank Volume (gallons): 1000

Date of Installation: \_\_\_\_\_  
Date of Abandonment: 1966  
Age (Years): May 1983  
Disposition: 22  
Currently old  
process tank

Waste Streams: Radionuclides  
\_\_\_\_\_  
\_\_\_\_\_

Reported Releases: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Comments: Under RCRA closure  
\_\_\_\_\_  
\_\_\_\_\_

## Tanks

Reference: (1) \_\_\_\_\_ Reference: (2) \_\_\_\_\_ Reference: (5) \_\_\_\_\_ Reference: (6) \_\_\_\_\_

Reference: (5)

Reference: (2)

Reference: (1)

Reference: (6)

Tank Designation:	T-29
Appendix 1 Map:	B-5
Rocky Flats Number:	118
SWMU Number:	121
Building Number:	207

Number of Tanks:

**Tank Material:**

Description of Tank:

Tank Diameter (in.):

Tank Height (ft.):

Tank Volume (gallons):

Date of Installation:

Date of Abandonment:

Age (Years):

**Disposition:**

**Waste Streams:**

**Reported Releases:**

Comments:

[illegible]

Original Process Waste Line  
Data Summary Sheet

	Reference: (1)	Reference: (3)	Reference: (6)	Reference: (7)
<u>Tanks</u>				
Tank Designation: T-30		DWG 25788-X12		
Appendix 1 Map: C-5				
Rocky Flats Number: 119				
SMU Number: 121				
Building Number: 731				
Number of Tanks:	1		1	1
Tank Material:	Concrete	Concrete	Concrete	Concrete
Description of Tank:	SU (open top sump)	E. of Bldg. 707		
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):				23111
Date of Installation:				25.8' X 12' X 10'
Date of Abandonment:				
Age (Years):				
Disposition:			Old process waste tank currently under RCRA closure	
Waste Streams:		Process waste		Laundry room waste
Reported Releases:	None			
Comments:		Sump in tank vault for T-11		Part B Secondary Containment Ref. 2011

	Reference: (1)	Reference: (6)	Reference: ( )	Reference: ( )
Tanks				

Number of Tanks:	1
Tank Material:	Steel
Description of Tank:	OG

[illegible]

**Reported Releases:**

**Comments:**

Original Process Waste Line  
Data Summary Sheet

<u>Tanks</u>	<u>Reference: (1)</u>	<u>Reference: (6)</u>	<u>Reference: (7)</u>	<u>Reference: ( )</u>
Tank Designation: T-32				
Appendix 1 Map: F-5				
Rocky Flats Number: 121				
SWMU Number: 121				
Building Number: 887				
Number of Tanks:	1			
Tank Material:	Concrete		Concrete	
Description of Tank:	SU			
	(open top sump in basement corner)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):			131160	
Date of Installation:				
Date of Abandonment:	December 1980			
Age (Years):				
Disposition:	Active-converted to the new process waste or the fire water deluge collection system	Converted to new FW system		
Waste Streams:			Lab and laundry waste	
Reported Releases:	None			
Comments:			Part B Secondary Containment	
			Ref. No. 2014	



Tanks

Reference: (1) \_\_\_\_\_

Reference: (5) \_\_\_\_\_

Reference: (6) \_\_\_\_\_

Reference: ( ) \_\_\_\_\_

Number of Tanks:	1
Tank Material:	Stainless steel
Description of Tank:	AG2

Date of Installation:		
Date of Abandonment:	July 1982	July 1982
Age (Years) :		
Disposition:	Removed	Removed

**Reported Releases:**

**Comments:**

Tanks

Reference: (1) \_\_\_\_\_

Reference: (5) \_\_\_\_\_

Reference: (6) \_\_\_\_\_

Reference: ( ) \_\_\_\_\_

Number of Tanks:	2	2
Tank Material:	Stainless steel	Stainless steel
Description of Tank:	AG1	
	(above grade)	

Date of Installation:			
Date of Abandonment:	July 1982	July 1982	1969
Age (Years):	19	19	July 1982
Disposition:	Active-converted to	Active	Converted to new PW

Reported Releases: \_\_\_\_\_

None \_\_\_\_\_

None \_\_\_\_\_

Comments:

Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: ( )	Reference: ( )
Tank Designation: T-35			
Appendix 1 Map: C-4			
Rocky Flats Number: 125			
SWMU Number: 121			
Building Number: 561			
Number of Tanks:	1		
Tank Material:	Concrete		
Description of Tank:	SU		
	(open top sump)		
Tank Diameter (in.):			
Tank Height (ft.):			
Tank Volume (gallons):			
Date of Installation:			
Date of Abandonment:	July 1982		
Age (Years):	19		
Disposition:	Abandoned		
Waste Streams:			
Reported Releases:	None		
Comments:			

Tanks	Reference: (1)	Reference: (6)
	Reference: (1)	Reference: ( )
	Reference: ( )	Reference: ( )

**Reference: ( )**

Number of Tanks:	1
Tank Material:	Stainless steel
Description of Tank:	AG2

Date of Installation:	1968
Date of Abandonment:	1984
Age (Years) :	20
Disposition:	Currently old process waste tank

### Floor drain sump RAD

None

Currently under RCRA

Original Process Waste Line  
Data Summary Sheet

Tanks	Reference: (1)	Reference: (6)	Reference: ( )	Reference: ( )
Tank Designation: T-37				
Appendix 1 Map: B-5				
Rocky Flats Number: 126				
SWMU Number: 121				
Building Number: 771C				
Number of Tanks:	1			
Tank Material:	Concrete			
Description of Tank:	SU			
	(open top sump)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):				
Date of Installation:				
Date of Abandonment:				
Age (Years):				
Disposition:		Old process waste tank currently under closure		
Waste Streams:				
Reported Releases:	None			
Comments:				

Original Process Waste Line  
Data Summary Sheet

<u>Tanks</u>	<u>Reference: (1)</u>	<u>Reference: (6)</u>	<u>Reference: ( )</u>	<u>Reference: ( )</u>
Tank Designation: T-38				
Appendix 1 Map: C-5				
Rocky Flats Number: 127				
SWMU Number: 121				
Building Number: 779				
Number of Tanks:	1			
Tank Material:	UG	Concrete		
Description of Tank:	(underground)			
Tank Diameter (in.):				
Tank Height (ft.):				
Tank Volume (gallons):		1000		
Date of Installation:				
Date of Abandonment:	1982	1982		
Age (Years):				
Disposition:	Active-converted to the new process waste system or the firewater deluge collection system	Converted to new process waste system in 1982		
Waste Streams:				
Reported Releases:	None			
Comments:				

Original Process Waste Line  
Data Summary Sheet

Tanks Reference: (4) Reference: (6) Reference: ( )

Tank Designation: T-39  
Appendix 1 Map: F-5  
Rocky Flats Number: 128-131  
SWMU Number: 121  
Building Number: 881

Number of Tanks: 4  
Tank Material: Stainless steel  
Description of Tank: Located in Room 114A

Tank Diameter (in.):  
Tank Height (ft.):  
Tank Volume (gallons): 250

Date of Installation: 1952  
Date of Abandonment:  
Age (Years): 36  
Disposition: Old process waste tank currently under closure

Waste Streams: 2 tanks for caustics  
2 tanks for HN03 & Be

Reported Releases:

Comments:

APPENDIX 3  
REFERENCE DOCUMENTS



### APPENDIX 3 . Reference Documents

Selected reports cited in the closure plan and in Appendix 2, Original Process Waste Lines Data Summary Sheets, are included in this appendix for reference. The included references are listed below:

CONCEPTUAL DESIGN REPORT, ENVIRONMENTAL IMPROVEMENT PROJECTS, Rockwell International, Rocky Flats Plant, Golden Colorado, December, 1985.

SURVEY OF THE STATUS OF THE EXISTING PROCESS WASTE LINES, Sunday, G., Rockwell International, September, 1976, (unnumbered report).

REPORT OF AN INVESTIGATION ON A RECENT PROCESS WASTE PIPELINE LEAK, Rockwell International, October 24, 1980, ES-376-80-217

UNUSUAL OCCURENCE REPORT - VALVE VAULT #7 OVERFLOW, APRIL 4, 1983, Rockwell International, May 5, 1983, UOR NUMBER RFP 83-2-SAGE 83-1.

A HISTORICAL SUMMATION OF ENVIRONMENTAL INCIDENTS AFFECTING SOILS AT OR NEAR THE U.S. AEC ROCKY FLATS PLANT, Dow Chemical, Undated (approximate date fall 1983), by J.B. Owen and L.M. Steward (Draft).

TANK LIST, Rockwell International, Mr. Bob James, 1988

CONCEPTUAL DESIGN REPORT  
ENVIRONMENTAL IMPROVEMENT PROJECTS  
UNDERGROUND PIPING AND TANK REMOVAL

ROCKY FLATS PLANT  
Golden, Colorado

U.S. DEPARTMENT OF ENERGY  
Albuquerque Operations Office  
Albuquerque, New Mexico

Prepared by

FACILITIES ENGINEERING DEPARTMENT  
Rocky Flats Plant  
North American Space Operations  
Rockwell International  
Authorization 389801

December, 1985

## SECTION 2

### TABLE OF CONTENTS

#### UNDERGROUND PIPING AND TANK REMOVAL

	<u>Page</u>
1. PART 1 - DESIGN CONCEPT	
1.1 GENERAL DESCRIPTION OF THE PROJECT	2-2
1.2 JUSTIFICATION	2-3
1.3 RELATIONSHIP TO OTHER PROJECTS	2-5
1.4 ALTERNATIVES	2-6
1.5 DESIGN CONCEPT	
1.5.1 Project Design Description	2-6
1.5.2 Energy Conservation	2-9
1.5.3 Environmental Considerations	2-9
1.5.4 Facility and Equipment Maintainability Considerations	2-10
1.5.5 Safety Considerations	2-10
1.5.6 Security Requirements	2-11
1.5.7 Outline Specifications and Criteria	2-11
1.5.8 -Site Development Plan Coordination	2-11
1.6 QUALITY ASSURANCE	2-11
1.7 PROJECT EXECUTION	2-11
1.8 SCHEDULE	2-13
1.9 COST ESTIMATE	2-14
1.10 PROCUREMENT ACTION	2-15
1.11 COST AND FUNDING PLAN	2-15
1.12 SUPPORTING APPENDICES	2-15

## UNDERGROUND PIPING AND TANK REMOVAL

### 1 PART 1 - DESIGN CONCEPT

#### 1.1 GENERAL DESCRIPTION OF THE PROJECT:

This project will provide for the removal of contaminated underground piping, storage tanks, surrounding bedding material and underlying contaminated soils from the abandoned process waste system located throughout the Department of Energy's 384 acre Rocky Flats Plant Site, north of Golden, Colorado. Figure 1 is an aerial photo of the Plant, showing production facilities as well as the Great Western Reservoir located east of the Rocky Flats Plant. A recent project provided a new contained, inspectable, and alarmed waste piping system which replaced most of the old network of buried process waste and treatment piping at the Plant. Additional pipes are scheduled to be abandoned before the completion of design on this proposed project. Other lines have been abandoned in place and have remained unused for many years. Removal of these pipes will further eliminate the potential for leaching of contaminants into surrounding soil and ultimately into ground water aquifers. Figure 2 shows the abandoned piping network to be removed, and its distribution throughout the Plant. Also shown are the buildings under which inaccessible piping is located. Approximately 17,000 linear feet of trenching will be required to remove an estimated 20,000 linear feet of buried piping. An additional 7900 linear feet of abandoned building process waste system piping, under concrete floor slabs, is inaccessible and will be flushed and plugged to stabilize contained contaminants. This piping will be abandoned in place until final decommissioning of the facility.

Six process waste storage tanks and surrounding contaminated soil will also be removed. Six other tanks will be decontaminated in-place and used for emergency fire water storage. Figure 3 locates all twelve tanks on the Plant Site and indicates whether the tank is to be removed or decontaminated. The abandoned process waste tanks to be removed or reworked, in priority order, are as follows: (1) Slurry Tank 40 located under the Waste Treatment Building (774); (2) Tanks 66, 67, and 68 located southeast of Building 774; (3) aboveground Tank 207 located south of Building 774; (4) Tank 123 located south of the Production Support Building (441), Area 11, will be removed along with the surrounding soil; (5) four process waste and laundry waste storage tanks located on the north side of the Manufacturing Building (776); and (6) two process and laundry water tanks located north of the Plutonium Recovery Building (771), decontaminated, painted, and used for emergency fire water storage.

Contaminated soils, piping and concrete from removed utilities will be packaged and shipped offsite for storage at the Nevada Test Site or other approved hazardous waste repository. Residual liquids and sludges within the pipes will be removed and processed through existing Liquid Process Waste Treatment Systems located in Building 374 at the Rocky Flats Plant.








FIGURE 1



**ABANDONED PIPING AT ROCKY FLATS PLANT**

**FIGURE 2**



●	TANKS TO BE REMOVED
●	TANKS TO BE TREATED IN PLACE

**ABANDONED TANKS AT ROCKY FLATS PLANT**  
**FIGURE 3**

## 1.2 JUSTIFICATION:

The purpose of this project is to eliminate a potential for a Plant shutdown due to a possible release of radioactive material into adjacent soils or the introduction of volatile organic compounds (V.O.C.) or other hazardous chemicals into the local ground water. Obsolete piping and tanks, which were heavily used for 25 years, are not inspectable and several dozen minor leaks have been documented over the years. Historical records are scarce, however, data indicates a high probability that the following contaminants have been deposited in the piping and tanks: 1) plutonium; 2) uranium; 3) americium; 4) beryllium; 5) nickel; 6) carbon tetrachloride; 7) chromates; and 8) nitrates.

As a conclusion of the documented leaks, it is obvious that contaminants have been deposited outside of the process waste piping in the adjacent bedding soils. The contaminants become an environmental concern in that they are exposed to several modes of mobilization. Downward movement may occur as a result of heavy rainfall soaking into the ground and carrying contaminants downward with it. Annual rains contributing to ground water recharge in the vicinity of the Rocky Flats Plant have been estimated at 20 million gallons. The capillary properties of trench backfill material may draw contaminants up in a manner similar to a sponge. Changes in the level of the ground water table from above the pipe network to below the pipe can cause "flushing" of the contaminants. Horizontal movement might be caused either by the flow of liquid along the outside of any of the Plant's utility piping through porous bedding materials or by the natural flow of the areas ground water.



Figure 4 shows the major geological formations in the area of the Plant Site. The top soil layer is known as the Rocky Flats Alluvium. This soil layer tapers off and ends just east of the Plant proper. The next layer is known as the Arapahoe Aquifer. The Arapahoe Aquifer is relatively porous and is an important water supply for cities and private well owners downstream of the Rocky Flats Plant. If contaminants are allowed to disperse into the Arapahoe Aquifer the resulting plume of hazardous materials could adversely effect use of this important water shed, resulting in civil actions and criminal penalties.

Although the rate of dispersion is dependent on many factors, including the solubility of the contaminant, the permability of the soil and the flow rate of the ground water, dispersion is still a fact. The distance the contaminants have traveled is not yet known. Studies are in progress which will help define the extent of the problem.

Potential contamination of the soil layers and groundwater by the abandoned piping network poses a significant threat to human health and the environment. These risks are critical and should prompt immediate cleanup actions to eliminate the threat.

There are several regulatory concerns discussed in the following paragraphs that also require removal of the abandoned piping and tanks.





## SITE GEOLOGY

FIGURE 4

First, the Plant's National Pollutant Discharge Elimination System (NPDES) permit, which is administered by the EPA is potentially at risk of suspension or revocation. If the permit is revoked the Plant may be required to shutdown until corrective action is taken. The NPDES permit establishes stringent limits on physical/chemical parameters monitored in all releases from the Plant Site. The horizontal movement of contaminants through the Rocky Flats Alluvium could surface as the alluvial soils taper off (refer to figure 3) upstream of the Plant's storm water retention ponds. Surface water could deposit the contaminants in the ponds, contributing to the quantity of hazardous materials retained, and potentially, to a permit violation at any of six EPA monitoring stations located in the same drainage basin. If, for any reason the Rocky Flats Plant does not comply with, or is unable to comply with, daily maximum effluent limitations specified within the permit, it faces consequential EPA actions including penalties and possible revocation of the permit to discharge waters from the ponds. Since the Rocky Flats Plant is required by the permit to "take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance", the Plant may be required to process the water retained within the ponds rather than releasing it. Processing would need to be accomplished in the Liquid Waste Treatment Facility, Building 374. This waste treatment facility was not sized with sufficient surplus capacity to handle the pond water. Therefore, waste generating production processes could have to be curtailed until sufficient drawdown of the ponds occurred to handle anticipated precipitation.

Second, accomplishment of this project may preclude state intervention in Plant operations under the Resource Conservation and Recovery Act (RCRA). RCRA's goal, through State implementation, is to regulate the management of hazardous materials from the time of their generation to the time of their proper disposal. Leakage from the abandoned process waste piping is not in compliance with RCRA's hazardous waste management goals. On November 1, 1985 the Rocky Flats Plant was required to submit a permit application, to the State of Colorado. The abandoned process piping was included as a part of that application, outlining potential concerns. Although the requirements of the State's RCRA program are still evolving during the early stages of implementation, it is almost a certainty that the waste piping will fall under the monitoring requirements of RCRA, Subtitle C. Using a parallel RCRA provision which governs the management of non-radioactive, non-mixed waste known as the Leaking Underground Storage Tank (LUST) program as an indication of the upcoming requirements of Subtitle C, it seems quite likely that the piping will have to be removed or an extensive system of monitoring well stations will have to be established to track the migration of contaminants. Assuming the permit is required to continue operations at the Plant, maintaining compliance with permit requirements is of paramount importance. The permit may be terminated "when a managers treatment, storage or disposal activity poses a threat to human health or the environment". Leaks in the abandoned systems can certainly be interpreted by the jurisdictional agency as posing a "threat to human health or the environment".

Third, removing the specified piping and tanks would prevent a violation of EPA Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) requirements. CERCLA is a law created to provide

liability, compensation, cleanup, and emergency response for hazardous substances released into the environment. Any facility, such as the Rocky Flats Plant, "knowingly releasing any elements, compounds, mixtures, solutions, or substances which present substantial danger to public health and welfare, or the environment", is liable for penalty under this act. If the piping and tanks aren't removed, and are found in violation of CERCLA requirements, (by releasing, or threatening a release of any substance defined as hazardous under Section 101 (14) of Comprehensive Environmental Response, Compensation and Liability Act of 1980) EPA intervention in plant operations may result, until acceptable steps towards compliance are completed (e.g. Oak Ridge, Y-12 Plant).

Fourth, the underground piping and tank removal project has been sighted as a priority action item under the Department of Energy, Albuquerque Operations Office Comprehensive Environmental Assessment and Response Program (CEARP). The objective of CEARP is to utilize the combined forces of the Albuquerque Operations Office, the Area Office, the Prime Operating Contractors, and the Los Alamos National Laboratory in implementing a phased program to identify, assess, and correct current or potential environmental problems.

Finally, removal of the abandoned process waste lines and tanks will conform to draft DOE Order 5480 initiating remedial actions to control migration of hazardous substances, and comply with CERCLA Section 101 (24) defining remedial action as those "consistent with permanent remedy taken, instead of, or in addition to, removal actions in the event of a release or threatened release of hazardous substance into the environment, to prevent or minimize the release of hazardous substances so that they do not migrate to cause substantial danger to present or future public health or welfare or the environment".

The presence of the abandoned system often causes interference with construction efforts. During excavation work, pipes are frequently encountered and/or broken. Due to the known contaminants within the pipe, typical demolition or repair techniques cannot be used. Construction crews are delayed while monitoring and removal/repair efforts are completed. Rocky Flats Plant Waste Management procedures, and Contamination and Exposure Control rules must be followed. Adhering to these guidelines involves substantial costs and delays in otherwise simple construction tasks.

Any delay in approval of funding will result in several adverse impacts upon the project. Although the extent of leaching of contaminants is not documented, considering the types of soil on Plant Site, the assumption that leaching is taking place is reasonable. Since the cost estimate is based on the volume of contaminated pipe and soil to be removed, delays in funding approval will result in additional soils requiring removal and associated increased costs.

In order to satisfy all of the requirements imposed by various regulatory agencies, and to terminate the constant threat to human health and the environment, the underground piping and tanks must be removed.

### 1.3 RELATIONSHIP TO OTHER PROJECTS:

The installation of the new, contained, inspectable piping system resulted in the need for abandonment and subsequent removal of the old system. Additional phases of this project must be completed before other piping, as shown on the drawings (see appendix 1.12), can be declared abandoned. These continuing phases are scheduled to be complete within the proposed construction period of this project.

The Underground Piping and Tank Removal project also shares many characteristics with the Leaking Underground Storage Tanks (LUST) program. The LUST program is a new RCRA provision designed specifically for the control and prevention of leaking underground storage tanks and associated piping. LUST bans the installation of unprotected storage tanks, initiates a tank notification program, sets federal technical standards for all tanks, coordinates federal and state efforts, and provides for federal inspection and enforcement. Tanks containing hazardous waste regulated under the RCRA hazardous waste program Subtitle C, are not covered under LUST. Since the Underground Piping and Tank Removal project is regulated by RCRA Subtitle C, in this case, the LUST program doesn't directly apply. However, the Underground Piping and Tank Removal project closely parallels the requirements in the LUST program, hence assuming compliance with current federal concerns and requirements with respect to contaminated underground storage tanks.

### 1.4 ALTERNATIVES:

There were several alternatives considered for this project. First, the option of removing only those portions of abandoned process waste piping and tanks having the highest hazard potential was considered. However, the remaining piping and tanks would still place the Rocky Flats Plant in noncompliance with State and EPA-CERCLA regulations. Second, draining, flushing, and plugging the entire plant wide abandoned piping network was considered. However, cleaning 20,000 linear feet of process waste piping underground is presently not technically feasible and still would not remove the potential migration of contaminants already outside the pipes. An extensive and costly monitoring system would still be necessary to track the impacts of these hazardous materials on the environment.

### 1.5 DESIGN CONCEPT:

#### 1.5.1 Project Design Description:


Approximately 20,000 linear feet of buried piping, six process waste storage tanks, and associated surrounding bedding material and underlying soils located throughout the Rocky Flats Plant Site will be excavated and removed in the project. Six other process waste storage tanks will be emptied, cleaned, painted and put into service as fire water storage reservoirs. 7900 linear feet of inaccessible piping will also be addressed in this project. Since the piping is inaccessible, (located below building basement floor slabs), it will not be excavated and removed. Rather, it will be cleaned and abandoned in place. Figures 5, 6, and 7 illustrate the methods to be used in accomplishing these tasks.

The buried piping and tanks will be treated in a similar manner. Figures 5 and 6 show, in diagrammatic form, the scope and process proposed to accomplish the project. The appendix to this report contains drawings which more completely describe the scope of the work. It should be noted that the drawings show only the piping to be removed. They do not show other existing utilities which may interfere with removal efforts.

The soil above the piping will be removed by backhoe, while the soil around the pipe will require hand excavation. During removal of the soil, soil and air contamination will be continuously monitored by Health, Safety & Environment (HS&E) personnel. Testing of the soil for volatile organic compounds (V.O.C.) and radioactive material will be accomplished on site using Gas Chromatography (G.C.) and portable Intrinsic Germanium Detectors. The principal hazards to human health anticipated during removal of the pipes and tanks are inhalation of contaminated dust particles and direct contact with contaminated soils and sludge. To prevent airborne dust, all soil will be wetted down with water prior to and during removal operations. Wetting of the soil will be kept to a minimum. Once the exposed soil layer is wet, underlying material will in turn become damp, controlling the propagation of dust from subsequent removal operations. Minimizing the use of water will also reduce the amount of liquid to be pumped from the excavated trench. To control direct contact with contaminants, white suits with respirators, booties, and gloves will be required for all personnel involved in removal activities.

Each branch, or run of pipe between branches, buildings, valve pits, or manholes, will be monitored using Gamma Scan equipment after the soil above the pipe has been removed. Assuming contamination levels do not warrant efforts to prevent a criticality, the pipe will be saw cut within the trench into 3 to 6 foot sections (opening each end), then drained of all liquids contained in the pipe. Dust generated during saw cut operations will be controlled and collected at the source. The opened ends of the pipe section will be wrapped in plastic prior to removal from the trench. The pipe section will be monitored prior to placement in the shipping box to document the quantity of radioactive material being transported offsite. Excavation and removal of each run of drained and wrapped pipe will be accomplished section by section with no more than 10 to 12 feet of trench open at any one time. This will control spreading of contaminants in the event of a sudden thunderstorm and associated downpour.

Soil around the buried pipe will be monitored as previously discussed. In areas where no contamination is detected, only the soil required to remove the pipe will be excavated. However, when contamination is detected, soil will be carefully scraped and broken-up using the backhoe bucket. The soil will be bagged in the trench using a shovel or other appropriate means. Bagging the soil in the trench will further reduce the potential for airborne contaminants. The process of monitoring and further excavation will continue until all "hot" soil in the area has been removed. Bagged soil will be lifted out of the trench and placed directly into boxes for shipment to an approved hazardous waste repository. The contents of each box will be monitored to document the quantity of radioactive material being shipped. The backhoe bucket will be cleaned after each encounter with contaminated soil.



**ABANDONED PIPE REMOVAL**  
**FIGURE 5**




FIGURE 6

Any ground water encountered during excavation will be monitored before it is pumped from the trench. Water which is determined to be uncontaminated ground water will be released into existing storm drainage systems. If the water is found to be contaminated, it will be pumped into geometrically stable tanks (pencil tank) to await further analysis by Criticality Engineering personnel. Assuming low level contamination, the water will be transferred to the new Liquid Process Waste Treatment System (LPWTS) for processing in accordance with established procedures. If contamination thresholds of the LPWTS are exceeded, the water will be cycled within the geometrically stable tank and circulated through filters until acceptable levels have been obtained. Sludge encountered while draining the opened pipe sections will be bagged and placed into approved one-liter containers to be reclaimed or treated for proper disposal. Additional backfill required to replace the soil that is removed and boxed will be composed of impervious clay and obtained from areas outside of the facility.


All boxed materials will be loaded on trucks for shipment to the disposal site. Loads will be secured and covered to prevent spillage during transport. Due to the volume of material to be shipped, it is anticipated that the services of a contract trucking firm will be retained for the duration of the removal effort.

Each tank designated in Figure 2 to be removed will be saw cut or broken into small sections. All material will be boxed for shipment to an approved hazardous waste repository. Contaminated soil adjacent to the tank will be removed as outlined for soil around pipes.

If the soil around each tank, indicated in Figure 2 to be treated in place, is found to be free of contamination, the tank will be reconditioned for emergency fire water storage. The tank will be decontaminated by sand blasting or high pressure scouring, then cleaned and coated with a sealant-type paint. The protective coating will prevent fluid migration into, or out of, the decontaminated tank.

Figure 7 illustrates the proposed method for cleaning approximately 7900 linear feet of inaccessible process waste treatment piping. The piping was historically abandoned underneath basement floor slabs in buildings shown in Figure 2. During the installation of the new contained and inspectable process waste piping network, the old building systems were removed to the basement floor slab. Plugs were forced a short distance down the pipes and the first 8 to 12 inches of pipe was filled with concrete. In order to gain access to flush the abandoned pipe, the concrete plug must be removed. All personnel involved in the removal and flushing process will be protected from exposure to contaminants by wearing white suits with respirators, booties and gloves. Access will be accomplished by saw cutting the area around the plugged drain, then using a jack hammer to remove the concrete floor slab as shown in the upper left diagram of Figure 7. The soil around the drain will be hand excavated. The plugged drain will be cut beyond the seal trap, and removed. All removed soil, concrete and pipe will be assumed contaminated and immediately packaged for disposal at an approved hazardous waste repository.





**INACCESSIBLE PIPE CLEANING**  
**FIGURE 7**

The terminal end of the pipe run, exterior of the building's foundation, will have already been excavated and opened. A 90 degree elbow will be attached to the open end, and directed into a catch basin. The basin will be equipped with special filters and baffles to prevent splashing of any flushed contaminants into the surrounding environment. The catch basin will be sized, proportioned and handled in a manner to assure compliance with Criticality Engineering requirements for geometric stability. A high pressure water nozzle and hose assembly will be fed into the upstream end of the exposed pipe to flush accumulated contaminants out of the pipe and into the catch basin. The nozzle/hose apparatus will be powered by a portable high pressure compressor which can be adequately operated by one individual. The hose will be capable of flushing 100 feet of continuous pipe length. Lengths greater than 100 feet between access points are not anticipated. The flushed contaminants in the catch basin will be monitored by Criticality Engineering personnel. If the contaminants are within acceptable levels, they will be pumped into a portable storage tank and transferred to the facility's Liquid Waste Treatment System for disposal. If the levels are unacceptable, the contaminants will be pumped into geometrically safe tanks for further analysis and determination of proper disposal. After flushing and draining, the pipe run will be capped on both ends. The excavated area around the removed floor drain will be backfilled with fresh material obtained off site. Finally, the backfill area will be capped with concrete to match the existing floor slab level.

All equipment used in the pipes or to collect material from the pipes will be cleaned and handled in accordance with the Rocky Flats Plant Contamination Exposure Control rules.

Concern with regard to Criticality Engineering and the use of geometrically stable containers may be addressed during Title I and II engineering design. The use of special equipment to monitor the level of contamination within the pipes before excavation and cleaning activities commence may show that measures to prevent the accumulation of a critical mass are not needed. If this proves to be the case, significant efforts can be eliminated in the handling of liquid waste encountered during project.

Incidental construction materials excavated during the removal effort (ie: thrust blocks, valve boxes, etc.) will be monitored and removed as necessary. Clean materials will be left in place.

During implementation of the project, as-built drawings will be continuously updated to reflect all work that has been done to the piping network. Noting such items as location of removed pipe, amounts removed, contamination levels remaining in inaccessible pipe, and type of pipe removed will be required as minimum documentation.

#### 1.5.2 Energy Conservation:

An Energy Conservation Analysis is not applicable for this project because the use of conventional construction equipment is required leaving no alternatives open to energy conservation and primarily because it is a demolition project which consumes no energy after its completion.

### 1.5.3 Environmental Considerations:

- 1) No measurable pollution will be created by the work on this project. All activities will be closely monitored by the HS&E Environmental and Radiation Monitoring and Industrial Hygiene Personnel and all contaminated materials encountered in the work will be removed in strict accordance with Rocky Flats Plant Waste Management procedures.
- 2) Trench lengths will be kept to a minimum to prevent spread of contamination due to flooding caused by sudden thunderstorms and associated precipitation.

### 1.5.4 Facility and Equipment Maintainability Considerations:

Trench cuts through roads, drives, sidewalks and fences will be designed and scheduled to permit access throughout the facility at all times. All cuts will be restored to their original condition immediately after the trenches are backfilled.

Equipment required for this project will be standard items that are common in the construction industry. Normal equipment preventative maintenance will be provided throughout the duration of the project. No equipment will be left in place at the completion of the project. Therefore, no ongoing maintenance considerations need to be addressed.

### 1.5.5 Safety Considerations:

Special precaution will be required as outlined in existing Rocky Flats procedures and requirements.

- 1) Pipe removal operations will require HS&E and Tank Surveillance Group monitoring because of the possibility of encountering contamination.
- 2) All personnel working on this project, including those of the Operating Contractor and Construction Contractor, will be fully briefed on HS&E rules and regulations that must be followed to accomplish this project.
- 3) Radiation monitors will be required on a continuous basis to assure conformance with the Rocky Flats Plant Contamination and Exposure Control rules and procedures, and to prescribe the measures necessary to protect health or to maintain contamination control.
- 4) Radioactively contaminated materials will be handled in strict accordance with Rocky Flats Plant Waste Management procedures.
- 5) Excavation for piping and storage tank removal will comply with the Rocky Flats Plant safety regulations and excavation permit procedures. Shoring will be provided to protect personnel

during operations accomplished in the trench.

- 6) A Safety Analysis Report (SAR) is not applicable for this project since no buildings will be constructed as a part of the work. SAR's are typically used to document safety features considered in building designs.

#### 1.5.6 Security Requirements:

The construction of this project will be performed in compliance with the established Rocky Flats Plant security program. All tasks to be accomplished in security exclusion areas will require the work force to have "Q" access authorizations. For work outside the exclusion areas, Contractors will be required to obtain visitor badges for all employees.

When trenches cross under security fences to allow the removal of abandoned piping, temporary fences will be installed around the trenching area. Temporary fences will be removed when the integrity of the original fence is re-established. In similar fashion when any security device is compromised because of construction, temporary backup systems will be implemented for the duration of that phase of the construction effort.

#### 1.5.7 Outline Specifications and Criteria:

The design of this project will conform to the requirements of the Department of Energy's General Design Criteria, DOE Order 6430.1. Other design standards (i.e., the National Electric Code, the Uniform Building Code, etc.) will be used to augment DOE 6430 when necessary.

Basic performance requirements have been discussed throughout Paragraph 1.5: DESIGN CONCEPT of this report.

#### 1.5.8 Site Development Plan Coordination:

There are no site development requirements for this project.

#### 1.6 QUALITY ASSURANCE:

The Quality Assurance (QA) level for this project shall be level I and level II, as defined by the Quality Assurance Plan developed by the Operating Contractor, included in this report as appendix item 1.12.2: Facility Quality Assurance Plan.

#### 1.7 PROJECT EXECUTION:

Titles I, II, and III services will be performed by an A-E firm working under a prime, negotiated fixed-price contract with the U. S. Department of Energy.

Due to the anticipated duration of the project, the amount of work to be performed in exclusion areas and work with contaminated substances, construction will be performed by the onsite Cost-Plus-Fixed-Fee Contractor under the direct inspection and health/physics monitoring of the Operating Contractor.

Construction equipment used on the project will be acquired by the Construction Contractor and will be turned over to the Operating Contractor for decontamination and decommissioning at the end of the project.

Boxes used to ship removed soils, piping, and tanks will be approved shipping containers, purchased by the Construction Contractor throughout the performance of the work.

1.8 SCHEDULE:

PROJECT MASTER SCHEDULE													
ENVIRONMENTAL IMPROVEMENT PROJECTS													
	FY85	FY86	FY87	FY88	FY89	FY90	FY91	FY92	FY93	FY94	FY95	FY96	FY97
<b>PLANNING</b> 1) CONC DESIGN REPORT 2) DESIGN CRITERIA 3) REQ'D FOR APPROVAL 4) DOE APPROVAL													
<b>ENGINEERING &amp; CONSTRUCTION</b> ENGRG GFE PROC (N/A) CONSTR													

**LEGEND**

☐ TITLE I & II ENGR'G, ETC  
☐ TITLE III ENGR'G  
☐ ENGR'G STUDIES  
☐ CONSTRUCTION  
☐ PROCUREMENT

**MERRICK**  
Merrick & Company  
 1000 West 10th Avenue  
 Denver, Colorado 80202  
 303 733 0941

**A ORIGINAL ISSUE**  
DESCRIPTION  
**U.S. DEPARTMENT OF ENERGY**  
**ROCKY PLATS AREA OFFICE**  
**Rockwell International**  
**ROCKY PLATS PLANT**  
**NORTH AMERICAN SPACE OPERATIONS**  
**GOLDEN COLORADO DIST**

**PROJECT MASTER SCHEDULE**  
**UNDERGROUND**  
**PIPING AND TANK**  
**REMOVAL**

**389801**  
CLASS  
JOB NO

**389801**  
CLASS  
JOB NO

# 1.9 COST ESTIMATE:

## 1.9.1 Cost Estimate Summary:

### Underground Piping and Tank Removal.

		Project Costs
Engineering, Design, and Inspection at approximately 3.4% of Project Costs-----		\$ 900,000
Title I-----	\$ 200,000	
Title II-----	\$ 500,000	
Title III-----	\$ 100,000	
Inspection-----	\$ 100,000	
Project Costs-----		\$26,500,000
Improvements to Land-----	0	
Buildings-----	0	
Special Facilities-----	0	
Utilities-----	0	
Project & Construction Management-----	\$ 140,000	
Project Administration---	\$ 140,000	
Security Escort-----	\$ 0	
Decontamination & Decommission-----	26,360,000	
Demolition-----	7,890,000	
Excavation-----	5,940,000	
Packaging and Handling--	8,950,000	
Shipping and Storage----	2,050,000	
Backfill and Improvement		
Repairs-----	1,480,000	
Decontamination-----	50,000	
Standard Equipment-----		\$ 20,000
Radiation Monitoring-----		4,700,000
Contingency Allowance at approximately 26.5% of above costs-----		8,480,000
Total Project Cost-----		\$40,600,000

#### 1.10 PROCUREMENT ACTION:

Major procurement items include contaminated material disposal boxes, contaminated waste disposal transportation, and waste disposal site facilities. The Architect/Engineer will develop waste volume calculations coinciding with the removal schedule to enable the Construction Contractor to arrange for acquisition of the items as they are needed. There is no Government Furnished Equipment (GFE).

#### 1.11 COST AND FUNDING PLAN:

It is anticipated that monies for Title I and II engineering will be obligated in the FY-88 budget year. Title II design efforts will not be complete until late in FY-89. Equipment will be specified and ordered in the budget year, if necessary to meet construction schedules.

Project Administration will start concurrent with Title I design. Actual removal of contaminated piping and tanks will begin at the start of the second quarter in fiscal year 1989. Title III A-E services and construction inspection will be ongoing during the removal work. Completion of as-built drawings and project close out will extend a short time after completion of the removal work, scheduled to end in the third quarter of 1994.

Appropriations of \$1,000,000 in FY' 1988 are required to initiate the design on this project; \$7,000,000 (FY 1989), \$6,600,000 (FY 1990), \$6,600,000 (FY 1991), \$6,600,000 (FY 1992), \$6,600,000 (FY 1993) and \$6,200,000 (FY 1994). Funds for the indicated fiscal years are required for construction, equipment, procurement and inspection activities. (refer to Figure 8 for a cost and funding profile).



**COST AND FUNDING PROFILE**  
Underground Piping and Tank Removal

TBC 40,800 a/  
(Includes Titles I, II and III)

	FY 1988	FY 1989	FY 1990	FY 1991	FY 1992	FY 1993	FY 1994
Titles I and II	700 500	0 200					
	Obligations Costs						
Title III/Insp		200 30	0 40	0 40	0 30	0 30	0 30
	Obligations Costs						
Equipment		20 20					
	Obligations Cost						
Decon/Decom	4,480 4,480	4,440 4,440	4,440 4,440	4,440 4,440	4,440 4,440	4,440 4,440	4,120 4,120
	Obligations Cost						
Const/Admin	20 20	20 20	20 20	20 20	20 20	20 20	20 20
	Obligations Costs						
Monitoring	810 810	800 800	800 800	800 800	800 800	800 800	690 690
	Obligations Cost						
Contingency	280 80	1,470 1,540	1,340 1,300	1,340 1,300	1,340 1,310	1,340 1,310	1,370 1,640
	Obligations Costs						
Rounded Totals	1,000 800	7,000 7,100	6,600 6,600	6,600 6,600	6,600 6,600	6,600 6,600	6,200 6,500
	Obligations Costs						

a/ All tabulated dollar amounts are given in thousands. All costs are escalated using the "Anticipated Economic Escalation Rates for DOE Construction Projects" developed by the Independent Cost Estimating (ICE) staff and updated in August 1985. Engineering design costs are escalated to the midpoint of Title I/II design. Equipment costs are escalated to the date of procurement. Construction costs are escalated to the midpoint of construction.

**FIGURE 8**

1.12 SUPPORTING APPENDICES:

1.12.1 Drawing Lists:

The following drawings are attached:

<u>Sheet</u>	<u>Drawing</u>	<u>Title</u>
<u>Underground Piping and Tank Removal</u>		
1	D-37348-CX1	Index and Title Sheet
2	D-37348-C01	Site Plan
3	D-37348-C02	Piping Partial Abandonment Plan No. 1
4	D-37348-C03	Piping Partial Abandonment Plan No. 2
5	D-37348-C04	Piping Partial Abandonment Plan No. 3
6	D-37348-C05	Piping Partial Abandonment Plan No. 4
7	D-37348-C06	Piping Partial Abandonment Plan No. 5
8	D-37348-C07	Piping Partial Abandonment Plan No. 6
9	D-37348-C08	Piping Partial Abandonment Plan No. 7
10	D-37348-C09	Piping Partial Abandonment Plan No. 8

1.12.2 Facility Quality Assurance Plan:

PROJECT AND AUTHORIZATION NO.: Environmental Improvement Projects No. 389801

1.12.2.1 Quality Assurance Level:

(QAL or QA Level) Assignments and Specific Requirements:

The following items need to be addressed and included with each project:

1.12.2.2 QAL or QA Level Assignments:

Systems conveying/controlling/sensing radioactive materials, environmentally-threatening substances and other hazardous, toxic or life-threatening substances shall be QAL I and QAL II as determined by the Project Engineer.

1.12.2.3 Radiation Contamination and HS&E Documentation

Documentation of the existence and the degree of the encountered contamination shall be included in the project file.

Any documentation generated as a result of instituting the necessary HS&E procedures shall be included in the project file.

1.12.2.4 Disconnects and Tie-Ins:

All service and utility disconnects and tie-ins shall be accomplished during normal working hours to the greatest extent feasible and shall be scheduled to minimize downtime and interruption of other facilities. It shall be necessary that the Construction Contractor schedule his work with the Contracting Officer (assisted by the Operating Contractor's, Construction Management (CM) Group) prior to the beginning of demolition and construction work.

1.12.2.5 Seismic:

New equipment shall be designed and documented for appropriate seismic forces specified in Rocky Flats Standard SC-106 and FE Manual 014.

Pipe supports shall be designed and documented for seismic forces.

1.12.2.6 Welding:

All welding for these projects shall be performed by welders who have been certified to the approved qualification procedures for the metals and plastics to be welded.

Documented Welding Procedures and Welding Qualification Records shall be submitted to the Contracting Officer for approval prior to the start of any welding.

#### 1.12.2.7 Component Checkout (CC) and System Operating (SO) Tests:

A Component Checkout test checklist and test procedure shall be prepared and included with the specifications. The CC tests shall be performed by the Construction Contractor. The CC tests shall be completed before "Beneficial Occupancy." System acceptance shall be based on SO test procedures.

#### 1.12.2.8 Material and Equipment Certification:

Mill test reports (MTRs) shall be required and MTR traceability is required on pipe fittings, valves and similar pressure-containing material. Traceability shall be 100 percent on all QAL I and QAL II components and material.

Certification documentation from the manufacturer showing that purchased equipment meets the specification requirements shall be supplied to the Operating Contractor prior to final acceptance.

#### 1.12.2.9 Receiving Inspection and Procurement:

A receiving inspection shall be required for all Government Furnished Equipment (GFE) and Contractor Furnished Equipment (CFE). This inspection shall comply with the requirements of the Receiving Inspection Procedure contained in the Quality Program Procedure Manual, Procedure Q1407. Suitable inspection checklists shall be available for use as part of the receiving inspection/procurement process on both GFE and CFE. Proper sign-offs by the responsible personnel shall be affixed and the inspection reports then filed in the project file. The specifications shall address receiving inspection.

Proper documentation shall be provided on the inspection of certifications, mill or material test reports, etc., during the receiving inspection. Heat numbers shall be verified as well as any other material identification documents.

#### 1.12.2.10 Inspection and Coordination:

Construction coordination and inspection by CM shall be required on these projects, and shall comply with the requirements set forth in Section V of Procedures - Facilities Engineering. The specification shall address this activity.

#### 1.12.2.11 Configuration Control:

Some systems indicated herein should be under configuration control after final occupancy has been established.

#### 1.12.2.12 Project Status Reviews:

Review meeting notes shall be written and distributed to those involved. Such notes shall be used for documentation of important matters and decisions. This form of communication and information is considered vital to control the design, quality and safety aspects. This is considered good quality assurance. All meetings should be documented.

#### 1.12.2.13 Flow Diagramming for Quality:

A critical path flow diagram indicating procurement, receiving inspection, certification review, warehousing and other vital processes/procedures to prove reliability claims and control of quality is recommended.

#### 1.12.2.14 NDT and Pressure Tests:

Piping shall be hydrotested per SP-201 which should include utility, process and similar systems.

Pipe welds shall be NDT tested for discontinuities with liquid penetrant inspection (PT) to prove weld quality unless radiographed for QALs I and II.

#### 1.12.2.15 As-Builts:

After job completion, drawings shall be updated to "AS-BUILT" conditions and should be maintained for the life of the systems/facilities.

#### 1.12.2.16 Miscellaneous:

"Letters of Compliance" or "Certification of Compliance" should not be considered an alternate for mill or material test reports where applicable.

Defined life on instrument controls and major equipment items should be included.

Overall, the Facilities Quality Assurance Program Manual applies.

Pumps shall have defined design life with pump curve certification.

The information contained herein contains the quality assurance requirements for the projects. These requirements should be considered as a minimum. Upgrading of these requirements may be directed at any time.

1.12.3 Cost Breakdown: Underground Piping and Tank Removal

<u>Line Item Costs</u>	<u>Break Down (x 1,000)</u>	<u>Unit Cost (x 1,000)</u>	<u>Item Cost (x 1,000)</u>	<u>Total Cost a/ b/ (x 1,000)</u>
a. Engineering, Design, and a\ Inspection at approximately 3.4% of Project Costs, Item b.				\$ 900
b. Project Costs				26,500
(1) Improvements to Land			\$ 0	
(2) Buildings			0	
(3) Special Facilities			0	
(4) Utilities			0	
(5) Project and Construction Management			140	
Project Administration		\$ 140		
Security Escort		0		
(6) Decontamination and Decommission			26,360	
Demolition - Pipe Removal		7,890		
Material	\$ 0			
Labor	5,460			
Equipment	10			
Escalation	2,420			
Excavation		5,940		
Material	0			
Labor	4,090			
Equipment	30			
Escalation	1,820			

<u>Line Item Costs</u>	<u>Break Down (x 1,000)</u>	<u>Unit Cost (x 1,000)</u>	<u>Item Cost (x 1,000)</u>	<u>Total Cost a/ b/ (x 1,000)</u>
Packaging and Handling		\$ 8,950		
Material	\$ 5,400			
Labor	810			
Equipment	0			
Escalation	2,740			
Shipping and Storage		2,050		
Material	10			
Labor	10			
Equipment	1,400			
Escalation	630			
Backfill and Improve- ment Repairs		1,480		
Material	970			
Labor	20			
Equipment	30			
Escalation	460			
Decontamination - Equipment		50		
Material	0			
Labor	30			
Equipment	0			
Escalation	20			
c. Standard Equipment				\$ 20
d. Radiation Monitoring				<u>4,700</u>
Subtotal				\$32,120
e. Contingency Allowance at approximately 26.5% of above				<u>8,480</u>
Total Project Cost b/				\$40,600

a/ Estimate based on 100% complete conceptual design.

b/ Costs were escalated using the "Anticipated Economic Escalation Rates for DOE Construction Projects" developed by the independent cost estimating staff. Engineering and design costs were escalated to the midpoint of Title I/II design. Equipment costs were escalated to the order date. Construction costs were escalated to the midpoint of construction.

~~4156~~ 126

SURVEY OF THE  
STATUS OF THE EXISTING  
PROCESS WASTE LINES

By  
Ginger Sunday

Prepared for  
Rockwell International  
Atomics International Division  
Rocky Flats Plant  
Golden, Colorado

September 1, 1976

REVIEWED FOR CLASSIFICATION

By *F J TRAPP MGR P.I*

Date *12-8-76* . . . . .



## TABLE OF CONTENTS

	<u>PAGE</u>
I INTRODUCTION	I-1
II. SUMMARY	II-1
III PROCESS WASTE STREAMS	III-1
IV PROCESS WASTE TANKS	IV-1
V PONDS	V-1
VI. PROCESS WASTE LINES	VI-1
VII APPENDICES	
1A - LEAKS AND REPAIRS	1-A-1
1B - LEAKS AND REPAIRS - 700 AREA	1-B-1
2 - PROCESS WASTE SUMMARY	2-1
3 - SOIL SAMPLE RESULTS	3-1
4 - PROCESS WASTE LINES - DRAWINGS	4-1
5 - LIBRARY SEARCH - METHODS OF PIPE CLEANING	5-1
BIBLIOGRAPHY	1
REFERENCE DRAWINGS	11

## I. INTRODUCTION

Recent changes of philosophy on the subject of environmental control at the Rocky Flats plant have led to changes in the handling of process waste. In the past, leak detection in pipelines has been extremely difficult or inaccurate, delaying necessary repairs. In conjunction with the construction of a new aqueous waste treatment plant (Building 374), a new process waste line has been installed which is doubly-contained, providing a secondary barrier to contain leaks. This new system is also completely inspectable.

Rather than simply abandoning the old lines, it becomes necessary to concern ourselves with the condition of the original process waste collection system. These lines are not only uninspectable, but have been in heavy use, in part, for 25 years and have required numerous repairs and modifications in that time. It is possible that some portions of these lines may present a residual hazard after being placed in idle status. Varying conditions may require more extensive actions than simply flushing and sealing the lines. In the extreme, filling or complete removal may be necessary.

In response to a request made by J. A. Watt, ERDA-RFAO, in the fall of 1975, an outline was initiated by B. L. Kelchner of Waste Processing to define the data needed to analyze the problem.

The following engineering study is a collection of information concerning the existing process waste collection system which will be removed from service and ultimately abandoned when the new waste treatment facility is operative. In order to assist in making a

judgement concerning the disposition of these lines, data has been tabulated that includes: line sizes, location, age, materials of construction, operating data, and unusual operating incidents. To supplement the criteria concerning possible environmental hazards, soil samples were taken and analyzed in areas of known leaks and repairs. The final step in the study was a library search for new developments in the area of pipe cleaning. This study includes lines buried in the field and waste collection tanks, both inside and out of the buildings.

## II. SUMMARY

The purpose of this study was to gather pertinent data for use by qualified consultants rather than to state conclusively the final disposition of these lines. However, a few general observations are the natural consequence of any exposure to analytical data. As the study progressed, some conclusions became obvious which might be helpful in minimizing the complexity of the problem.

One major factor in considering abandonment of any of the lines is that several times in the past, leaks have been caused by equipment accidentally breaking into a line. It is likely that, once the lines are no longer in use, consciousness of their existence will become increasingly obscure. Filling of these abandoned lines with some inert material would confine contaminants if future construction activities should damage the lines.

One example where removal would be both practical and desirable is the old saran-lined pipe that runs between 881 and 707. The line was installed in 1952 and has had heavy usage and numerous repairs since that time. Since the line is doubly-contained, removal of the 3" inner saran-lined steel pipe could be accomplished without excavation by pulling the line through the 10" vitrified clay pipe casing. Waste treatment personnel, under the direction of M. E. Maas have already successfully removed 120' of the line in this manner. Because the line was, at that time, the only means of transferring process waste from the south side of the plant to 774, no attempt was made to remove the longer pieces of line. Since the line was abandoned in 1975, this method would be an economical, expedient way to eliminate one area of concern.

An area where a strong argument could be made for abandonment in-place is the line running east-west between 444 and 883. Although the line is old and pipe material is cast iron, it has carried only very small amounts of depleted uranium and nitrates. A soil sample at the location of the only known break in the line was found to contain 62 ppm  $\text{NO}_3$ . Plutonium 239 is near background level at this same location.

Soil samples were obtained from areas known to be contaminated as a result of leaks. The soil sample results indicate that pipeline removal would not require removal of surrounding soil. Assuming that these soil sample results are typical, they do not by themselves constitute a basis for removal of the lines. It should be noted that the samples taken from the 700 Area (samples 4-9) are above plutonium background level which is approximately 0.03 d/m/g. The two taken in the south part of the plant (samples 1-2) are closer to background. An expanded soil sampling program would define the boundaries within which contamination levels are higher than normal.\*

Although there are no established levels for nitrates in soil, the sample results are not high. They do verify that there has been leakage \*

---

\*Evaluation of the soil sample analysis was made with the help and direction of Merlyn R. Boss and Daryl D. Hornbacher of Health and Environmental Science

Disposition of lines in the 700 Area will require careful consideration. Decisions should be made on a case by case basis. After the process waste lines are no longer in use, samples taken from the inside of the lines would be very helpful in gauging any residual hazards. The description of these lines contained in the process waste lines section of this report and the process waste summary should be helpful in determining the condition of these lines.

### III. PROCESS WASTE STREAMS

These streams originate from production and research activities and laboratory, laundry, decontamination, and janitorial operations. Aqueous chemical and radioactive waste are generated in Buildings 123, 444, 707, 771, 776, 779, 865, 881, 883, and 889. Each tank of waste is sampled before shipment and, depending on the level of radioactivity and chemical composition, can be routed to Building 774 for treatment, Pond B-2 on South Walnut Creek, or the solar evaporation ponds, Facility 207. Average volume and level of contamination have varied over the years as various building operations have been changed. Usage, in general, has been high and both lines and tanks normally contain liquids. Monthly averages covering all years the plant has been in operation are listed in Appendix 2 for each building.

#### IV. PROCESS WASTE HOLDING TANKS

To be consistent with the current philosophy on environmental protection at the Rocky Flats plant, process waste holding tanks must be made double-contained and inspectable. Some have already been modified by placing a new tank inside the old one. Others are under authorization as part of construction projects to be made doubly contained.

In 1971, several sample wells were drilled around the buried tanks so that they could be regularly monitored for releases to the environment. Twice a year, liquid samples are taken from the sample wells and they are analyzed for plutonium, americium, uranium, and nitrates by the Health and Environmental Science Laboratories.

In assessing any potential environmental hazard, Appendix 2 will be helpful. The highest level of contamination and usage history of each building's process waste is listed. This is, of course, the same waste that has been carried by the process waste lines. Tank material, capacity and age are tabulated in the table included in this section of the study.



# PROCESS WASTE HOLDING TANKS

Bldg	Location, Depth	Name/No	NI (2)	Capacity (gallons)	Dimensions (feet)	Material	Age (years)	No /Mo (1)	Notes
889	In pit W of bldg , 15' deep	/2	x	1,000	5x7x4 25	concrete with carbollene lining	10	3 in 6 mos	to be made double contained under Auth 385050
776	N of 776 (N 37080 E 20911 5), 26'	A88/2 C&D/2	x	22,500 4,500	25x15x10 5x15x10	concrete	20	5	
771	N of NE corner of bldg , 18'	A88/2	x	20,000	22x15 5x7 5	concrete	23	2	
707	E side of 707 (N 37080 E 20911), 20'	2		3,000		fiberglass	2	5	placed inside old concrete tanks
865	located on the first level, Column C-4, 15'	2	x	3,000		concrete	6	6	to be double contained, Auth 385050
779	basement level, Column C-5, 10'	1A&1B/2 2A&2B/2	x	8,000 1,000	22x9x7.5 5x9x7 5	concrete	11	1	to be double contained, Auth 375030
444	basement level, Col F, E-6, 7	T2-T3/2 2	x	3,500 500	7 5x12 5	steel	23	17	to be made double contained, Auth 385050
122	SE of bldg , underground	1	x	800		concrete with floor drain	23		
887	lower level	7		2,700		stainless steel	23	7	
881	Room 114A	4		250		stainless steel	23		
559	In holding pit SE of bldg	1&2/2		1,800	7x9	stainless steel	23	7	2 for caustics 2 for HNO <sub>3</sub> & Be
		3/1		500	3 5x8	stainless steel	10	2	
883	basement - Room 1	2		1,000		stainless steel	10		
		2		1,000		welded steel		3	
		1		750		welded stainless steel			
886	18 feet W of bldg	1		300		steel			aboveground, transported by portable tanks

PROCESS WASTE HOLDING TANKS (continued)

Bldg	Location, Depth	Name/No	NI (2)	Capacity (gallons)	Dimensions (feet)	Material	Age (years)	No./Mo (1)	Notes
441	S of bldg (holds 123 process waste), 6'8"	1	x	3,000	13 25x13		23	7	
774		2	x	14,000				30	
		1	x	30,000					

(1) Present number of tank shipments per month Based on first five months of 1976

(2) Not Inspectable

## V. PONDS

Low-level waste from the buildings and filtrate from the Building 774 second stage operations are sent either to the solar evaporation ponds, 207-A, B, C or discharged off-site to Pond B-2 on South Walnut Creek.

In the Process Waste Summary, Appendix 2, 207-A, B are referred to as 2-A and 2-B, respectively. These were the original terms used to identify these ponds.

Of the ponds on South Walnut Creek, only one is used for process waste. It was previously the Building 995 Pond (later called Pond 3). It is now Pond B-2.

<u>Solar Evaporation Ponds</u>	<u>Dimensions (ft)</u>	<u>Capacity (gal)</u>
207-A	521 x 250	Operational - 5,112,000 Overflow - 6,155,000
207-C	248 x 168	Operational - 1,286,000 Overflow - 1,673,000
207 B-1	*250 x 181	Operational - 1,583,000 Overflow - 2,188,000
B-2	*250 x 181	Operational - 1,705,000 Overflow - 2,310,000
B-3	*250 x 181	Operational - 1,710,000 Overflow - 2,315,000

\*Depths vary

<u>S Walnut Creek Ponds</u>	<u>Type of Waste</u>	<u>Capacity (gal)</u>
B-2	Laundry Waste	$1.9 \times 10^6$
B-1	Sanitary Waste	$0.8 \times 10^6$
B-3	Sanitary Waste	$0.9 \times 10^6$
B-4	Sanitary Waste	$0.6 \times 10^6$

## VI PROCESS WASTE LINES

The process waste lines presently in use vary greatly in age, material and usage history. Consequently, any decision concerning their ultimate disposal will vary from line to line.

In general, the system is gravity-flow and vented so the lines have not been subject to any pressure. The line coming from Building 444 to Building 883 is pumped but is essentially at atmospheric pressure due to its large 4" diameter and the low volume of waste carried from this area. The line coming from 881 north to 883 is also pumped but pressure should not exceed about 10 psi.

The only thermally hot waste coming through the lines has been steam condensate from Building 881. Although the temperature should not have affected the saran-lined steel used in this line, the steam condensate is believed to be the probable cause of numerous leaks at the 45° elbows of the lines. The steam caused expansion in the flanges which allowed acids in the waste to corrode the outer mild steel. (For more information, see Appendix 1-A 2.)

The following table is a collection of data concerning the process waste lines which will be superseded by the new, double-contained system. Line sizes, length, age, and materials of construction have been tabulated. The operating data and leak information are contained in the appendices. The last column of the table refers to the appendix which contains information pertinent to each line.

# OUTSIDE PROCESS WASTE PIPES

<u>General Location</u>	<u>Pipe Material</u>	<u>Pipe dia (inches)</u>	<u>Total Feet</u>	<u>Year Installed</u>	<u>Usage, Leaks, and Repairs</u>
See Appendix 4-Dwg 15507-1					
400 Area					
exits S side of 123, ends at E18623 5	polyethylene in steel	3 inside 4	120	1968	see Appendix 2, bldg 123
begins E18623 5, enters 441 at N36081 8	vitrified clay	4	162	1952	see Appendix 2, Bldg. 123
begins 441 tank, connects 441, 444 & 883 (N36056)	cast iron	4	1,193	1952	see Appendix 2, Bldgs 123, 441, & 444, see Appendix 1A, 111, & IV
800 Area					
connects 881 to valve pit W of 884 (N36232 E20560)	steel	3	865	1957	see Appendix 2, Bldg 881
connects 883 to valve pit W of 884	steel	3	504	1957	see Appendix 2, Bldg 883
exits S side of 881, connects 81 & 89	stainless steel	2	78	1952	see Appendix 4, Dwg. 15507-1 Detail 1
exits S side of 881, connects 81 & 89	stainless steel	3	140	1952	and Appendix 2 Bldg 881
exits S side of 881, connects 81 & 89	stainless steel	4	158	1952	
connects 865, 889 to N36191, E20560	stainless steel	3	550	1968	see Appendix 2, Bldg. 865 & 889 see Appendix 4 Dwg 15507-1 Detail 2
Main north-south line (E20560)					see Appendix 2, Bldgs 881, 865 889, 883, 441, 444, & 123 see Appendix 1A-1 see Appendix 1A-1
begins valve pit W of 884, to just N of Central Avenue	new FG inside old VCP	3 inside 10	165	FG 1975 VCP 1952	
N of Central to valve pit W of 707 (N36910)	3" saran-lined steel in 10' VCP		573	1952	
N of Central to valve pit W of 707 (N26910)	3" ribbed hose in 4" FG reinforced epoxy		523	1975	
begins valve pit W of 707, ends H707 (E21058)	stainless steel	3	878	1968	see Appendix 2, Bldgs 123, 444, 559, 707, 865, 889, 881, & 883 see Appendix 2, Bldgs 441, 444, 123, 881, 883 (abandoned 1968), and see Appendix 1A, 11
diagonal (N36910 E20560 to N37370 E21058) then N to N36581 E21058	3' saran-lined steel in 10" VCP		942	1952	

# OUTSIDE PROCESS WASTE PIPES (continued)

General Location	Pipe Material	Pipe dia (inches)	Total Feet	Year Installed	Usage, Leaks, and Repairs
559 Area exits E side of 561 (N37072), connects to main line (E20560) exits SE side of 559 (N37124 E20370) enters NE 559 (N37216 E20406) exits S of 559 (E20278), enters W of 561 (N37071 5)	polyvinyl chloride glass rigid teflon	3 4 2 3/4	170 135 150	1968 1968 1968	see Appendix 2, Bldg 559 see Appendix 2, Bldg 559 see Appendix 2, Bldg 559
See Appendix 4 Dwg 15507-2					
700 Area H 707 (N37292 E21058) to N 777 (N37681 E20990)	stainless steel	3	455	1968	see Appendix 2, Bldgs 123, 444, 559, 707, 865, 883, 889, & 881
H 777 to Bldg 774 (enters W side at N38025)	stainless steel	3	336	1952	see Appendix 2 all bldgs except 771
E 707 (N37132) to N 707 (N37284)	stainless steel	3	186	1968	see Appendix 2, Bldg 707
exits H 771 (E20588) to 771 tanks (N38207)	cast iron	6	85	1966	see Appendix 2, Bldg 771
771 tanks to reducer N of 774	cast iron	6	180	1966	see Appendix 2, Bldg 771 & Appendix 1B & 111
reducer H of 774 to valve pit N of tank 207 (N37820)	stainless steel	3	516	1972	see Appendix 2, Bldg 771 & Appendix 1B & 111
See Appendix 4 Dwg 15507-2					
700 Area 774 to H37931 E21077	stainless steel	two 3" pipes	185	1968	see Appendix 2 treated waste from 774 to ponds
N37931 E21077 to valve pit N of tank 207	stainless steel	two 3" pipes	111	1972	see Appendix 1B-1
tunnel between 771 & 774	plastic hoses	three 1" pipes two 2" pipes			see Appendix 2, 771 into 774 first stage
exits H 776 (E20769 5) to 776 tanks	cast iron	6	72	1957	see Appendix 2, Bldg 776
776 tanks to Ponds (N37715 3)	steel	3	1,055	1957	
776 tanks to valve pit N of 207 (N37820)	stainless steel	3	402	1957	see Appendix 2, Bldg 776
exits W side 779 (N37552) to valve pit H 77 (N37715 E21056)	stainless steel	3	164	1957	see Appendix 2, Bldg 779
779 to valve pit N of 777	stainless steel	3	44	1957	
W 771 (N3791) to 771 tanks (N38207)	fiberglass	10	395	1969	see Appendix 2, Bldg 771
lines around tank 207	steel	3	230	1965	
	vitirified clay pipe	4	153	1952	
	vitirified clay pipe	6		1966	

OUTSIDE PROCESS WASTE PIPES (continued)

<u>General Location</u>	<u>Pipe Material</u>	<u>Pipe dia (inches)</u>	<u>Total Feet</u>	<u>Year Installed</u>	<u>Usage, Leaks, and Repairs</u>
<u>Ponds</u>					
exits E 774 (N38075) to Pond 207-A valve pit NE of tank 207 to off site (E23700)	polyvinyl chloride vitrified clay pipe	two 1 5" 10	-1,500 - 660		see Appendix 2
from N37335 E22652 to N37287 E23239	vitrified clay pipe vitrified clay pipe	6 6	-2,190 - 590		abandoned see Appendix 2, Bldg 774 to Bldg 95 ponds
from valve pit NE of tank 207 (N37713 E21050) to ponds 207 A & B	steel	3	-1,190		
connects 207 & 207 A	cast iron	8	85		

## VII. APPENDICES

Appendix 1-A and 1-B describe leaks and repairs. 1-A is crossreferenced to Drawing 15507-4 in Appendix 4. 1-B is crossreferenced to Drawing 15507-5 in Appendix 4. Appendix 2 is a summary of the wastes carried by the lines over the years. Appendix 3 contains the results of eight soil samples taken in areas of possible contamination from leaks. These areas are also marked on the drawings in Appendix 4. The first columns of the Process Waste Lines Table locate the piece of line being described. Reference points and coordinates refer to the drawings in Appendix 4.



## APPENDIX 1-A - LEAKS AND REPAIRS

(Notes on Drawing 15507-4)

- A. The line between the 884 valve pit and the valve pit east of Building 557 (guard station) was found to have a leak rate of 2.7 gal/hr at 20 psig (65 gal/day) in May 1971 by International Leak Detection Services in Houston, Texas. This line (E20560 from N36232 to N36910) is 3" mild steel lined with saran and encased in a 10" vitrified clay pipe. The line was installed in 1952 and abandoned in 1975. The remaining piece of line (going from the valve pit of N36910 to the valve pit east of Building 557) is 3" stainless steel and was placed in 1968. The first 120' north of the 884 valve pit was repaired as follows: the 10" VCP containment was kept in place but the inner 3" saran-lined pipe was replaced with a 3" ribbed hose. Just north of Central Avenue (even with the concrete anchor for the power pole) a new double-contained line (3" ribbed hose in 4" FG-reinforced epoxy) jogs to the west of the old line about 4 ft. and continues north, parallel to the abandoned 3" saran-lined pipe and 10" VCP containment. A soil sample and clay tile pipe sample taken in May 1972 (Report PRD 950463-107) of the abandoned line showed no measurable amount of contamination and a visual inspection showed only surface rust. Some bolts at the flanges were tested and found to be in good condition. A soil sample was taken for this study at the 884 valve pit (see Appendix 3 for a sketch). Analysis results showed  $\text{Pu}^{239}$  - 0.049 d/m/g and  $\text{NO}_3$  - 110 ppm.
- B. There is an abandoned line from the valve pit at N36910 E20560 (West of 707) running at a diagonal to the northeast and ending at N37370 E20990. The line is 3" saran-lined steel in 10" vitrified clay containment.

A large portion of it lies under Building 707 which was built after the line was abandoned in 1968. Substantial leaks occurred at the elbow connections during its use due to expansion from steam condensate from Building 881. Leaks of acidic process waste resulted in corrosion of the outside mild steel. The abandoned line continues north from the joint at N37370 E20990 and is buried beneath Building 777. It is probable that portions of all this line were removed as excavation for 707 and 777 made necessary. One bad leak occurred in December of 1958 when the south 45° elbow broke and process waste followed the containment pipe to the north 45° elbow and leaked into a ditch. From Building 881, 2,700 gallons of lab waste (radioactivity .51 ppm enriched uranium, pH 5.6, NO<sub>3</sub> 120 ppm) and 2,700 gallons of laundry waste (radioactivity .51 ppm enriched uranium, pH 9.4) was sent and 1,350 gallons were received in 774. The elbow was repaired and the line remained in use for another 10 years. A soil sample taken for this study at the valve pit west of 707 (see Appendix 3, soil sample #4) showed Pu<sup>239</sup> - 0.145 d/m/g and NO<sub>3</sub> - 54 ppm.

- C The east-west line running at N36030 and connecting Buildings 122, 123, and 444 to a junction with the north-south line west of Building 883 is the original 4" cast iron pipe with bell-and-spigot construction and is about 23 years old. Significant leaks were found in the joints by International Leak Detection Service in 1971. Leak rate was determined to be 2.5 gal/hr at 37 psig. The line itself seemed to be intact and the joints were repacked to stop further leakage. The line was tested under pressure greater than that normally found under ordinary working conditions. Report PRD 950463-107, May 1972 by Hornbacher and Lott describes the problem and repair in detail.

- D. A break in the line close to the driveway of Building 663 occurred around 1960 to 1962. The line chipped as trucks backed over the shallow cover and the leak was detected as water bubbled to the ground surface. A small portion of the line was replaced and no subsequent leaks were reported.
- E. A piece of line right under the outside perimeter road (this line goes off-site to Pond B-2) was broken by a cable-laying operation and recovered. The leak was detected by excess water in the culvert and subsequently repaired by replacing a piece of the line.

## APPENDIX 1-B - LEAKS AND REPAIRS

(Notes on Drawing 15507-5)

- A. The two parallel lines running between 774 and the valve pit north of tank 207 were found to be leaking badly in the old cast iron sections. The 3" line had a leak rate of 14 gal/hr at 20 psig. The parallel 4" line had a leak rate of 45 gal/hr. Both were replaced in April 1972. Soil sample #8 taken east of the valve pit north of tank 207 showed  $\text{Pu}^{239}$  - 1.83 d/m/g,  $\text{NO}_3$  - 76 ppm.
- B. The valves on the north of 777 (N37715 E21055) were found to be leaking in 1971 at a rate of 25 gal/hr at 20 psig. A valve pit was constructed in May 1974. Soil sample #6 showed  $\text{Pu}^{239}$  - 0.05 d/m/g,  $\text{NO}_3$  - 105 ppm.
- North of the new waste packaging facility joining 771 and 774, a leak rate of 15 gal/hr at 20 psig at the junction of a 6" cast iron with a 3" steel line was found in 1971 by International Leak Detection Services. The 3" steel has since been replaced with a 3" stainless steel line when the waste packaging facility was added in 1972. Soil sample #9 was analyzed to contain  $\text{Pu}^{239}$  - 3.385 d/m/g and  $\text{NO}_3$  - 44 ppm.

## APPENDIX 2 - PROCESS WASTE SUMMARY

These data were taken from the records of shipments to and from Building 774 kept by M. E. Maas, Waste Treatment Supervisor. The records were summarized to find the highest concentrations of radioactivity and chemical contamination that have been present in the process waste lines and tanks. Because of the huge amount of data and time limitations, approximately one-fourth of the data was selected to be tabulated. In most cases, there was little variation in monthly volumes and three months were picked at random (usually January, May, and October). When a marked change was noticed in usage, the month with the highest total volume was used. At times, it was possible to scan the entire year and total the volume. Those places have been marked as yearly totals.

Units and notation are the same as in the original records. The notes which clarify which substances are referred to in the activity column were given by Bob Carpenter, Assistant Manager of General Labs

## APPENDIX 2 - PROCESS WASTE SUMMARY

<u>Buildings - Waste into 2nd Stage of 774</u>	<u>Page</u>
441	2-3
883	2-3
881	2-3, 2-4, 2-5
444	2-5, 2-6
559	2-6
889	2-7
122 -	2-7
123	2-7
886	2-7
776	2-7
771	2-8
707-779	2-8
Treated Waste from 774 to Ponds	2-9
Raw Waste to Ponds	2-11
Building 771 - Waste into 1st Stage of 774 - see Footnote - Page 2-7	

PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774

Bldg	General Types and Levels of Contamination	Year	Monthly Average Volume	Highest Activity	NO <sub>3</sub> (ppm)	CR <sup>235</sup> (ppm)	pH	Other
441	Lab waste - low level activity is total uranium with 98% depleted uranium	1953	31,300	3 2 ppm				
		1954	17,800	4,600 d/m/l				
		1955	14,900	01 gu/l	1,066			
		1956	12,600					
		1957	9 600					
		1958	16,000					
		1959	16,530					
		1960	27,900					
		1961	30,300					
		1962	30,500					
		1963	39,700					
		1964	17,600					
		1965	21,800					
		1966	27,200					
883	Converted to office building in 1967							
	Janitor water and process waste	1959	3,300	3 3 gT/l	146 ml			Th<100 ppm
	Total gallons for year	1960	2,600	3 9 gT/l				
	Total gallons for year	1961	400	1 02 gT/l				
	depleted uranium	1973	2,800	46 x 10 <sup>6</sup> d/m/l	5,800	30 9	4-9 8	Be 1 ppm
		1974	5,100	33 x 10 <sup>6</sup> d/m/l	182,000			
		1975	3,200	30 x 10 <sup>6</sup> d/m/l			<1-13 0	U238-4600 ppm
		1976	950	1 4 x 10 <sup>6</sup> d/m/l				6-9.4
881	Laundry waste, process & lab waste, caustic	1953	52,430	060 ppm			1 0-2 5	1 28,700
		1954	43,580	34 ppm	103,750		2 0-11 5	5 126,000
	95% enriched uranium U-235	1955	69,960	1 22 ppm	440,000		5 3-12 0	0 (r 20

PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774 (continued)

Bldg	General Types and Levels of Contamination	Year	Monthly Average Volume	Highest Activity	NO <sub>3</sub> (ppm)	CR <sup>+</sup> 6 (ppm)	pH	Other
	This is the only building that sent some	1956	74,230	48 ppm	409,000		0-12	
		1957	16,800	4 9 ppm	20,500		2 5-11 7	F 20,200 I 14,000
	that sent some thermally hot waste through	1958	79,230	76 ppm	900		3 1-12 3	Cr <sup>+</sup> 6 <1
	the lines in the form of steam condensate	1959	27,130	14 0 ppm			6 5-11 1	
		1960	82,100	19 ppm	<100		3 2-12 0	
		1961	138,800	1 6 ppm	860		3 0-12 0	
		1962	60,830	58 ppm	350		2 2-12 2	
		1963	123,600	1 4 ppm	400		2 4-12 0	
		1964	129,400	1 2 ppm	545		2 4-12 3	
		1965	90,920	3 ppm	435		3 1-11 9	
		1966	64,800	1 8 ppm	19,000		1 3-6 8	
		1967	54,900	1 3 ppm	17		2 4-9 4	
		1968	65,230	1 92 ppm	4,800		1 8-11 7	
		1969	4,500	12 6 ppm	11,800		1 5-12 3	
		1970	2,700	35 ppm	116		3 3-3 5	
	Year total volume							



PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774 (continued)

Bldg	General Types and Levels of Contamination	Year	Monthly <sup>3</sup>		CR <sup>6</sup> (ppm)	pH	Other
			Average Volume	Highest Activity			
		1971	4,500	11 ppm	1,660		1 7x10 <sup>6</sup> d/m/l Pu
		1972	24,660	10 <sup>7</sup> d/m/l	25,800		6,900d/m/l Pu U235-.7 ppm U238-150 ppm
		1973	7,630	210,000 d/m/l	2,870		170,000 d/m/l Pu U235-3.3 ppm U238-210 ppm
		1974	19,560	600,000 d/m/l	9,000		310,000 d/m/l Pu U235-.64 ppm U238-155 ppm
		1975	3,130	2 7 x 10 <sup>5</sup> d/m/l			220,000 d/m/l Pu U235-3 5 ppm U238-1300 ppm
		1976	6,200	1 7 x 10 <sup>6</sup> d/m/l <sup>1</sup>			
		1953	28,230	240 ppm	8,750	8 2-9 4	Fe 60 ppm
		1954	16,700	416 ppm	72,000	6 9-8 4	Fe 0
		1955	22,300	267 ppm	4,000	7 4-10 8	CO <sub>3</sub> 144 ppm Fe 55 ppm
		1956	30,700	2 18 gT/l <sup>2</sup>	2,400	2 4-11 1	Fe 90 ppm
444	Process waste - depleted uranium	1957	47,100	52 gT/l		10 5-12	
		1958	87,600	106 gT/l	205	9-12	Fe 85
		1959	41,200	129 gT/l	92	10 5-12	Fe 47
		1960	43,670	01 gT/l	<10	11-12 5	
		1961	47,670	028 gT/l	165	10 5-12 0	
		1962	41,670	0039 gT/l	775	9 0-12 3	
		1963	61,600	0158 gT/l	122	3 1-12 5	
					19		

PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774 (continued)

Bldg	General Types and Levels of Contamination	Year	Monthly <sup>3</sup> Average Volume	Highest Activity	NO <sub>3</sub> (ppm)	CR <sup>+6</sup> (ppm)	pH	Other
		1964	59,030	019 gT/l	173		2 6-11 6	
		1965	41,300	044 gT/l	435		3 7-11 3	
		1966	61,000	051 gT/l	732		3 8-11 3	
		1967	17,910	029 gT/l	19	< 05	3 4-8 6	
		1968	41,700	25 gT/l	9 5	< 05	2 8-11 9	
		1973	4,900	110,000 d/m/l	< 5	105	2 1-13 2	
	Year total	1974	3,600	28,000 d/m/l	10	< 05	8 2	
		1975	3,470	77,000 d/m/l	76	1	2 9-9 9	PO <sub>4</sub> 12 ppm
	Year total	1976	2,300	5,600 d/m/l			9 9	
559	Lab waste - activity refers to plutonium	1969	4,960					
		1970	9,550					
		1971	4,450					
		1972	5,120					
		1973	3,430					
		1974	1,770					
		1975	3,630					
		1976	1,800	8 5 x 10 <sup>6</sup> d/m/l				6 31x10 <sup>-5</sup> g/l- Pu <4 29x10 <sup>-6</sup> g/l Am

1 = total alpha in disintegrations/minute/liter

2 = gT/l is grams of tuballoy (U-238) per liter

3 = all volume in gallons

PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774 (continued)

Bldg	General Types and Levels of Contamination	Year	Monthly Average Volume	Highest Activity	NO <sub>3</sub> (ppm)	CR <sup>+</sup> 6 (ppm)	pH	Other
889	Decontamination water contains both uranium and plutonium	1969	1,000	14.7 ppm 2.3 x 10 <sup>6</sup> d/m/1	5,000	< 05	10.2-12.5	
	Year total	1970	1,000	2.3 x 10 <sup>5</sup>	< 5	< 05	9.9	
		1971	1,000	4.8 x 10 <sup>5</sup>	< 5	< 05	5.8	
		1972	1,000	1.3 x 10 <sup>5</sup>	11,100	52	5.4-9.6	
		1973	2,500	4.9 x 10 <sup>5</sup>	117	1	7.6-12.6	
		1974	1,400	4.6 x 10 <sup>5</sup>	55	74	11.6-13.5	
		1975	1,600	3.1 x 10 <sup>5</sup>			1.7-8.5	2,400d/m/1Pu
		1976	na entries					
122	Small amount of low-level waste - it is held in an underground tank and transferred to a portable tank which is transported to either 774 or one of the ponds depending on the level							
123	Small amount of low-level lab waste but with nitrate ion concentration (raw waste to 207 ponds)							
886	Small amount of waste held in aboveground steel tank and transported by portable tank (U-235)							
776	High volume - high activity (prior to 1969 waste was low-level and transferred directly to the ponds - see raw waste section)	1969	149,000	13 x 10 <sup>6</sup> d/m/1	117	< 05	7.7-10.3	
		1970	164,000	39 x 10 <sup>6</sup> d/m/1	< 5	< 05	6.2-12.2	
		1971	68,900	86 x 10 <sup>6</sup> d/m/1	138	< 05	2.1-9.8	
		1972	136,300	630 x 10 <sup>6</sup> d/m/1	135,100	< 05	6.7-10.4	
		1973	112,900	3.77 x 10 <sup>9</sup> d/m/1	< 5	< 05	5.8-9.5	
		1974	40,100	17.2 x 10 <sup>6</sup> d/m/1	< 5	< 05	4.0-10.3	31 6x10 <sup>6</sup> d/m/1 Pu
		1975	26,900	58 x 10 <sup>6</sup> d/m/1	< 5	< 05	5.0-10.5	
		1976	25,000	6.86 x 10 <sup>6</sup> d/m/1	< 1	< 05	9.9-11.2	

NOTE

771 Waste into first stage of 774 - all this waste was transferred in lines that run through a tunnel between 771 and 774 and are thus double-contained and inspectable. This waste was summarized for 1953-1966 and this summary is contained. After 1966 the volume was greatly increased and time limitations prevented a summary of more recent years.

PROCESS WASTE DATA SUMMARY - FLUIDS INTO 2ND STAGE OF 774 (continued)

Bldg	General Types and Levels of Contamination	Year	Monthly Average Volume	Highest Activity	NO <sub>3</sub> (ppm)	CR <sup>+</sup> 6 (ppm)	pH	Other
771	Janitor waste and decontaminated water (prior to 1969 waste was low-level and transferred directly to the ponds - see raw waste section) Activity refers to plutonium	1969	25,600	1 9 x 10 <sup>6</sup> d/m/1	39	< 05	4 1-7 8	
		1970	46,500	8,000 d/m/1	108	< 05	5 4-8 4	
		1971	14,000	14,000 d/m/1	10	< 05	7 6-8 8	
		1972	7,700	7,700 d/m/1	100	< 05	3 5-7.4	
		1973	8,700	5,100 d/m/1	650	< 05	3 3-11 6	
		1974	5,500	210,000 d/m/1	20	< 05	7 4-10 3	
		1975	6,000	4,200 d/m/1	<5	< 05	6 8-7 9	
		1976	4,200	1,300 d/m/1	21	< 05	5 7-6 6	
707		1972	18,200					
		1973	12,000					
		1974	8,300					
		1975	8,100					
		1976	8,000					
779		1972	11,400					
		1973	9,200					
		1974	8,000					
		1975	4,300					
		1976	5,000					

TREATED WASTE FROM 774 (TANKS 66, 67, 68) TO PONDS

Description	Year	Monthly Average Gallons Volume	d/m/l Activity	NO <sub>3</sub> (ppm)	CR <sup>+6</sup> (ppm)	F <sup>-</sup> (ppm)	Beta
To Pond 2-A (207-A)	1956	200,000	200,000				
	1957	181,000	60,000	9,600			
	1958	233,500	32,000	22,000			
	1959	110,100	200,000	64,000			
	1960	108,000	154,800	715,000			
	1961	26,700	4,400	25,000			
	1962	no entries					
	1963	no entries					
	1964	86,200	19,000	41,200			
	1965	223,100	40,000	68,000			
	1966	280,000	23,000	110,000		1,000	
	1967	129,000	52,000	135,600	< 05		
	1968	145,500	130,000	87,900			
	1969	78,850	190,000	52,000			
	1970	94,600	130,000	70,400			
	1971	196,000	37,000	59,700			
	1972	266,300	200,000	151,200			
	1973	292,000	320,000	70,400			
	1974	195,000	30,000	90,000			
	1975	253,600	30,000				
	1976	172,650	27,000				
	1960	40,800	5,800	21,000			
	1961	96,340	18,000	26,000			
	1962	140,900	9,400	35,000			
	1963	142,400	7,100	45,200			
	1964	114,900	11,000	56,600			
	1965	288,400	24,000	113,000			
	1966	230,600	12,000	90,000			
	1967	144,300	55,000	98,200			
	1968	82,100	150,000	93,600			
	1969-1972	no entries					
	1973	9,900	34,000	69,600			
	1974	221,000	29,000	166,400			
	1975-1976	no entries					
Year total							
To Pond 2-B (207-B)							
							770,000.6
							2.1 x 10 <sup>5</sup>
							4 ? x 10 <sup>5</sup>

TREATED WASTE FROM 774 (TANKS 66, 67, 68) TO PONDS (continued)

Description	Year	Monthly Average Gallons Volume	d/m/l Activity	NO <sub>3</sub> (ppm)	CR <sup>+</sup> 6 (ppm)	F <sup>-</sup> (ppm)	Beta
To Building 95 Ponds (Pond 3)	1954	68,700	440	3,300	18 ppm U	20 ppm	
	1955	47,800	693	4,850			
	1956	54,940	900	10,000	< 05		
	1957	143,100	2,000	5,800			
	1958	104,700	1,000	6,800	< 01	125	
	1959	82,500	2,200	5,900	< 05	>100	
	1960	100,600	1,100	1,300	< 05	50	
	1961	199,000	1,000	800	< 05	50	
	1962	158,800	1,100	995	< 05	60	
	1963	218,300	2,700	620	< 05	40	
	1964	200,800	1,400	880	< 05	20	
	1965	45,900	1,700	480	< 05	40	
	1966	242,400	2,100	650	< 05		
	1967	146,300	1,700	388	< 06		
	1968	no entries					
	1969	212,700	5,300	53	18		
	1970	204,500	1,600	22	< 05		
	1971	93,700	2,700	<5	< 05		
	1972	57,140	3,000	28.4	52		
	1973	Average 67,730	1,600	12 ppm	< 05 ppm		
To Sewage Tank 990							

Total year

Description	Year	RAW WASTE TO PONDS (FOR BREAKDOWN BY SOURCE - SEE COMPLETE DATA)							
		Volume	U-235	U-238	NO <sub>3</sub>	CR <sup>+6</sup>	Other (ppm)	pH	Pu
To Pond 2-A	1956	101,580	9,200 d/m/l						
	1957	215,800	34,800		550 ppm	16 ppm	F 154,000 I 6,020	3 1-11 7	
	1958	77,600	168,600	1 31 g/l				2 0-11 8	
	1959	66,100	5 7 ppm	45 g/l		<1			
	1960	87,500	14 ppm	1 1 g/l			1 1 g/l		
	1961	48,500	15 ppm	1 72 g/l					
	1962	56,200	2 ppm	1 23 g/l					
	1963	no entries							
	1964	108,200	2 1 ppm	1,500 d/m/l 625 g/l	<5 ppm			10 4-12	
	1965	104,800	2.2	05 g/l	240	< 05	F 100	6 6-11 7	
	1966	106,000	2 9		38,000				
	1967	691,504	78 ppm		9,600				
	1968	235,900	39 ppm		195			2 7-7 5	
	1969	70,750	1 25		8,480	30 8			
	1970	94,750	5 8		10,120	110		1 2-10 9	
	1971	267,100	4 6	1,056 ppm	492	210	Be 100 ppm	1 5 x 10 <sup>6</sup> d/m/l	
	1972	94,000	5 4	647	3,000	24 2	Be 1 15	3 5-11 7	027g/12600d/m/l
	1973	154,600	180,000 d/m/l		5,800	194			5,100 d/m/l
	1974	125,400	150,000 d/m/l	1 7 ppm	338	24			5,800 d/m/l
	1975	122,100	27,000		135	13	PO <sub>4</sub> 29		9,600 d/m/l
	1976	103,600	26,000 41 ppm	46 ppm	<1				21,000

Description	Year	RAW WASTE TO PONDS (FOR BREAKDOWN BY SOURCE - SEE COMPLETE DATA) (continued)							
		Volume	U-235	U-238	NO <sub>3</sub>	CR <sup>+6</sup>	Other (ppm)	pH	Pu
To Pond 2-B	1961	40,300	7 3 ppm	1 05 g/l				9 0-11 8	
	1962	106,800	8 6 ppm	1 1 g/l	6			4 0-12 0	
	1963	55,400	4 ppm	1 52 g/l	140			5 0-11 3	
	1964	37,300	2 9 ppm	29 g/l		<1		11 0	
	1965	41,750	5 5 ppm	980,000 d/m/l	4,200	<1	25	3 0-11 1	
	1966	27,200		53 g/l	540			2 5-11 2	
	1967	110,800	10 5 ppm	50,000 d/m/l	7,200	< 05			
	1968	no entries		069 g/l					
	1969	99,900	335 ppm	82,000 d/m/l	8,000	< 05		1 4-10 1	
Year total	1970	8,100	54 ppm		1,560			2 7-3 3	
	1971	no entries							
	1972	no entries							
	1973	121,800	22,000 d/m/l	4,500 d/m/l	438	< 05	tritium 7136		12,000 d/m/l
	1974	146,400	28,000	20,000	640	< 05		1 7-12 6	6600
	1975	4,500		13,000				7 0	
	1976	no entries							



Description	Year	Volume Gallons	RAW WASTE TO PONDS			CR <sup>+6</sup> (ppm)	pH	Other (ppm)
			Activity	NO <sub>3</sub> (ppm)				
To Building 95 Pond (Pond 3)	1957	208,200	800 d/m/l	8		01 ppm		F <sup>-</sup> 50
	1958	482,100	1,000 d/m/l					F <sup>-</sup> 10
	1959	339,100	800 d/m/l	10		< 05	9.0	F <sup>-</sup> <10
	1960	550,800	1,600	40			8-10.5	
	1961	432,400	1,400	45			5.8-11.5	
	1962	459,200	1,700	68		< 05	4.5-11.4	F <sup>-</sup> <10
	1963	667,100	2,400	10		46	6.5-11.9	F <sup>-</sup> 25
	1964	651,200	2,200	< 5		< 05	8.9-12.0	F <sup>-</sup> 45
	1965	661,300	2,800	< 5		< 05	10.4-11.7	F <sup>-</sup> 30
	1966	580,700	2,600	97		< 05	6.1-11.9	
	1967	308,620	2,900	21		< 08	3.8-10.5	
	1968	359,000	6,400	128		1.1	3.1-10.5	
	1969	306,000	5,800	50		33	3.9-10.0	
	1970	299,000	4,500	11		< 05	6.3-9.4	
	1971	449,200	19,000	47		< 05	6.5-10.2	
	1972	496,500	25,000	16		< 05	2.8-11.4	Be .67
	1973	331,000	16,000	40		09	6.1-12.2	
Raw waste to Pond 2 (old clay-lined)	1954	7,500	753					
	1955	42,300	4,000					
	1956	18,600	1,000	5				F <10
	1957	291,600	1,000			01	1.6-11.7	
	1958	46,600	42,600			<1 ppm	4.5-12.5	
	1959	172,800	24,000	2,400 ppm		3.9		
Treated waste to Pond 2 (old clay-lined)	1960	41,400	1,300 d/m/l	162				
	1954	123,700	25,213	16,800				F 160 .59 ppm U
	1955	81,200	2,600	22,000				F <sup>-</sup> 1000
	1956	104,100	4,000	39,700			11.8-12.6	
	1957	no entries						
	1958	78,000	2,700	800				F <sup>-</sup> >100 Cd < 05
1959	75,208	280,000	26,500					

### APPENDIX 3 - SOIL SAMPLES

Nine locations were chosen for soil sampling in areas where repairs or leaks have occurred. All samples were taken from the bit of an auger after drilling to about 4' deep. Soil sample pits were located as close as possible to the area of concern and generally on the northeast side. Exact distances are noted on the sketches contained in this appendix.

Soil sample analyses were conducted by the Health and Environmental Science Labs, under the direction of Weldon Williams.

Soil sample analysis results:

<u>Sample No.</u>	<u>NO<sub>3</sub> (ppm)</u>	<u>Pu<sup>239</sup> (d/m/g)</u>
1	62	0.037
2	110	0.049
4	54	0.145
5	148	0.485
6	104	0.05
7	70	0.185
8	76	1.83
9	44	3.385

EIGHTH STREET

ELECTRIC POWER LINE

3"-PW-STL


3"-PW-STL

3"-PW-NEWER IN OLD 10" V&P

VALVE PIT



3'-4"  
2'



884

CENTRAL AVE

FENCE

ANALYSIS RESULTS:

NO<sub>3</sub> - 110 ppm

Pu<sup>239</sup> - .049 g/m<sup>2</sup>

N ↑

DESCRIPTION	APPROVED	CL. APPROVED	REV	DESCRIPTION	APPROVED	CL. APPROVED	REV
DESIGNED				SOIL SAMPLE PIT 2			
DRAWN				REF DWG			
CHECKED				15501-37 E-5			
APPROVED							
RELEASE DATE							

SIZE	REV	SHEET	CAT
A	PG 3-3	OF	



ROCKWELL INTERNATIONAL  
ATOMIC INTERNATIONAL DIVISION  
S.A.S. CONTRACT 1 02-0-020  
ROCKY PLATE PLANT GOLDEN, COLORADO 80401

ELECTRIC  
POWER LINE

SOIL SAMPLE  
PIT 1

(4"-PW-CI)

INSTALLED 1952  
SEE APPENDIX I-A (III)  
FOR LEAK INFORMATION



ANALYSIS RESULTS:

$\text{NO}_3^-$  - 62 ppm

$\text{Pu}^{239}$  - 0.037  $\alpha/\text{m/g}$

N ↑

DESCRIPTION	APPROVED	CL. APPROVED	REV	DESCRIPTION	APPROVED	CL. APPROVED	REV
DESIGNED				SOIL SAMPLE PIT 1			
DRAWN				REF DWG			
CHECKED				15506-36			
APPROVED				E-4			
RELEASE DATE							

SIZE	REV	SHEET	OF
A	PG 3-2		

ROCKWELL INTERNATIONAL  
ATOMIC INTERNATIONAL DIVISION  
E.A.S.A. CONTRACT E 120-0-000  
ROCKY PLATE PLANT  
GOLDEN, COLORADO 80401

SAGE AVE.

SOIL SAMPLE 3 WAS TO HAVE BEEN  
IN THIS AREA BUT A PREVIOUS  
STUDY SHOWED NO MEASURABLE  
CONTAMINATION - SEE APPENDIX I-A(I)

3" RUBBED HOSE IN 4" EG-REIN. EPOXY PIPE

ABANDONED 1975  
3" JARIN-LINED STL IN 10" VCP

3" RUBBED HOSE IN OLD 10" VCP

CENTRAL AVE

EIGHTH STREET

N ↑

Y	DESCRIPTION	APPROD	CL APPROD	REV	DESCRIPTION	APPROD	CL APPROD	RDG.
WORKED								
DRAWN	SOIL SAMPLE PIT 3 REF DWG 15501-29 D-5				ROCKWELL INTERNATIONAL ATOMIC INTERNATIONAL DIVISION U.S.A. CONTRACT # 124-2-1533 ROCKY PLATE PLANT GOLDEN, COLORADO 80021			
CHECKED								
APPROVED								
RELEASE DATE								
				SIZE	REV		SHEET	CAT
				A	PG 3-4		OF	

3"-PW-SST

707

3" SARAN-LINED STL IN 10" VCP  
ABANDONED 1968  
SEE APPENDIX I-A (II)

SOIL SAMPLE  
PIT 4

ANALYSIS RESULTS .

$\text{NO}_3$  - 54 ppm

$\text{D}_u^{239}$  - 0.145  $\alpha/\text{m}^2/\text{g}$

N↑

DESCRIPTION		APPROVED	CL. APPROVED	REV	DESCRIPTION		APPROVED	CL. APPROVED	REDA
SOIL SAMPLE PIT 4					ROCKWELL INTERNATIONAL ATOMIC INTERNATIONAL DIVISION E.R.A. CONTRACT 2 02-6-555				ROOM
REF DWG					ROCKY PLATE PLANT GOLDEN, COLORADO 80401				CAT
15501-29				D-5	SIZE	PG 3-5	REV	SHEET	OF
RELEASE DATE					A				

SOIL SAMPLE  
PIT 5

$$\frac{5}{x} \times$$

42

50'

~~3" SAG - 40' - ED~~

778

$\text{NO}_3 - 148 \text{ pp}$



$P_{11}^{234} = 0.455$  J.

N ↑

REV	DESCRIPTION	APPR'D	CL APPR'D	REV	DESCRIPTION	APPR'D	CL APPR'D	BLDG	
DESIGNED	SOIL SAMPLE PIT 5  REF DWG  15501-21  G-5	ROCKWELL INTERNATIONAL ATOMICS INTERNATIONAL DIVISION E.R.D.A CONTRACT E (78-25-252) ROCKY PLATE PLANT GOLDEN, COLORADO 80401						ROOF	
DRAWN								CAL	
CHECKED									
APPROVED									
RELEASE DATE									
		SIZE					REV	SHEET	CAL
		A	PG 3-6					OF	

# ANALYSIS RESULTS:

SAMPLE NO.	NO <sub>3</sub> (ppm)	Pu <sup>239</sup> (ppm/g)
6	104	0.05
7	70	0.185
8	76	1.83



SEE APPENDIX I-B (II)  
FOR LEAK INFORMATION

N ↑

777

79

REV	DESCRIPTION	APP'D	CL APP'D	REV	DESCRIPTION	APP'D	CL APP'D	BLDG.	
DESIGNED					ROCKWELL INTERNATIONAL ATOMIC INTERNATIONAL DIVISION ERDA CONTRACT E (78-25-262) ROCKY PLATE PLANT GOLDEN, COLORADO 80401				ROOM
DRAWN	SOIL SAMPLE PITS 6,7,8 REF DWG 15501-13 B-5				SIZE			CAT	
CHECKED						REV	SHEET		
APPROVED					A	PG 3-7	OF		
RELEASE DATE									



# ANALYSIS RESULTS.

NO<sub>3</sub> - 44 ppm

Pu<sup>239</sup> - 3.385 α/m/g

SOIL SAMPLE - SEE APPENDIX 1-B  
PIT 9

GUARD  
POSTS

→ 3' ←

X

↓ 3' ↑

10' DCW-CI

6"-PW-CI

REDUCER

3" PW-SST

774

N ↑

771

Y	DESCRIPTION	APPRD	CL APPRD	REV	DESCRIPTION	APPRD	CL APPRD	BLDG.
	SIGNED							
	DRAWN							
	CHECKED							
	APPROVED							
	RELEASE DATE							
SOIL SAMPLE PIT 9 REF DWG 15501-13					ROCKWELL INTERNATIONAL ATOMICS INTERNATIONAL DIVISION U.S.A. CONTRACT # 15501-13 ROCKY PLATE PLANT GOLDEN, COLORADO 80401			
B-5					SIZE A	PG 3-8		REV OF
						SHEET OF		CAT

## APPENDIX 5 - LIBRARY SEARCH

### PIPE CLEANING METHODS

A survey of the technical periodical indexes was conducted to search out new developments in the areas of pipe cleaning, plugging, and removal. Cross references were used in the area of nuclear wastes as well as general pipe listings.

Although there are now a number of installations in this country which handle nuclear materials, not many have been in service as long as the Rocky Flats Plant. Understandably, there has been little written on the problem of abandoning pipelines which have the potential of containing nuclear residue. Some information was found which could be helpful in cleaning the lines but nothing on pipe plugging or removal.

One very specific procedure was recommended by Dr. J A Ayres of Battelle Northwest <sup>(1)</sup>

1. Use a solution of 18% potassium hydroxide and 3% potassium permanganate for three hours at 105° C (221° F)
2. Rinse thoroughly
3. Use 10% sulfamic acid for three hours at 70° C (158° F)
4. Rinse thoroughly
- 5-8 Repeat steps 1-4

Dr. Ayres has used this method to clean pipes that have carried nuclear materials. Although the temperatures seem unrealistic for cleaning pipes several hundred

---

(1) How to Employ Chemical Cleaning for Power and Process Piping, C M Loucks, Heating, Piping and Air conditioning, June 1965

feet long, the solutions could still be an improvement over those used for cleaning pipes with more typical waste products.

There is ample information suggesting that sulfamic acid is better than hydrochloric. Specifically (2)

- A. Inhibited sulfamic acid vs. hydrochloric acid
  - 1. sulfamic is safer to use, a more effective descaler and poses no corrosion problems
  - 2. the solution strength and temperature are not critical, even if an error is made, there is no danger of damage to equipment
- B. Basic rules for using sulfamic acid
  - 1. keep it hot - the best temperature is about 160° F
  - 2. keep it strong - 40 lb dry acid descaler/50 gallons of water. Too much acid is uneconomical, too much water is not strong enough
  - 3. keep it moving - to keep fresh, strong acid against the pipe walls

Other periodicals which might be helpful are

Applying Chemical Cleaning Solvents, C. M. Loucks, Heating-Piping, September 1964.

Steps for Chemical Cleaning of Piping Systems, C. M. Loucks, Heating-Piping, May 1964

How to Choose An Acidic Cleaner, J. D. Palmer, Can Chem. Process., January 1970

---

(2) It's Cheaper to Clean it In-Place, C. T. Gallinger, Mill & Factory, May 1965

## BIBLIOGRAPHY

A Survey of the Rocky Flats Division Waste Streams, C. E. Plock,  
CRDL 950351-009, June 30, 1972

Building 774 Log Books, kept by M. E. Maas, 1952-1976

Correspondence; letter to J. A. Watt from B. L. Kelchner; Re  
Engineering Study for Abandoned Process Wastes Lines,  
September 22, 1975

Correspondence; letter to H. E. Bowman from B. L. Kelchner, Re  
Inspectable and Repairable Process Systems

Evaluation of Two Sections of the Rocky Flats Process Waste Line,  
Hornbacher and Lott, PRD 950463-107, May 1972

Liquid Wastes and the Nitrate Problem at the Rocky Flats Plant,  
B. L. Kelchner, oral presentation given at the Problems Analysis  
Meeting held at Rocky Flats on May 25-26, 1971

Pressure Testing and Leak Location Survey of Process Waste Lines  
at the Rocky Flats Facility

## REFERENCE DRAWINGS

The following drawings for location and dating of the process waste collection system are available in the Facilities Engineering and Construction Department.

### Original Process Waste Lines\*

15501-(Utility Drawings)

13902

25609-X08

SK-410204-(1-5)

### New Process Waste Lines

25052-047

### Process Waste Collection Tanks

19878-1

19878-2

- \* The drawings contained in this study of the process waste lines have been thoroughly checked and altered for accuracy. Most of the changes incorporated in the drawings are from information obtained from M E. Maas of Waste Treatment. The numerous sketches of changes and repairs in the lines kept by Mr. Maas and his excellent memory were a most important resource in locating lines. Field checks were made whenever possible such as at entry points to buildings, valve pits, etc.

10/24/80

REPORT OF INVESTIGATION ON A RECENT  
PROCESS WASTE PIPELINE LEAK

ES-376-80-217

C T Illsley  
Environmental Analysis

ENVIRONMENTAL SCIENCES

ROCKWELL INTERNATIONAL  
Rocky Flats Plant  
Energy Systems Group  
P. O. Box 464  
Golden, Colorado 80401

Work Performed Under Department of Energy  
Contract DE-AC04-76DP03533

60-13023-KK-002

Distribution

T R Crites  
D D Hornbacher  
M E Maas  
E A Putzier  
E Vejvoda  
C E Wickland  
R E Yoder

KWIC Index

Contamination  
Leak/Spill  
Process Waste Water  
~~Soil Cleanup~~  
Illsley, C T  
ES-376-80-217

## INTRODUCTION

This report summarizes an environmental incident investigation of a radioactive liquid process wasteline leak that occurred on July 21, 1980. It includes a description of the incident, subsequent cleanup activities and costs, and future plans for the process waste line.

## INCIDENT SUMMARY

During the morning of July 21, 1980 two painters were walking along the road southeast of Building 774. They observed water seeping up in the soil on the south side of the road. They immediately returned to Building 774 and informed Waste Processing personnel of the possible leak. The 3 inch line carrying process waste from Building 774 to the solar evaporation ponds was immediately shut off. The leak was then observed to have stopped.

Figure 1 shows the location of the leak. From this point, the leaking process waste water flowed down slope through a 30 foot culvert, along the east chain link fence and under the fence at the corner. From there, the liquid flowed under the unpaved access road into a boggy area north of Building 774. These areas are shown in Figures 2 and 3.

Based on the pumping time and flow rate, the volume of process waste liquid that leaked onto the hillside was estimated to be about 1000 gallons. Samples of the liquid were collected by personnel from the Environmental Analysis Group and subsequent analysis showed the presence of about 2500 pCi/l total alpha, 4000 pCi/l gross beta, 10,000 mg/l nitrate and a pH of 12.

As soon as the soil dried out, FIDLER measurements verified the presence of alpha contamination. The FIDLER survey also verified the direction of flow and that the flow did not go beyond the boggy area into North Walnut Creek. If the leaking liquid had reached North Walnut Creek, it would have been contained in Pond A-3 or Pond A-1 as the A-1 bypass system was activated to divert flow into Pond A-1 soon after the leak was discovered.

# **NOTICE:**

**“BEST AVAILABLE COPY”**

**PORTIONS OF THE FOLLOWING  
DOCUMENT ARE ILLEGIBLE**

**The Administrative Record Staff**






Figure 1  
Location of Waste Line Break (continued)



Figure 2. Flowline of Leak Along Fence



Figure 3. Vegetation Killed by Waste  
Process Liquids

#1 - EXTERNAL VIEW VV #7






#2 - INTERNAL VIEW VV #7



#3 - MAIN ELECTRICAL BOX



#4 - UPPER ALARM AND SEEPAGE  
COLLECTION BOTTLE




#5 - HIGH-LEVEL AND LOW-LEVEL  
LINES ENTERING VAULT






#7 - UPPER VIEW OF SUMP PUMP LINE



#4 - EXTERNAL VIEW  
CHECK VALVE HOUSING



#9 - INTERNAL VIEW  
CHECK VALVE HOUSING



**TECHNOCHECK VALVE**  
SERIAL **2800920**  
TEMP. **2800920**  
PATENT **2800920**  
ERIE, PENNA.  
TECHNOCHECK VALVE

## CLEANUP ACTIVITIES

On July 24, 1980 the broken line was excavated and the source of the leak was found to be a loose flange. A new gasket was installed, the flange nuts were tightened and the line passed a leak test.

A soil decontamination planning meeting also was held on July 24, 1980. Those in attendance were C. J. Barker and R. W. Hawes, Environmental Analysis, W. F. Bates, Waste Management, E. Klanecky, Operational Safety, and G. Webber, Radiation Monitoring.

Soil excavation with a tractor mounted backhoe began on the morning of July 28, 1980. Radiation monitors checked the soil as it was excavated. Portable air samples were used to check the air activity in the vicinity of the excavation and at the receiving container (box) as it was being filled. The air concentrations of total long-lived alpha activity were  $<0.001 \text{ pCi/m}^3$  in the general area and  $0.108 \text{ pCi/m}^3$  near the box. The total long-lived alpha concentration in the general area was below the shutdown action level of  $<0.06 \text{ pCi/m}^3$ .

## CLEANUP COSTS

The estimated costs of the spill cleanup, as provided by Waste Management, are as follows:

Boxes	\$3,600
Transportation	2,644
Labor	<u>7,600</u>
Total	\$13,844

## ENVIRONMENTAL IMPACT

A review of the data from permanent ambient air samplers that are located in the general vicinity of the spill was conducted. The total long-lived alpha concentrations measured from samples collected during the spill and subsequent cleanup period all were normal.

80-RF-2046

NAME	INITIALS
WILLIAMS, R.O.	
DORR, J.E.	X
BENJAMIN, A.	
ISLAND, W.D.	
IAR, D.H.	
AFR, W.V.	
KUNZ, E.G.	
OWEN, P.G.	
REBRO, W.L.	
SHANNON, W.M.	
SMITH, R.E.	
SWERNEY, P.F.	
VEJVODA, E.	X
WIEDERECHT, D.	
YODER, R.E.	X
YOUNG, E.R.	
SHIFT, SUTTS	
ARMSTRAD, W.E.	
BARNES, W.L.	
BARTLETT, J.B.	
BELLAGAMBA, E.	
BOYD, C.W.	
BYRNE, J.P.	
CALKINS, E.	
CREAGER, S.W.	
DENNIS, P.W.	
DOLBE, P.G.	
DONDELINGER, M.	
DUMN, D.A.	
ELLS, R.R.	
FARRELL, L.C.	
FARULO, L.A.	
FLOYD, D.R.	
FREIBERG, E.	
GIER, J.A.	
HEALY, T.J.	
HILBIG, R.A.	
HOPMAN, R.R.	
HOPPE, E.	
RAMBETTI, E.	
ROSE, R.T.	
ROSE, R.E.	
ROSE, J.M.	
ROSENBERG, E.	
ROSE, D.M.	
LOUDEMBO, G.E.	
MARTIN, R.L.	
MARTINEZ, J.L.	
MASON, D.G.	
MCCARTHY, J.D.	
MCMANARA, E.E.	
O'BRIEN, M.	
PALIAN, M.A.	
PUTZIER, E.A.	
RHOADES, R.E.	
ROOKER, W.L.	
ROSE, C.	
STEWART, L.M.	
STUMP, W.D.	
THOMAS, E.G.	
TROELTZSCH, R.	
VELASQUEZ, R.M.	
WAGNER, J.D.	
WEIDNER, C.	
WERNER, M.R.	
WILLIAMS, R.A.	
Hamberger, X	
Healey, C. X	

CLASSIFICATION	INITIALS
UNCLASSIFIED	
CONFIDENTIAL	
SECRET	
AUTH. CLASSIFIED SIG	

11-12-80

L APPROVALS

ORIG & TYPED INITIALS  
 TRC/DPH/mmK  
 IN REPLY TO LTR. NO.

ROCKY FL. PLANT  
 ENERGY SYSTEMS GROUP  
 P O Box 464  
 Golden Colorado 80401  
 (303) 497 7000  
 Contractor to  
 U S Department of Energy



Rockwell  
 International

November 12, 1980

80-RF-2046

Mr. E. W. Bean  
 DOE, RFAO

# REPORT OF INVESTIGATION ON PROCESS WASTE LINE LEAK

Enclosed are two copies of a report that summarizes  
 an environmental incident investigation of the process  
 waste line leak that occurred on July 21, 1980

Please direct any question that you may have to  
 C. T. Illsley at extension 7079.

*T. R. Crites*  
 T. R. Crites, Manager  
 Environmental Sciences

TRC:DDH:mmk  
 Orig. and 1 cc - Mr. Bean  
 Enc.

*Keywords*  
*Illsley, C T*  
*ES-376-80-217*  
*Contamination*  
*Leak*  
*Process waste water*

21003-RR

INSTR NO  
1036

ST		ENC
LA		
ND WD	X	X
DH		
WV		
L		
WM		
E	X	X
HT DA		
BD		
E	X	X
R		
EJ		
FN		
R		
A		
RJ		
V		
K		
RH		
RG GE		
JL		
JD		
R		
IK		
Z RN		
D		
ZW		
CE		
INTROL	X	X
W	X	X
B	X	X
T	X	X
G	X	X
E	X	X
LC	X	X
FA	X	X
DC	X	X
NG	X	X
S	X	X
ATION		
FILED	X	X
STIAL		
SSIFIER SIG		
PIST INITIALS		

Rocky Flats Plant  
Energy Systems Group  
Rockwell International Corporation  
P O Box 464  
Golden Colorado 80402-0464  
(303) 497-7000



Contractor to U.S. Department of Energy

May 5, 1983

83-RF-1036

James R. Nicks  
Area Manager  
DOE, RFAO

UNUSUAL OCCURRENCE REPORT - VALVE VAULT #7

Attached is the UOR Number RFP 83-2--Sage 83-1. This interim report was prepared in accordance with DOE Order 5484, Unusual Occurrence Reporting.

*Robert E. Yoder*  
Robert E. Yoder, Director  
Health, Safety and Environment

Orig. and 1 cc - J. R. Nicks  
Enc.

60-20100-KK-002

*Revised  
UOR  
Yoder RE  
Valve vault  
Process waste*

UNUSUAL OCCURRENCE REPORT

ROCKWELL INTERNATIONAL

ROCKY FLATS PLANT

VALVE VAULT #7 OVERFLOW - APRIL 4, 1983

1 UOR Number RFP 83-2--Sage 83-1

2. Status and Date Initial 5-5-83  
Interim 5-5-83  
Final

3 Division or Project

Rocky Flats Plant, Energy Systems Group

4 Facility, System or Equipment

Process waste collection transfer system, Valve Vault #7, transporting aqueous process waste from Buildings 881, 889 and 865 to Building 374 (see Figure 1, diagram of system).

5. Date of Occurrence

April 4, 1983

6 Time of Occurrence

Overflow from Valve Vault #7 was first observed at approximately 0950. A chronological sequence of events is provided in Attachment 1.

7 Subject of Occurrence

Process waste water overflowing around manhole cover at Valve Vault #7

8. Apparent Cause

Wastes were being inadvertently pumped into Valve Vault #7 through either a break in the transfer line or a malfunctioning check valve in the sump pump line

Alarm system indicating problem in Valve Vault #7 assumed to be inoperative

"REVIEWED FOR CLASSIFICATION

By Ed V. Depina

Date 5/5/83"



9. Description of Occurrence

A check valve located in Valve Vault #7 (see Figure 2) malfunctioned allowing process waste water, being pumped out of upstream holding tanks, to backflow through the check valve and sump pump line into the vault. The vault filled with waste water and overflowed. The overflow drained into an adjacent ditch and traveled in an easterly direction toward South Walnut Creek and the "B Series" ponds (see Figure 3). Photographs of the vault and faulty check valve are contained in Attachment 2.

10. Operating Conditions of Facility at the Time of Occurrence

Operating conditions of the facility at the time of the occurrence were abnormal. The alarm (designed to indicate the presence of water in the vault) had malfunctioned on March 10, 1983. An inspection of the vault revealed the presence of moisture, but no accumulation of water. From past experience, it was surmised that ground water moisture had caused an electrical short. A work order was submitted to repair the system on March 11, 1983 (Attachment 3). Normal waste transfer through Valve Vault #7 was allowed to continue to avoid shut down of operations in buildings upstream from the vault.

11. Immediate Evaluation

The sequence of events provided in Attachment 1 indicate that several factors contributed to the overflow occurrence. The contributory factors are sited below.

On March 10, 1983, the alarm system in Valve Vault 7 malfunctioned.

On March 11, 1983, a work order was submitted to repair the alarm. The repair had not been initiated at the time of the occurrence.

On March 28, 1983, alarms in Valve Vaults #1, 3, 4, 5 and 6 activated. They were inspected, and no evidence of water buildup was found. Valve Vault (VV) #7 was not inspected for two reasons.

- 1) Access to the vault cannot be accomplished until Security opens the gate. No one from Security was available to open the gate when two requests for access were made. No further attempts were made to gain access to VV #7 for a visual inspection. In retrospect, operating personnel surmise that the check valve had actually failed before March 28, and VV #7 was partially filled with water before the overflow was observed on April 4.
- 2) The previous inspection indicated a faulty alarm rather than water in the vault. False alarms occur and are a continuing problem because of intrusion of ground water through leaky conduits.

- . On April 4, transfer of waste water through the system was initiated. The water entered the vault through the broken check valve, filled the vault and overflowed to the adjacent environment.

The occurrence caused a temporary suspension of aqueous waste transfer through VV #7. However, the cause of the occurrence was established and remedied before operations in the upstream facilities (Buildings 881, 889 and 865) were affected. Transfer through the system was permitted before electrical repairs were completed, provided an operator remained at the pit to provide visual inspection for leaks during the transfer. Environmental samples have been taken for analysis. Evaluation of the results is complete.

## 12 Immediate Action Taken and Results

The following actions were taken

The transfer of liquid waste from holding tanks at Building 881 was discontinued after personnel verified that waste water was flowing out of VV #7

Temporary dikes were constructed to contain the overflow. Drainage from the area was diverted from Pond B-4 to B-1, and samples were taken for analysis from the vault and from areas of environmental concern.

- . Water was pumped out of VV #7 and out of the containment dikes into a tanker truck for transfer to Waste Processing.
- . After emptying, the vault was cleaned and inspected.
- . Inspection identified a faulty check valve as the primary cause of the occurrence.

The check valve was repaired, and the system was leak-checked by pumping waste through the system. No leaks occurred.

- . The sump pump was replaced, and repair of the electrical system was initiated. Repairs were completed on April 12, 1983.

Arrangements were made to transfer waste through the system using an operator stationed at the pit to check for leaks. Constant visual check during transfer was required until the electrical repairs were completed and the system fully operational.

- . A new type of check valve has been ordered for all the valve vaults in the transfer system. When the new check valves arrive, all check valves in this transfer system will be replaced.

13 Is Further Evaluation Required? Yes ☒ No ☐ See #15

The primary cause of the occurrence was corrected by replacing the check valve and making electrical repairs. Future problems may be alleviated by installing a better quality check valve. However,

the secondary causes of this occurrence will still exist. Specifically, the unresolved problems are

- . False alarms occur regularly due to humidity from ground water intrusion through leaky conduits. Human nature tends to ignore alarms that often "cry wolf" when no wolf is there

Repair of a faulty alarm should be given high priority. The work order specified that the "date needed" was the same date that the order was submitted. Three weeks later, the work had still not been initiated. The system does not appear to be functioning as intended.

- . The location of VV #7, beneath the security fence, requires coordination with Security to gain access to the vault. The individual with the key may not be available when entry is needed.

These problems should be addressed by management to avoid a similar occurrence in the future (E. R. Young, W. D. Crossland, E. Vejvoda 7-5-83)

#### 14. Final Evaluation and Lessons Learned

This section will be completed in the final report.

regarding the nature of the vault and whom to notify in the event of an emergency had been posted at the vault, the response time would have been reduced. It is recommended that the following information be posted at each vault (E. Vejvoda)

Valve vault number and type  
(i e., VV #7, Process Waste Line)

Responsible Organization

Emergency telephone number

Additional recommendations not directly associated with the occurrence (R. E. Yoder)

The presence of oil in the overflow was visually detected. Disposal of oil to the process drain is prohibited since it interferes with the waste treatment process. Generators should be reminded that compliance with HS&E 21 01, sections 3.3 and 4 are mandatory.

New construction on the plant site has occurred. The current map of the storm sewer system should be reviewed and updated as deemed necessary.

Environmental Impact Evaluation - The environmental impact was negligible. In addition to the immediate actions cited in Section 12, Environmental Control retained snow melt water in the ditch for several days and later transferred this water to process waste storage. Gravel from the ditch was excavated and removed to a special storage area for drying. This material will be analyzed for nitrates, oil and radioactivity before final disposition.

Final analyses of water samples from Pond B-1 and Pond B-4 one week after the incident indicated no abnormal concentration of oil, nitrate, pH or radioactivity.

Evaluation of Data for Pond B-5 - The only pond that will be discharged to off site waters indicated the absence of any material from the leak. Furthermore, the water meets the DOE and CDH Radiation Guides for discharge to uncontrolled areas.

16. Programmatic Impact

None

17. Impact Codes and Standards

None

18 Similar Unusual Occurrence Report Numbers

None

19 Signatures

John A. Hayden Date 4-25-83  
John A. Hayden, Chairman Investigating Committee

Donald M. Anderson Date 4-25-83  
Donald M. Anderson, Investigating Committee

William S. Bennett Date 4/26/83  
William S. Bennett, Investigating Committee

Charles T. Illsley Date 4/25/83  
Charles T. Illsley, Investigating Committee

C. Al Noble Date 4/25/83  
C. Al Noble, Investigating Committee,  
Trained Investigator

Garvin T. Hewitt Date 4/26/83  
Garvin T. Hewitt, Line Supervisor, Liquid Waste Processing

Charles E. Wickland Date 4-28-83  
Charles E. Wickland, Manager, Waste Operations

R. E. Yoder Date 5-5-83  
R. E. Yoder, Director, HS&E

E. Vejvoda Date 5-4-83  
E. Vejvoda, Director, Plutonium Operations

G. J. Steppen Date 5-4-83  
G. J. Steppen, HS&E Area Representative

W.D. Crossland  
W D Crossland, Plant Director, Support Operations

Date

10/1/53






Figure 1 Process Waste Collection Transfer System

FIGURE 1

VALVE VAULT # 7





FIGURE 2



ATTACHMENT NO 1

SEQUENCE OF EVENTS  
LEADING UP TO OCCURRENCE

- March 10, 1983 - Alarm in Valve Vault (VV) #7 activated. An inspection of the vault revealed the presence of moisture but no accumulation of water. The alarm remained in the activated state even though no water was present (could not reset alarm)
- March 11, 1983 - A work order was submitted to repair the system. Transfer through VV #7 was allowed to continue to avoid shutdown of operations in buildings upstream of the vault.
- March 28, 1983 - Alarms in VV's 1, 3, 4, 5 and 6 activated. VV #7 was still in the activated alarm state since the March 10 occurrence. The alarm in VV #2 did not activate.
- March 29, 1983 - VV's 1, 2, 3, 4, 5 and 6 were inspected. Moisture was (Midnight Shift) present, but no accumulation of water. All alarms were reset to the nonactivated state. VV #7 could not be inspected because it was under the security fence.
- April 2, 1983 - A second attempt to gain access to VV #7 was unsuccessful.

SEQUENCE OF EVENTS DURING AND AFTER DISCOVERY OF OCCURRENCE - as obtained through interviews with the following individuals

J. Suthern - S&W  
J. D. Tadolin - Plant Protection  
L. P. Ferris, III - Shift Superintendent  
J. L. DiRocchi - Liquid Waste Operations  
J. D. Morrison - Liquid Waste Operations

All times listed are approximate

8 30 J. D. Morrison began pumping operations to transfer liquid waste from Building 881 to Building 374. At approximately the same time,

J. Suthern, S&W, drove his snow plow into the Building 776 area to clear snow. After completing the snow removal assignment, Mr Suthern drove onto Sage Avenue. While driving on Sage, he noticed a rising stream of water from VV #7. He proceeded to Portal #1 Guard Shack to report the sighting to the guard on duty.

09 57 The guard on duty, Patrolman Paul Beights, radioed Captain Tadolini.

10 00 Captain Tadolini called Dispatch to notify Utilities. The Shift Superintendent heard radio transmissions concerning the incident but did not respond, because there is a Utilities steam pit at the approximate location of VV #7.

10.05 Utilities foreman determined the problem was in a transfer pit and not a Utilities problem. Captain Tadolini requested Shift Superintendent assistance.

10:10 Plant Protection notified R. E. Brady, Liquid Waste Processing Foreman, Building 374. Brady, in turn, notified J. D. Morrison, Waste Tank Operator, that there was a problem with VV #7. After checking the vault problem, Morrison returned to Building 881 to shut down the pumping operation and called for access to the vault area.

10.30 Morrison entered the valve vault area. The Shift Superintendent arrived on the scene.

10 50 C. Illsley.(Environmental) arrived at scene.

10 55 S&W employee, Suthern, dammed the ditch east of the guard shack at Portal #1. Illsley noticed drainage was running across the old 750 parking lot, through the Building 991 normal run-off drainage. Another dam was made just west of Guard Shack 762 to stop the liquid's flow from entering the drainage ditch.

A water sample was taken from VV #7.

11 00 Sample was taken from storm drain near Building 995

11 05 Pond B-4 was sampled

2.00 Pumping of liquid from VV #7 into tanker truck began.

2 30 South Walnut Creek was diverted into Pond B-1.

5-30 The second series of samples was taken from the following locations

- 1 Ditch above dam on Sage
- 2 Storm drain near Building 995
3. Pond B-1
4. Pond B-4

## PHOTOGRAPHIC LEGEND

### Photograph No

- 1 External view of Valve Vault #7 (VV #7) showing the location of the vault beneath the security fence. Access to the vault can be gained only after Security personnel open the overhead gate.
- 2 Internal view of VV #7 showing vault after water was pumped out and the vault cleaned.
- 3 Main electrical box which was inundated. The entire electrical system had to be replaced.
- 4 The upper alarm system is designed to activate when seepage water collects inside the poly bottle through the small conduits (normally inside the bottle).
- 5 Shows the incoming high level line (open) and low-level line (closed). Seepage is collected from outer pipe.
- 6 Water entered the sump through the sump pump line. The location of the faulty check valve is shown to the right and above the gauge. The lower alarm system is located beneath the sump pump.
- 7 The upper view of the sump pump line shows the sump line connecting with the high-level line.
- 8 The check valve housing was removed to examine the check valve.
- 9 The interior view of the check valve housing shows one flap on the check valve is missing.
- 10 This photo shows the check valve after removal from the housing. The missing flap would be located to the right of the center screw. The cleavage edge of the rubber can be seen just above the metal trough.





606487 ROCKY FLATS

10/12/87 KAJ

ORNL

DOW CHEMICAL, U.S.A., UNDATED (AROUND FALL 1983 TO EARLY 1984), "A HISTORICAL SUMMATION OF ENVIRONMENTAL INCIDENTS AFFECTING SOILS AT OR NEAR THE U.S. AEC ROCKY FLATS PLANT," by J.B. OWEN & L.M. STEWART DRAFT.

- Soils under and around Bldgs 559, 771, 774, 776-777, 779 & 995 have become infiltrated w/ various radioactive and chemical matter as a consequence of long-term, routine operations. Principal rad matter in these areas is Pu w/ minor amts. of other radioisotopes & Pu decay products ( $\text{Am}^{241}$ ). Major chemicals include nitrates, chromates ( $\text{Cr}^{+6}$ ), organics (such as  $\text{CCl}_4$ ), & in some locations, Beryllium. Soils under Bldg 707, are not considered particularly affected to the extent noted above.

Soils under & around Bldgs 441, 444, 447, 665, 881, 883, 886 & 889 are also infiltrated. Soils under Bldgs 122 & 123 are involved to a lesser degree. The major radioisotopes in these areas are enriched & depleted U, w/ the exception of possible extremely low levels of Pu under & around Bldg 122, 23 & 881 and minor  $\text{U}^{233}$  in Bldg 881. Enriched U spills @ & around Bldg 665 are considered as the only major possible contributions. Chemically, nitrates, chromates & Be infiltration are to be expected, especially in the 400 Complex & Bldgs 665 & 881.

TABLE I

The following buildings at Rocky Flats are currently known or suspected to be radioactively or chemically infiltrated. It is assumed that the soil under each building is similarly infiltrated.


<u>Building</u>	<u>*Type Of Radioactive Infiltration</u>	<u>**Estimated Degree</u>	
		<u>Radioactive Infiltration</u>	<u>Chemical Infiltration</u>
122	Pu	Trace	Trace
123	Pu	Low	Moderate
125	Pu	Trace	Trace
331	EU	Trace	
334	EU	Trace	
439	DU	Trace	
440	DU	Trace	
441	DU	Trace	Moderate
442	DU	Low	Trace
444	DU	Low	Moderate
447	DU	Low	Low
559	Pu	Moderate	High
663	Pu	Trace	Trace
701	Pu	Low	Trace
707	Pu	Low	Trace
770	Pu	Low	Low
771	Pu	High	High
774	Pu	Moderate	Moderate
776	Pu	High	Low
777	Pu	Moderate	Low
778	Pu	Low	Low
779	Pu	Low	Moderate
865	DU	Low	Low
881	EU	Low	High
883	EU	Low	Trace
884	EU	Trace	
886	Pu	Trace	Trace
889	EU	Low	Moderate
991	Pu	Trace	

\*Type of radioactive infiltration refers only to major radioactive material involved. Other radioactive elements are also involved but to lesser extent.

\*\*Degree of infiltration refers to relative cost of cleanup.

THE FOLLOWING MAPS ARE NOT INCLUDED IN THIS KEY.

- MAP 108 B SERIES HOLDING PONDS
- MAP 11 BURIAL SITES
- MAP 13 ROADWAYS
- MAP 14 PROCESS WASTE SYSTEM
- MAP 14A. PROCESS WASTE LINE LEAKAGE AREAS
- MAP 15 STORAGE TANKS
- MAP 15A X GAS BOTTLE DISPOSAL
- MAP 16 PLUTONIUM ISOPLETHS
- MAP 16A,B ANALYTICAL RESULTS IN PLANT VICINITY
- MAP 17 PLUTONIUM CONTOURS BASED ON KATHREN STANDARDS
- MAP 18 STATEWIDE PLUTONIUM/SOIL RESULTS
- MAP 19. AUSTIN GRID SAMPLES
- MAP 20 SAMPLE WELL LOCATIONS



KEY TO SECTIONAL MAPS

DRAFT

TABLE II


Major Incidents in the Area of Buildings 770, 771, and 774 (See Map 1)

(Note: Pipeline leaks, etc., are discussed separately.)

Prior to 1956, the process waste holding tank located north of Building 771 overflowed on several occasions with minor impact.

- 1956     October: Process waste tanks (Building 774) overflowed, minor environmental infiltration.
- 1957     August: Leaking process waste tanks (Building 774), minor environmental infiltration cleaned up.
- September: Building 771 fire - some environmental infiltration, particularly north and near the hatch on the southwest corner of the building. Actual levels unknown, soil and vegetation samples inconclusive.
- 1958     April: Soil infiltration noted at laundry outfall (Building 773), 17,400 dpm/g.
- 1963     January: Liquid containing plutonium spilled outside Building 774 entrance. Material cleaned up.
- 1964     January: Coveralls containing plutonium found on west dock of Building 771. Levels to 100,000 dpm/100 cm<sup>2</sup> found on dock and in locker room. Cleaned up immediately.
- 1968     May: Sewer line break at Building 771 resulted in sewage lift station tank overflow to Building 773 outfall. Low concentration of radioactive and chemical materials.

- 1970 May: Soil samples collected from Building 773 outfall; approximately 100,000 dpm/g. Plumbing modified in September 1970 and 149 drums of soil removed for off-site disposal. (Removal completed August 30, 1971.)
- 1971 Scrap drum leakage (June and July) resulted in recorded levels to 300,000 dpm/100 cm<sup>2</sup> on about 2,500 square feet of asphalt north of Building 771. Asphalt removed for off-site disposal. In September, construction excavation between Buildings 771 and 774 exposed tunnel which contains process waste line and which at one time was used as an exhaust ventilation duct for Building 774. The exposed cracks in the tunnel were sealed. Eight drums of soil (approximately 24 dpm/g) were removed for off-site disposal in January, 1972.
- September: Building 774 dock - unknown source resulted in estimated levels to 200,000 dpm/100 cm<sup>2</sup>. Thirty-six drums of soil removed for off-site disposal.
- 1972 March: Approximately 500 gallons of plutonium waste (approximately 350,000 dpm/liter) inadvertently released from Building 774. Pond samples showed only slight increase in activity. Started removing soil around Building 774 waste tanks for installation of new inspectable processing tanks.
- August: A punctured scrap box and drum resulted in up to 200,000 dpm/100 cm<sup>2</sup> on approximately 3,600<sup>square</sup> feet inside and approximately 500 square feet outside Building 770. Cleanup began immediately, soil and asphalt removed for off-site disposal.
- 1973 There were no incidents which were considered to have resulted in environmental infiltration.



Map 1A

This map gives an arbitrary indication of possible affected areas as a result of operational incidents and accidents in the Buildings 770-771-774 area. As indicated, low level nitrate and radioactive infiltration is expected. Soil samples of the area justify this low-level assumption, with plutonium values ranging from undetectable to 64.9 dpm/g.

It must also be emphasized that the variables inherent in soil sampling (i.e., particle size, type of soil, physical location, vegetation cover, etc.) and the state-of-the-art do not permit wholesale drawing of conclusions as to levels, accurate isocurie contours, etc. It is the nature of the technology that a "high" sample could be detected immediately adjacent to an undetectable one and vice versa. Where such contours have been derived, by one means or another, they will be incorporated into this report for reference. Wherever possible, however, actual sample results should be the only judgment criterion and will be so presented herein.

E20500

E21000

E21500

E22000

EXTREMELY LOW LEVEL RADIOACTIVE AND CHEMICAL  
INFILTRATION PROBABLE IN NORTH WALNUT CREEK .  
PARTICULARLY FROM (N)20,250 EAST TO PONDS

E

NORTH WALNUT CREEK

PERIMETER ROAD

771

PARKING

770

771

774

N38500

N38000

ARBITRARY INDICATION OF  
EXTENT OF POSSIBLE LOW  
LEVEL RADIOACTIVE AND  
CHEMICAL INFILTRATION AS  
A RESULT OF 771 - 774  
OPERATIONS AND INCIDENTS



Map 2 (Buildings 701, 776-777, 778, and 779)

In June 1964, an explosion within a glovebox in Building 776 resulted in extensive release of plutonium to the interior and some to the exterior, primarily north of that building.

A fire on May 11, 1969, released plutonium to all of Building 776-777 and areas of Buildings 771, 778, and 779. The integrity of the buildings involved, however, remained essentially intact and very little environmental infiltration can be attributed to the actual fire. Subsequent extinguishing efforts, and cleanup did, however, provide some contribution (Map 2A).

These two incidents are primarily responsible for soil infiltration in this area. The majority of the affected soil has either been removed or covered with asphalt. As examples, in September 1969, approximately 320 tons of soil and asphalt (containing an estimated 14 mg Pu) were removed from the west side of Building 776. An asphalt-covered area of about 10,000 square feet, north of Building 776-777, has levels of radioactivity of about 700 dpm/g. When this area was surveyed, no particular "hot spots" were found but the material was somewhat deep in places, particularly around a drain in the dock area. A French drain north of Building 776 may have contributed to some plutonium infiltration below the surface although no surface expression has been noted. Radioactive levels of up to 80,000 dpm/100 cm<sup>2</sup> were noted in October 1971, north of the Building 776 compressor shed directly under the gravel and the soil was subsequently removed for disposal.

More recent incidents, such as process waste backing up into a stool and sink in Building 701 (June 1972) have also contributed some degree of infiltration to the area in the vicinity of that structure. Also there has been some minor spillage of carbon tetrachloride into the soil at the storage tank near the southwest corner of Building 701. No significant environmental consequences are expected from this spillage.

Building 779 was erected over the site of one of the original solar evaporation ponds. During excavation (September 1962) levels of radioactivity ranging from 11 to 75 dpm/g were noted, and later, pools of water in these excavations had levels to 150 dpm/l. The radioactive material involved was mostly uranium.

With the exception of the recent tritium incident and minor involvement in the 1969 fire, only one other major incident of environmental significance has been documented in Building 779. In June of 1969, an improperly opened waste drum resulted in radioactive material spread to the first floor, utility room, dock and adjacent grounds, and walkways east and south of the building, mostly by personnel tracking. Levels up to 50,000 dpm/100 cm<sup>2</sup> were recorded, and a number of drums of soil were subsequently removed for off-site disposal.

Thus the entire Buildings 776-777, 778, and 779 areas (including substructures) must be considered at least partially infiltrated with radioactive materials primarily on the north side of the complex, the west side of Building 776, between Buildings 777 and 779, and the courtyard between Buildings 776-777 and 778.

Some chemical infiltration, notably nitrates, chromate, and particularly in and near Building 776, possible organics (CCl<sub>4</sub>), is to be expected, particularly beneath and north of the buildings.

~80,000 DPM NOTED IN 1971.  
REMOVED.

ABOUT 10,000 SQUARE FEET, ASPHALT COVERED,  
ABOUT 700 DPM/G.

PROCESS WASTE BACKUP, 1972. SOIL  
REMOVED

LOCATION OF OLD SOLAR EVAPORATION  
POND. 11 TO 75 DPM/G NOTED DURING  
CONSTRUCTION. PROBABLE HIGH NITRATE  
LEVELS.

IMPROPERLY OPENED WASTE  
DRUM. UP TO 50,000 DPM  
NOTED, SOIL  
REMOVED.

AREAS AFFECTED  
MAY '69 FIRE...SEE  
FOLLOWING MAP)

776-777

779

778

ARBITRARY "AREA OF CONCERN":  
NITRATES, CHROMATES, SOME B<sub>2</sub>,  
AND LOW LEVEL ORGANIC  
INFILTRATION EXPECTED

ONE SOURCE OF  
RECENT TRITIUM  
INFILTRATION.


E-21,000




E-21,500

N-37,500

E-20,500

## ROOF AND OUTSIDE AREAS



  $10^5$  to  $10^6$  cpm  
  $10^4$  to  $10^5$  cpm  
  $10^3$  to  $10^4$  cpm


EXTERIOR AREAS OF 776-777 AND 778  
AFFECTED IN AFTERMATH OF MAY, 69  
FIRE

Map 3 (Buildings 559 and 707)

The Service Laboratory Facility, Building 559, began operation in March 1968. Original process waste pipelines under the building were made of Pyrex<sup>®</sup> glass to combat a persistent corrosion problem. Operations and natural settling of the building have resulted in several breaks in this glass line, which are discussed in conjunction with Map 14.

Building 707, the newest production complex, has created no known environmental infiltration. Before construction, however, a section of the original process waste line (see Map 14) was removed and some residual material might be in residence. A sampling well (see Map 20) located near the process waste holding tank (between Buildings 707 and 750) has produced slightly elevated nitrate levels, but this could be due to a number of factors. No radioactivity has been detected in these samples, therefore, no leak or infiltration is assumed.

LOCATION OF ORIGINAL  
PROCESS WASTE LINE  
(REMOVED DURING  
707 CONSTRUCTION).



DRAFT

Map 6 (Buildings 439, 440, and 444-447)

Depleted and enriched uranium and beryllium are the principal materials of concern to this area.

In 1953, high winds blew the lids off waste drums and uranium was released to the dock, driveway, and surrounding grounds. Direct count as high as 7,500 dpm/100 cm<sup>2</sup> and smears as high as 350 dpm were reported. The docks and sidewalks were cleaned up and the driveway areas seal-coated. A broken process waste line (June 1966) north of the building resulted in some possible infiltration as did leaking storage drums south of the building. An open ingot storage area east of Building 444 and a metal storage area south of the building have undoubtedly resulted in low-level infiltration of the soil, as has a uranium machine tool storage area west of the building.


Bldg 444

In May 1960, a vacuum collector fire in Building 447 resulted in approximately 44  $\mu$ Ci depleted uranium deposited on the roof of the building. In December 1962, a uranium/beryllium release from Building 444 (due to use of an unfiltered hood) was noted.

Thus, these areas immediately adjacent to Buildings 439, 440, and 444-447, as well as the storage areas noted on Map 6, must be considered radioactively infiltrated to some degree as should the footings and foundations of these buildings.

Chemically, no specific incidents have been noted, but routine generation of nitrates and chromates would indicate at least the possibility of these materials being present in soil under and around these buildings.

1953 INCIDENT RELEASED URANIUM TO DOCK, SIDEWAYS AND DRIVEWAYS,  
CLEANED AND/OR SEAL-COATED.



1960 VACUUM COLLECTOR FIRE  
(447) AND 1962 RELEASE FROM  
UNFILTERED HOOD (444) HAVE  
PROBABLY ADDED TO LEVELS  
IN THE VICINITY OF THESE  
BUILDINGS



Map 7 (Buildings 122, 123, 351, 354, 441, 442, 443, 551, and 554)

Building 122 (Medical Facility), with its extremely low level waste-liquid generation, operated with a 55-gallon drum as a waste tank. Rusting of this drum and subsequent leakage resulted in some low-level infiltration of soil under the building and the removal of a section of the floor inside (southeast corner) the building. Significant infiltration is not suspected and has not been detected in areas around the building.

Building 123 (Health Physics Laboratories) generates low-level radioactive liquid waste as well as chemical wastes. Known or suspected underground waste-line leakage has contributed some material to the soil beneath the building. Leakage, however, also appears to be into the lines due to high hydrostatic pressure, thus minimizing the potential.

Building 441 was originally a laboratory handling small quantities of radioactive material as well as quantities of various chemicals. Thus, the soil and piping beneath the building must be considered suspect in regard to both chemical and radioactive infiltration.

The Laundry, Building 442, is also potentially affected by both radioactive and chemical materials, notably depleted uranium and beryllium, and in 1964 the Laundry was infiltrated by enriched uranium, impregnated in clothes from Building 883. The soil in the vicinity of this building has also been affected by instances of radioactivity release. For example, in December 1963, rag-cleaning barrels stored near the building either leaked or spilled. The liquid drained east into the ditch on the northwest side of the building. Radioactivity was detected as far east as the east end of Building 551. Cleaning efforts and subsequent runoff has reduced concentrations in that area to a low level.

Building 443, the Steam Boiler Plant, has had no known radioactive material involvement. Routine operations do involve chemicals,

DRAFT

particularly sulfuric acid and sodium hydroxide. The only incident of note occurred when a quantity of sulfuric acid was spilled to the environs of the building. The acid drained eastward (on the south side of Building 442) to a trap dug in the center of the lot which is now used for Building 444 parking. This soil in the area would undoubtedly be somewhat acidic, but no adverse effect on the environment has been noted.

A portion of Building 331, the Plant Garage, was at one time used for a special R&D effort involving depleted and enriched uranium. No incidents or releases were noted during this operation and no environmental residue is expected. Due to the repair and storage of vehicles there is possibility of organics such as oil and gasoline in the soil beneath the building.


Building 334, the main Maintenance Shop, was also used for special work involving the shearing of some depleted uranium. Some thorium has also been handled in Building 334, again, with no known incident. No environmental encroachment of any material has been detected or is expected as a result of operations in this building.

The Warehouse, Building 551, and adjacent grounds, have been areas of concern several times. For example, detectable uranium was discovered on the Warehouse floor in April 1953. Uranium chips and turnings were discovered in an aluminum scrap pile near the Warehouse in 1963 and again in 1964. These were removed and the grounds cleaned. In July 1963 and again in 1970, Rocky Flats received equipment and drums from off site which contained uranium above the Rocky Flats acceptable level. In 1970 the entire shipment of 55-gallon drums was returned to that vendor. These and other minor incidents lead to at least suspect areas under and around Buildings 551 and 554 (where the "hot" drums were received). A small drum storage area east of Building 552 is suspect for the same reason.

██████████

DRAFT

There have been some minor leaks and spills from drums and storage containers in the non-radioactive chemical storage area east of Building 551. While a small area might have been affected, quantities involved have been so small that no impact has been noted nor expected. This area is used primarily to store drum quantities of acids, oils, soaps, and solvents.




POTENTIAL ENRICHED OR DEPLETED URANIUM INFILTRATION AREAS. ALTHOUGH UNDETECTED, OPERATIONS PERFORMED IN THE NOTED AREAS MAKE LOW LEVEL INFILTRATION A PROBABILITY

MAP 7

Map 8 (Buildings 865, 883, 886, and 889)

Due to the nature of operations in these buildings, soil infiltration is expected to some degree under and possibly around these buildings. Spills involving uranium in Building 886 have occurred, with an inherent possibility of substructure infiltration. No specific incidents have been documented in the other buildings (with the exception of a January 1969 incident wherein the roofing was blown off Building 889 with no environmental effect). At one time, however, some equipment from a uranium laboratory was stored outside (just east) of Building 883 and west of Building 889. Present practice includes temporary storage of equipment from uranium areas on a pad north of Building 889 prior to processing. Therefore, these would also be areas of interest, although no incident or infiltration has been noted.



Map 9 (Building 881)


Building 881, originally a production building, was partially converted to a general support building in 1964. Although few incidents involving the building have been documented, it represents an area of interest, primarily due to the age of the structure (one of the original plant buildings). Both uranium (east dock February 1960) and plutonium (laboratory area October 1961 and 1968) incidents have been noted in the building and waste lines have been broken with resultant probable infiltration. Low levels of plutonium have been detected in the air tunnel and the cooling tower northeast of the building.

In addition to burial sites (see map), some exterior areas near Building 881 have been involved with radioactive material. An area of several hundred square feet northwest of the building was involved in 1958 when a concrete slab, removed from the east side of Building 776, was deposited there. The slab was broken up and removed and the area cleaned. Conversion activities also resulted in some possible infiltration, primarily to the northeast of the building.

In May 1973, oil (#6 fuel oil) from an undetermined source was discovered on the hillside below Building 881. Prompt action prevented the spread of the oil into Koman Creek or any holding pond. Leak tests on the Building 881 fuel tank and lines (the only known possible sources) did not show any leakage, but to date the oil continues to emerge through the Building 881 footings drain. A concrete skimmer dam has been built to trap the oil, which drains in extremely small quantities. The oil-soaked straw which was used to trap the material, as well as most of the soil involved, has been removed.

CONCRETE SLAB STORAGE (TEMPORARY). CLEANED.

LOW-LEVEL Pu NOTED IN AIR TUNNEL AND COOLING TOWER.





DRAFT

Map 10 (Buildings 991 and 995)

Building 991 and the associated storage vaults (tunnels 996, 997, 998, and 999) are also original plant structures and thus under suspicion due to age. Incidents involving very small quantities of plutonium, as well as uranium and beryllium, have been noted in Building 991, and extensive research activities have undoubtedly spread some trace concentrations of materials in the vicinity of the building.

Although radioactive materials have been continuously stored in the vault areas, routine surveys have indicated that with the possible exception of 996, which might be slightly uranium infiltrated, the vaults have remained remarkably "cold." Any environmental leakage has been in rather than out as determined by salt infiltration into the tunnel areas.

Building 995, the Sewage Treatment Facility, has historically been the recipient of effects from incidents in other areas of the plant. For example, the overflow incident in Building 701 (June 1972) contributed elevated levels of radioactive material (plutonium) to the Building 995 effluent and drying beds. In 1972, plumbing changes were initiated to channel all wastes through Building 995. The increased load thus generated lead to increasing radioactivity levels in sewage sludges which are shipped off site for disposal. Surge overflows and incidents involving spillage of the dried or drying sludge have created an area of concern which extends from the outlet of the South Walnut Creek diversion culvert to and through the B-series holding ponds, and surrounding the treatment area including both sides of the perimeter road east of Building 995.

The original process waste outfall (from Building 774) was located just west of the Building 995 outfall. The line was later rerouted to discharge further upstream. In 1972, the line was routed through Building 990 and then, through the sanitary sewer lines, into Building 995. The abandoned line is still in place. The area of the original outfall as well as the abandoned line are noted on Map 10 as areas of interest

[REDACTED]

11/11/11

Map 10A details soil sample results from a recent survey in the vicinity of Building 995. These results are only illustrative, as actual levels vary with flow rates through the creek bed.

The B-series holding ponds are located in this area. Sediment sample results from all holding ponds taken in 1971 by the Radiobiology Department of Colorado State University (CSU), are detailed in Map 10B. The values given are questionable due to the analytical technique employed. Values shown may be high due to the presence of isotopic uranium or low due to inadequate sampling technique.

Regardless of the accuracy of the values shown in Map 10B, the B-series ponds must be considered an area of concern regarding both chemical and radioactive infiltration. Studies have shown that these ponds have performed what they were designed to do, provide residence time and holding capacity to allow materials to settle out, and in so doing have become infiltrated with those materials. It should be noted that the concentrations decrease throughout the system, which is further indication of the effectiveness of the ponds.

INFILTRATED AREA DUE TO  
LONG TERM OPERATIONS.  
SEE FOLLOWING MAP.

ORIGINAL PROCESS WASTE OUTFALL.  
LINE IS STILL IN PLACE, CAPPED...  
POTENTIAL INFILTRATION CONSIDERED  
SLIGHT

SEWAGE HOLDING TANKS.


SOME MINOR INCIDENTS INVOLVING Pu, U, AND  
Be HAVE BEEN REPORTED IN 991. INVOLVEMENT  
SHOULD BE VERY LIGHT BOTH UNDER AND  
AROUND BUILDING, AND IN STORAGE TUNNELS.


AREA OF CONCERN DUE TO OVERFLOWS,  
SPILLS, ETC. INFILTRATED SEWAGE SLUDGES  
ARE SHIPPED OFF-SITE FOR DISPOSAL.

OIL BURNING PIT No. 2

PALLET DESTRUCTION AREA.

MOUND AREA





[REDACTED]

JAN 11 1974

Map 14 (Process Waste Lines)

Map 14 details the process waste system at Rocky Flats, tankage, and possible major materials present in those tanks.

In an effort to reduce corrosion, original process waste lines had a saran-lined inner pipe enclosed in a protective clay tile pipe. This saran lining was very susceptible to leakage. Leaks were noted in 1952 and by 1956 most of the original pipe had been replaced with stainless steel. To date, all but about 600 feet of this line has been replaced. The remaining section was thoroughly tested in 1971 and was not leaking.

An exhaustive leak-test survey was conducted in 1971 by an off-site contractor. This leak test was conducted under pressure and disclosed several minor leaks, mostly in low-pressure (essentially gravity-flow) lines. Repairs were started immediately. Attempts were made to repair the higher pressure leaks in place. When these attempts failed, an alternate line was installed. The low leak-rate detected around joints in the gravity flow line is to be expected since this type line is not designed to operate under pressure. Lines have been observed under operational pressures and no leakage observed.

With the exception of Building 559 and between Buildings 776 and 774 as noted below, no radioactive infiltration has been detected outside the lines even in the vicinity of the leaks, but some chemical infiltration, particularly nitrate solutions, is probable. These areas are noted as "areas of concern" on Map 14A primarily in the interests of conservatism. As pipelines have been replaced, soils and liquids have been monitored and, with the noted exceptions, have not resulted in detectable concentrations. However, extremely low-level radioactive and chemical infiltration must be presumed.

Process waste lines between Buildings 776-777, 779, and 774 and between Buildings 771 and 774 have broken and leaked several times. Valve

leakage has occurred in the valve pit near waste storage tank 207. Although noted incidents in this area have resulted in clean up (soil removal), residual infiltration is a surety. Thus the entire area from Buildings 776-777 and 779 Complex to Building 774 should be considered an area of concern as shown on Map 14B.


Building 559, a Service Laboratory Facility commissioned in 1968, was originally built with Pyrex<sup>®</sup> glass waste lines. Less than one year later, a break was discovered in the line from the building to the pump house. Several hundred square feet of infiltrated soil was removed as radioactive waste as a result of the leakage. This same type of line is buried beneath Building 559. In 1972, the south half of this two section line was discovered to be leaking. A PVC pipe bypass was installed. Vertical core sections taken under the building confirm some infiltration directly under the pipeline (approximately 250 dpm/g). Core samples taken outside the building, however, did not detect measurable quantities, indicating that any infiltration is contained beneath the building proper.

The remaining waste lines in Building 559 were static-leak tested following the bypass installation. Current plans call for yearly static-test to prevent recurrence.


Abandoned process waste lines under Building 707 (removed), under the new Filter Plenum for Building 779 (removed), and at the original outfall near Building 990 (still in place) as well as smaller sections elsewhere (i.e., west of Building 771) should be noted. Although not considered as sources for further contributions, some soil has been infiltrated in the immediate vicinity of the lines or original locations.



— PROCESS WASTE LINES  
 ⊕ AREAS OF CONCERN DUE TO KNOWN  
 LINE LEAKAGE  
 - - - - - ARBITRARY DEFINITION OF POSSIBLE  
 AREAS OF CONCERN DUE TO KNOWN,  
 SUSPECT, OR POSSIBLE LEAKAGE,  
 BREAKAGE, SPILLAGE, ETC.







MAP 14B



TANK LIST  
Rockwell International

by  
Mr. Bob James

1988

ID	BLDG	CONTENTS	SIZE (gal)	MAT'L	CATH	TEST/INSP	INST'L	APP'L	SMU	USER & EXTENSION	REMARKS 1
No	No				PROT	DATE	DATE	REG	No		
1	120 SE	Diesel	1,000 CS	85 RCRA I					R	RINGER	4656
2	124 S	Diesel	500 FG	71 RCRA I	NA				R	RINGER	4656
3	127 W	Diesel No 2, EG 127	550 FG	78 RCRA I	NA				R	RINGER	4656
4	381 N	Diesel, EG 374 & 371	47,500 FG	80 RCRA I					C	ROSS	2539 Size & Instl date Req Verification
5	331 N 1	#2 Fuel Oil/Diesel	6,000 FG	71 RCRA I	NA				R	ERWIN	2500
6	331 N 1A	#2 Fuel Oil/Diesel	6,000 FG	71 RCRA I	NA				R	ERWIN	2500
7	331 N 2	Gasoline	6,000 FG	71 RCRA I	NA				R	ERWIN	2500 OS '83, Abandoned in Place,
8	331 N 3	Unleaded Gasoline	18,000 CS	76 RCRA I					R	ERWIN	2500 check volume
9	443 SE	Diesel, EG	1,500 CS	70 RCRA I					B	ABBOTT	2535
10	443 E-2	#6 Fuel Oil	20,000 CS	52 NA					B	ABBOTT	2535 See Tank No 12, Not Reg UST
11	443 E 3	#6 Fuel Oil	20,000 CS	52 NA					B	ABBOTT	2535 See Tank No 12, Not Reg UST
12	443 E 4	#6 Fuel Oil	20,000 CS	67 RCRA C					B	ABBOTT	2535 CLOSURE PLAN FILED W/CDH 7/1/88
13	443 NE	Diesel, EG	2,133 FG	76 RCRA I	NA				157 1 B	ABBOTT	2535
14	559 NE	#2 Fuel Oil, EG 559	1,000 CS	67 RCRA I					B	PHIPPS	2363
15	562 E	#2 Fuel Oil/Diesel	3,000 CS	75 RCRA I					159 B	PHIPPS	2363
16	709 NW	#2 Diesel, EG 709&711	4,000 CS	68 RCRA I					B	PHIPPS	2363
17	718 SE	Diesel	4,000 CS	69 RCRA I					B	PHIPPS	2363
18	727 W	#2 Diesel, EG 727	3,000 CS	75 RCRA I					150 8 J	REED	2614
19	729 ESE	#2 Diesel, EG 729	650 CS	74 RCRA I					J	REED	4240
20	771 SE	Diesel	3,000 CS	52 RCRA I					139 1 J	QUAYLE	2253 OS 72, Abandoned in Place, May
21	771 S	Diesel, EG 715	5,260 FG	73 RCRA I	NA				J	QUAYLE	2253
22	776 N	#2 Fuel Oil/Diesel	1,000 CS	85 RCRA I					118 1 J	REED	2614 Verify volume
23	776 NW	Diesel	500 CS	68 NA					118 1 J	REED	2614 Above Ground Tank
24	779 NE	#2 Diesel, EG 779	500 CS	75 RCRA I					J	REED	2614
25	827 S	#2 Diesel, EG 827	2,000 CS	71 RCRA I					J	LYONS	
26	881 A NE	#2 Fuel Oil	1,000 CS	56 NA					J	LYONS	OS 76, Removed & disposed
27	881 S	Diesel	2,100 CS	56 NA					yes J	LYONS	Drawings Con't 37004 X54, 200
28	881 S 1A	#6 Fuel Oil	21,000 CS	56 NA					yes J	LYONS	Drawings Con't 37004 X54, 200
29	881 S 2A	#6 Fuel Oil	21,000 CS	56 NA					yes J	LYONS	Drawings Con't 37004 X54, 200
30	881 S 3A	#6 Fuel Oil	21,000 CS	56 NA					yes J	LYONS	Drawings Con't 37004 X54, 200
31	883 N	#2 Fuel Oil/Diesel	500 CS	58 NA					J	LYONS	OS 79

ID	BLDG	CONTENTS	REMARKS 2	REMARKS 3	PENDING ACTION	DRAWINGS
No	No					
1	120 SE	Diesel			Tank Thtness Test & Est	37184 026
2	124 S	Diesel			Tank Thtness Test & Est	
3	127 W	Diesel No 2, EG 127 Records @ 124&130			Tank Thtness Test & Est	25741 6, D02
4	381 N	Diesel, EG 374 & 371Records @ 124&130			Tank Thtness Test & Est	25001 117
5	331 N 1	#2 Fuel Oil/Diesel			Tank Thtness Test & Est	24974 3, 8, 6, 28134 01
6	331 N 1A	#2 Fuel Oil/Diesel			Tank Thtness Test & Est	24974 3, 8, 6, 28134 01
7	331 N 2	Gasoline	Emptied, Inventory records 331		EA During Removal	24974 3, 8, 6
8	331 N 3	Unleaded Gasoline	Salvaged Propane Tank ??		Tank Thtness Test & Est	24974 3, 28134 01, -001, 02, 03
9	443 SE	Diesel, EG	Loc So of Door 3T, Bldg 443		Tank Thtness Test & Est	20555 76, 77
10	443 E 2	#6 Fuel Oil	Heating Oil	Planned removal 1991 92	Delete fm Sub I List	14262 3
11	443 E 3	#6 Fuel Oil	Heating Oil	Planned removal 1991-92	Delete fm Sub I List	14262-3
12	443 E 4	#6 Fuel Oil	Contents Compressor Oils and Solventure area, plan submit 7/1/88		Delete fm Sub I List	14262 3
13	443 NE	Diesel, EG			Tank Thtness Test & Est	28082 1, 2, 27058 6, 28081-2, 28080 1
14	559 NE	#2 Fuel Oil, EG 559 Inventory records Exist			Tank Thtness Test & Est	
15	562 E	#2 Fuel Oil/Diesel Inven Recds Exist			Tank Thtness Test & Est	23450 203, 205, 25608 1, 23451-201
16	709 NW	#2 Diesel, EG 709&711Inv Rcds Exist			Tank Thtness Test & Est	RF BZ 20221 04, 20221 09
17	718 SE	Diesel	Verify Existence??????		Investigation by FE	
18	727 W	#2 Diesel, EG 727 Inven Recds Exist			Tank Thtness Test & Est	23470 405, 23471-405
19	729 ESE	#2 Diesel, EG 729 Inven Recds Avail			Tank Thtness Test & Est	19675 4, 19675-22
20	771 SE	Diesel	Contain Waste Product!!!	*** EXPEDITE REMOVAL ***	EA During Removal	1-13295 71
21	771 S	Diesel, EG 715 Inven Rcds Exist			Tank Thtness Test & Est	25486 001, 25483 003
22	776 N	#2 Fuel Oil/Diesel Site Insp by FE			Tank Thtness Test & Est	28165 027, 37515 10
23	776 NW	Diesel			Delete fm Sub I List	
24	779 NE	#2 Diesel, EG 779 Inven Recds Avail			Tank Thtness Test & Est	E 14019 5
25	827 S	#2 Diesel, EG 827 Inven Rcds Avail			Tank Thtness Test & Est	21154 06
26	881 A NE	#2 Fuel Oil			Delete fm Sub I List	28084 1
27	881 S	Diesel	Filled w/ Conc, 1977		Delete fm Sub I List	28086 1, 2, 37004 251, -202,
28	881 S 1A	#6 Fuel Oil	Filled w/ Conc, 1977		Delete fm Sub I List	28086 1, 2, 37004 251, 202,
29	881 S-2A	#6 Fuel Oil	Filled w/ Conc, 1977		Delete fm Sub I List	28086 1, 2, 37004 251, 202,
30	881 S-3A	#6 Fuel Oil	Filled w/ Conc, 1977		Delete fm Sub I List	28086 1, 2, 37004 251, 202,
31	883 N	#2 Fuel Oil/Diesel Filled w/Sand 1979			Delete fm Sub I List	25673 1

ID	BLDG	CONTENTS	SIZE (gal)	MAT'L	CATH	TEST/INSP	INST'L	APPL'L	SMMU	USER & EXTENSION	REMARKS 1
No	No				PROT	DATE	DATE	REG	No		
32	920 NW	Diesel, EG 920	1,000 CS	85 RCRA I						R RINGER	4656
33	989 E	Diesel, EG989	3,000 CS	73 RCRA I						R RINGER	4656 Previously listed as 898, typo
34	371 FW1	Firewater(Clean w/N)	3,000 CS	76 Non RCRA						C ROSS	2439 Room 2011 near column V6
35	371 FW2	Firewater(Clean w/N)	3,000 CS	76 Non-RCRA						C ROSS	2539 Room 2307
36	429 1	Plenum Deluge	3,000 Conc	53 RCRA C	NA						OS 6/82 PER W EDWARDS as proc
37	561 FW	Empty	3,000 SS	73 NON RCRA159	NA					A SEMPBON	2220 Free standing non UST
38	728 1	Plenum Deluge	25,000 Conc	53 RCRA C	NA					150 1 J QUAYLE	2253 OS as UST 9/84
39	728 2	Plenum Deluge	25,000 Conc	53 RCRA C	NA					150 1 J QUAYLE	2253 OS as UST 9/84
40	730 1	Plenum Deluge	22,500 Conc	56 RCRA C	NA					118 1 J REED	2614 Drawings Con't 28714 X11
41	730 2	Plenum Deluge	22,500 Conc	56 RCRA C	NA					118 1 J REED	2614 Drawings Con't 28714 X11
42	730 3	Radionuclides	4,500 Conc	56 RCRA C	NA					139 1 J REED	2614 Drawings Con't 28714 X11
43	730 4	Radionuclides	4,500 Conc	56 RCRA C	NA					139 1 J REED	2614 Drawings Con't 28714-X11
44	730 CT	Carbon Tetrachloride	5,000 CS	53 NA						118 1 J REED	2614 OS as UST '81
45	731 1	Double Containment	2,000 Conc	60 RCRA C	NA					J GEORGE	2330 OS as UST 7/82
46	731 2	Double Containment	2,000 Conc	60 RCRA C	NA					J GEORGE	2330 OS as UST 7/82
47	731 FW	Firewater	1,300 SS	79 NA						J GEORGE	2330 Free standing non UST
48	771 C	Floor Drain Sump Rad	500 SS	68 RCRA I	NA					J QUAYLE	2253 OS 84, aka T 36
49	771 FW	Plenum Deluge	3,000 CS	72 NA						J QUAYLE	2253 Free standing non UST
50	774	Radionuclides	30,000 Conc	53 RCRA C	NA					J GONZALES	Gravel Filled w/ Conc Cap, 7/82
51	774 T 66	Radionuclides	12,550 Conc	52 RCRA C	NA					J REED	2614 aka T40
52	774 T 67	Radionuclides	12,550 Conc	52 RCRA C	NA					J REED	2614 aka T66
53	774 T 68	Radionuclides	30,850 Conc	57 RCRA C	NA					J REED	2614 aka T67
54	774 T 40	Radionuclides	7,200 Conc	52 RCRA C	NA					J REED	2614 aka T68
55	776 FW	Firewater	3,000 FG	71 NA							Free standing non UST
56	782 FW	Firewater	3,000 SS	73 NA						150 8 J REED	2614 Free standing non UST
57	828 1	Radionuclides	250 CS	64 RCRA C						164 2	Abandoned 1978, aka T-21
58	828 2	Radionuclides	250 CS	64 RCRA I						164 2	OS 78, VERIFY MAT'L
59	865 1	Radionuclides	3,000 Conc	70 NA	NA					J NORRIS	4467 OS 5/82, closure pre 84
60	865 2	Radionuclides	3,000 Conc	70 NA	NA					J NORRIS	4467 OS 5/82, closure pre 84
61	875 FW	Plenum Deluge	3,000 SS	72 NA	NA					R ROTH	2989 Free standing non UST
62	889 W1	Radionuclides	1,000 Conc	66 RCRA C	NA					L CHAVEZ	2421 OS 5/83, aka T 28

ID	BLDG	CONTENTS	REMARKS 2	REMARKS 3	PENDING ACTION	DRAWINGS
No	No					
32	920 NW	Diesel, EG 920	Inven Rclds Avail		Tank Thtness Test & Est	37178 021
33	989 E	Diesel, EG989	Inv Rclds Avail		Tank Thtness Test & Est	23495 402, 23490 401, 23491 401
34	371 FW1	Firewater(Clean w/N)			Delete fm Sub I List	25155 305
35	371 FW2	Firewater(Clean w/N)			Delete fm Sub I List	25155 305
36	429 1	Plenum Deluge	Waste Line, aka T 2	Unable To Locate	Investigation by FE	
37	561 FW	Empty			Delete fm Sub I List	23450 204, 23451 202
38	728 1	Plenum Deluge		aka T-8	Delete fm Sub I List	23815 2
39	728 2	Plenum Deluge		aka T-8	Delete fm Sub I List	23815 2
40	730 1	Plenum Deluge	OS as UST 12/82, aka T 9	Currently under RCRA Closure	Delete fm Sub I List	27830 D16, 25847 3, 28714 401,
41	730 2	Plenum Deluge	OS as UST 12/82, aka T 9	Currently under RCRA Closure	Delete fm Sub I List	27830 D16, 25847 3, 28714 401,
42	730 3	Radionuclides	OS as UST 12/82, aka T 10	Currently under RCRA Closure	Delete fm Sub I List	27830 D16, 25847 3, 28714-401,
43	730 4	Radionuclides	OS as UST 12/82, aka T-10	Currently under RCRA Closure	Delete fm Sub I List	27830 D16, 25847 3, 28714-401,
44	730 CT	Carbon Tetrachloride	Removed pre 11/4/84		Delete fm Sub I List	
45	731 1	Double Containment	aka T-11		Delete fm Sub I List	27097-1, 27367 4, 6, 13, 1, 23815 1
46	731 2	Double Containment	aka T 11		Delete fm Sub I List	27097 1, 27367 4, 6, -13, -1, 23815 1
47	731 FW	Firewater			Delete fm Sub I List	
48	771 C	Floor Drain Sump	RadOld Process Waste Tank Currently	under RCRA Closure	Investigation by FE	
49	771 FW	Plenum Deluge			Delete fm Sub I List	26629 2, 25958 002, -04
50	774	Radionuclides	Removed Pre 11/4/84	aka T-14	Delete fm Sub I List	26629 1, RF 74 654 E, RF 74S4 B
51	774 T 66	Radionuclides	RCRA C, Replacement design in	progress, S Sisk	Delete fm Sub I List	
52	774 T 67	Radionuclides	RCRA C, Replacement design in	progress, S Sisk	Delete fm Sub I List	
53	774 T 68	Radionuclides	RCRA C, Replacement design in	progress, S Sisk	Delete fm Sub I List	
54	774 T 40	Radionuclides	RCRA C, Replacement design in	progress, S Sisk	Delete fm Sub I List	
55	776 FW	Firewater	verify volume	aka T76	Delete fm Sub I List	25846 1S, 13S
56	782 FW	Firewater			Delete fm Sub I List	23474 302, 23470 304, 23471 301
57	828 1	Radionuclides	Old Process Waste Tank Currently	under RCRA Closure	Delete fm Sub I List	23484 303, 23480 301
58	828 2	Radionuclides	Removed from Ground????	chk drw maybe 2 tanks see RCRA PtB	Investigation by FE	23484 303, 23480 301
59	865 1	Radionuclides	Converted to occupied space	aka T23, under RCRA Closure	Delete fm Sub I List	26377 4, 26378 3, X01, 21151 04, 14
60	865 2	Radionuclides	Converted to occupied space	aka T23, under RCRA Closure	Delete fm Sub I List	26377 4, 26378 3, X01, 21151 04, 14
61	875 FW	Plenum Deluge			Delete fm Sub I List	23484-302
62	889 W1	Radionuclides	Old Process Waste Tank Currently	under RCRA Closure	Delete fm Sub I List	26378 4

ID	BLDG	CONTENTS	SIZE (gal)	MAT'L	CATH	TEST/INSP	INST'L	APP'L	SWMU	USER & EXTENSION	REMARKS 1
No	No				PROT	DATE	DATE	REG	No		
63	889 W2	Radionuclides	1,000 Conc	NA				66 RCRA C	L	CHAVEZ	2421 OS 5/83, aka T 28
64	985 FW	Plenum Deluge	3,000 SS	NA				73 NA	173 J	REED	2614 Free standing non-UST
65	443 E 1	No 6 fuel oil	20,000 CS					66 RCRA C	B	Abbott	2535 See Tank No 12, Not Reg UST
66	881 SE	No 2 Diesel, EG 881	5,000					86 RCRA I	J	Lyons	
67	111 E	GASOLINE						RCRA I			Removed 78, not reported as UST
68	331 S1	Fuel Oil						RCRA I			Removed 76, not reported as UST
69	331 S2	Fuel Oil						RCRA I			Removed 76, not reported as UST
70	771 S2	No 6 Fuel Oil						RCRA I			Removed 85, Not reported as UST
71	771 S3	No 6 Fuel Oil						RCRA I			Removed 85, Not reported as UST
72	771 S4	No 6 Fuel Oil						RCRA I			Removed 85, Not reported as UST
73	776 S	No 2 Fuel Oil						RCRA I			Removed 85, Not reported as UST
74	778 N	Diesel						RCRA I			Removed 85, Not reported as UST
75	991 SE	Fuel Oil						RCRA I			Removed 85, Not reported as UST
76	776							RCRA I			Removed 86, Not reported as UST
77	122 T1		800 SS					55 RCRA C			next to tank no 22
78	441 T3		3,000 Conc					52 RCRA C			Removed Jan 84
79	444 T4,1		Conc					62 RCRA C			
80	444 T4,2		Conc					62 RCRA C			
81	444 T5,1		4,000 STL					52 RCRA C			
82	444 T5,2		4,000 STL					52 RCRA C			
83	444 T5,3		4,000 STL					52 RCRA C			
84	444 T5,4		4,000 STL					52 RCRA C			
85	444 T5,5		4,000 STL					52 RCRA C			
86	444 T6,1		400 Conc					52 RCRA C			
87	444 T6,2		400 Conc					52 RCRA C			
88	528 T7		Conc					RCRA C			
89	771 T12,1		20,000 Conc					52 RCRA C			
90	771 T12,2		20,000 Conc					52 RCRA C			
91	774 T13		600 Conc					52 RCRA C			
92	774 T15,1		3,750 Conc					69 RCRA C			Removed 1970
93	774 T15,2		3,750 Conc					69 RCRA C			Removed 1970



ID	BLDG	CONTENTS	REMARKS 2	REMARKS 3	PENDING ACTION	DRAWINGS
No	No					
63	889 W2	Radionuclides	Old Process Waste Tank Currently	under RCRA Closure	Delete fm Sub I List	26378 4
64	985 FW	Plenum Deluge			Delete fm Sub I List	23490 302
65	443 E 1	No 6 fuel oil	Heating Oil		Delete fm Sub I List	14262 3
66	881 SE	No 2 Diesel, EG 881***REPORT TO CDH***		Planned removal 1991 92	Tank Thtness Test & Est 37004 251, 202, 209, 550, 551	
67	111 E	GASOLINE			No Action	
68	331 S1	Fuel Oil			No Action	
69	331 S2	Fuel Oil			No Action	
70	771 S2	No 6 Fuel Oil	Possible Space Heat		Report to CDH & EA Unless Sp Heat	
71	771 S3	No 6 Fuel Oil	Possible Space Heat		Report to CDH & EA Unless Sp Heat	
72	771 S4	No 6 Fuel Oil	Possible Space Heat		Report to CDH & EA Unless Sp Heat	
73	776 S	No 2 Fuel Oil	Possible Space Heat		Report to CDH & EA Unless Sp Heat	
74	778 N	Diesel	****REPORT TO CDH****		EA	
75	991 SE	Fuel Oil	Possible Space Heat		Report to CDH & EA Unless Sp Heat	
76	776		per Jim Luter		Investigation by FE	
77	122 T1		Curr under RCRA Closure		No Action	
78	441 T3		Old Process Waste Tank Currently	under RCRA Closure	No Action	
79	444 T4,1		Old Process Waste Tank Currently	under RCRA Closure	No Action	
80	444 T4,2		Old Process Waste Tank Currently	under RCRA Closure	No Action	
81	444 T5,1		Old Process Waste Tank Currently	under RCRA Closure	No Action	
82	444 T5,2		Old Process Waste Tank Currently	under RCRA Closure	No Action	
83	444 T5,3		Old Process Waste Tank Currently	under RCRA Closure	No Action	
84	444 T5,4		Old Process Waste Tank Currently	under RCRA Closure	No Action	
85	444 T5,5		Old Process Waste Tank Currently	under RCRA Closure	No Action	
86	444 T6,1		Old Process Waste Tank Currently	under RCRA Closure	No Action	
87	444 T6,2		Old Process Waste Tank Currently	under RCRA Closure	No Action	
88	528 T7		Old Process Waste Tank Currently	under RCRA Closure	No Action	
89	771 T12,1		Old Process Waste Tank Currently	under RCRA Closure	No Action	
90	771 T12,2		Old Process Waste Tank Currently	under RCRA Closure	No Action	
91	774 T13		Old Process Waste Tank Currently	under RCRA Closure	No Action	
92	774 T15,1		Old Process Waste Tank Currently	under RCRA Closure	No Action	
93	774 T15,2		Old Process Waste Tank Currently	under RCRA Closure	No Action	

ID	BLDG	CONTENTS	SIZE (gal)	MAT'L	CATH	TEST/INSP	INST'L	APP'L	SWMU	USER & EXTENSION	REMARKS 1
No	No				PROT	DATE	DATE	REG	No		
94	774	T16,1	14,000	Conc				52	RCRA	C	Abandoned 1970
95	774	T16,2	14,000	Conc				52	RCRA	C	Abandoned 1970
96	774	T17,1	7,500	Conc				69	RCRA	C	Removed 1970
97	774	T17,2	7,500	Conc				69	RCRA	C	Removed 1970
98	774	T17,3	7,500	Conc				69	RCRA	C	Removed 1970
99	774	T17,4	7,500	Conc				69	RCRA	C	Removed 1970
100	778	T18		Conc					RCRA	C	Removed Oct '82
101	779	T19,1	1,000	Conc				64	RCRA	C	Decon & Converted to non UST 12/82
102	779	T19,2	1,000	Conc				64	RCRA	C	Decon & Converted to non UST 12/82
103	779	T20,1	8,000	Conc				64	RCRA	C	Decon & Converted to non UST 12/82
104	779	T20,2	8,000	Conc				64	RCRA	C	Decon & Converted to non-UST 12/82
105	887	T24,1	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
106	887	T24,2	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
107	887	T24,3	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
108	887	T24,4	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
109	887	T24,5	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
110	887	T24,6	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
111	887	T24,7	2,700	SS				52	RCRA	C	Decon & Converted to new sys 12/80
112	883	T25,1	750	STL				52	RCRA	C	Converted to new sys 8/84
113	883	T25,2	750	STL				52	RCRA	C	Converted to new sys 8/84
114	883	T26,1	1,000	STL				66	RCRA	C	Converted to new sys 8/84
115	883	T26,2	1,000	STL				66	RCRA	C	Converted to new sys 8/84
116	883	T26,3	1,000	STL				66	RCRA	C	Converted to new sys 8/84
117	886	T27	300	STL					RCRA	C	Abandoned 1978
118	207	T29	200,000	STL				50	RCRA	C	
119	731	T30		Conc					RCRA	C	Cannot Locate in Field
120	990	T31		STL					RCRA	C	Currently in use process waste sys
121	887	T32		Conc					RCRA	C	Converted to new MP Sys, 12/80
122	561	T33	5,000	SS					RCRA	C	Removed 7/82
123	561	T34,1	5,000	SS				69	RCRA	C	Converted to new MP Sys, 7/82
124	561	T34,2	5,000	SS				69	RCRA	C	Converted to new MP Sys, 7/82

## DRAWINGS

## PENDING ACTION

## REMARKS 3

## REMARKS 2

## CONTENTS

ID BLDG  
No No

94	774 T16,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
95	774 T16,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
96	774 T17,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
97	774 T17,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
98	774 T17,3	Old Process Waste Tank Currently	under RCRA Closure	No Action
99	774 T17,4	Old Process Waste Tank Currently	under RCRA Closure	No Action
100	778 T18	Old Process Waste Tank Currently	under RCRA Closure	No Action
101	779 T19,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
102	779 T19,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
103	779 T20,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
104	779 T20,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
105	887 T24,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
106	887 T24,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
107	887 T24,3	Old Process Waste Tank Currently	under RCRA Closure	No Action
108	887 T24,4	Old Process Waste Tank Currently	under RCRA Closure	No Action
109	887 T24,5	Old Process Waste Tank Currently	under RCRA Closure	No Action
110	887 T24,6	Old Process Waste Tank Currently	under RCRA Closure	No Action
111	887 T24,7	Old Process Waste Tank Currently	under RCRA Closure	No Action
112	883 T25,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
113	883 T25,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
114	883 T26,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
115	883 T26,2	Old Process Waste Tank Currently	under RCRA Closure	No Action
116	883 T26,3	Old Process Waste Tank Currently	under RCRA Closure	No Action
117	886 T27	Old Process Waste Tank Currently	under RCRA Closure	No Action
118	207 T29	Old Process Waste Tank Currently	under RCRA Closure	No Action
119	731 T30	Old Process Waste Tank Currently	under RCRA Closure	No Action
120	990 T31	Old Process Waste Tank Currently	under RCRA Closure	No Action
121	887 T32	Old Process Waste Tank Currently	under RCRA Closure	No Action
122	561 T33	Old Process Waste Tank Currently	under RCRA Closure	No Action
123	561 T34,1	Old Process Waste Tank Currently	under RCRA Closure	No Action
124	561 T34,2	Old Process Waste Tank Currently	under RCRA Closure	No Action

ID	BLDG	CONTENTS	SIZE	MAT'L	CATH	TEST/INSP	INST'L	APPL	SWMU	USER & EXTENSION	REMARKS 1
No	No		(gal)		PROT	DATE	DATE	REG	No		
125	561	T35		Conc				69	RCRA	C	Abandoned 7/82
126	771	T37		Conc					RCRA	C	Cannot locate in field
127	779	T38	1,000	Conc					RCRA	C	Converted to new sys '82
128	881	T39,1	250	SS				52	RCRA	C	Abandon date unk, Loc in Rm 114A
129	881	T39,2	250	SS				52	RCRA	C	Abandon date unk, Loc in Rm 114A
130	881	T39,3	250	SS				52	RCRA	C	Abandon date unk, Loc in Rm 114A
131	881	T39,4	250	SS				52	RCRA	C	Abandon date unk, Loc in Rm 114A

the Rocky Mountain Arsenal in the 1960s and possible surface rupture on the Golden Fault approximately 600,000 years ago (Kirkham and Rogers, 1981)

## SECTION 4

### SITE GEOLOGY

Presented below are results of the geologic site investigation conducted in the vicinity of the Original Process Waste Lines in 1986 and 1987. The section begins with detailed descriptions of surficial (Section 4.1) and bedrock (Section 4.2) geology including lithologies, thicknesses, and extent of materials.

Information for these discussions was obtained from previous studies, aerial photographs, 46 monitor well boring logs, 16 shallow borings, and field mapping. Plate 4-1 shows the location of all monitoring wells at the Rocky Flats Plant, and Plate 4-2 presents monitor well locations in the study area. Geologic logs of all boreholes and wells in the vicinity of the Original Process Waste Lines along with well completion data sheets are located in Appendix A.

It is important to note that it is not known to what depth the Original Process Waste Lines were placed. They are believed to be within the surficial materials, but at this time no data are available to verify this assumption.

#### 4.1 SURFICIAL GEOLOGY

Surficial materials in the Original Process Waste Lines Area consist of the Rocky Flats Alluvium, colluvium, valley fill alluvium, disturbed ground, and artificial fill unconformably overlying bedrock (Plate 4-3). In addition, there are a few isolated exposures of claystone and sandstone bedrock located along slopes and the road cut directly east of the Perimeter Security Zone.

The Plant is located on a terrace which is capped by Rocky Flats Alluvium Colluvium (slope wash) covers the hillsides of the terrace, and valley fill alluvium is present in the drainages of North and South Walnut Creeks. Much of the area adjacent to the solar ponds is disturbed ground due to construction of the ponds, roads, the Perimeter Security Zone (PSZ) fence, nearby buildings, and the French drain system. The area around Building 881 consists of fill material derived from the excavation of Building 881 and also from materials placed at SWMU 130 from the 1969 fire cleanup and is represented on Plate 4-3 as Qaf.

#### 4.1.1 Rocky Flats Alluvium

The Quaternary Rocky Flats Alluvium is the oldest and topographically highest alluvial deposit of the Rocky Flats Plant, it is Nebraskan in age (Scott, 1965). The Rocky Flats Alluvium occurs at an elevation of approximately 5,950 feet above mean sea level in the vicinity of the solar ponds. The Rocky Flats Alluvium is a series of coalescing alluvial fans deposited by braided streams (Hurr, 1976). The erosional surface (pediment) on which the alluvium was deposited slopes gently eastward truncating the Arapahoe Formation at the Solar Evaporation Ponds.

Following deposition of the Rocky Flats Alluvium, eastward flowing streams began dissecting the deposit by headward erosion and lateral planation. All of the alluvium was eroded in the drainages of North and South Walnut Creeks, and the terrace on which the ponds are located remained. Colluvium and valley fill alluvium were subsequently deposited along the slopes and in drainages, respectively. Rocky Flats Alluvium capped the terrace at the Plant prior to Plant construction. Much of the alluvium was removed and/or reworked during construction activities (Cross sections A-A', B-B', and C-C', Plate 4-4).

The reworked Rocky Flats Alluvium in the study area is described as a generally poorly sorted, unconsolidated deposit of clay, silt, sand, and gravel. Colors range from light brown (5 YR 5/6) to gray brown (5 YR 3/2) with isolated horizons of olive gray (5 Y 3/2) to gray brown (5 YR 3/2). Color codes are adopted from GSA Color Chart. The grain size of the quartz and granitic sand ranges from fine- to coarse-grained (30 Ø - 10 Ø on the Wentworth Scale) with no single size taking predominance. Gravels range from 0.25 mm to 20 mm in size and are angular to subangular, indicative of materials transported short distances. The deposits are mildly calcareous and weakly cemented in places. Where undisturbed to the east of the Solar Evaporation Ponds, the Rocky Flats Alluvium is 8.7 feet thick (well 29-86).

#### 4.1.2 Colluvium

Colluvial materials are present on hill slopes to the northeast and southeast of the Plant descending to North and South Walnut Creeks and along the slopes of Woman Creek (Plate 4-3). Much of the colluvium on the slope due north of the Solar Evaporation Ponds was removed during construction of the PSZ fence and the French drain system. Colluvium was penetrated by wells 21-87 and 22-87 to depths of 9.5 and 12.8 feet, respectively.

Colluvium is described as consisting predominantly of clay with common occurrences of sandy clay and gravel layers. Colluvial clay is typically poorly consolidated and ranges in color from dark yellowish brown (10 YR 4/2) to light olive gray (5 Y 5/2) and light olive brown (5 Y 5/6). Occasional dark yellowish orange iron staining (10 YR 6/6) and stringers of brownish gray (5 YR 4/1) are present. Sand, when present, is very fine-grained to coarse-grained and poorly sorted. Occasional cobbles occur within gravel layers, which are poorly sorted and unconsolidated.



#### 4 1 3 Valley Fill Alluvium

The most recent alluvial deposit on Plant site is valley fill alluvium found along the drainages of North and South Walnut Creeks, and Woman Creek. This alluvium is derived from reworked and redeposited older alluviums and bedrock material.

Valley fill alluvium was encountered in eight wells in the study area ranging from 55 feet (36-86) to 161 feet (34-86) in thickness. The unconsolidated valley fill alluvium consists of poorly sorted sand, gravel, and cobbles in a clay matrix. Colors range from olive gray (5 Y 3/2) with dark yellowish orange mottles (10 YR 6/6) to dark yellowish brown (10 YR 4/2). Gravels are subangular to subrounded and unsorted. Composition of the valley fill alluvium does not differ significantly between North and South Walnut Creeks based on lithologic descriptions from borings for wells 13-86, 14-86, 15-86, 16-86, and 17-86 drilled in the North Walnut Creek drainage and borings for wells 34-86, 35-86, and 36-86 drilled in the South Walnut Creek drainage.

#### 4 1 4 Disturbed Ground

Plate 4-3 shows much of the area around the Solar Evaporation Ponds and on the 881 Hillside (wells 1-87, 51-87, and 53-87, Cross Section D-D', Plate 4-4) as disturbed ground. This includes the ponds, buildings, roadways, the PSZ fence, and the French drain system north of the ponds. A total of 20 wells and all 16 borings were drilled through disturbed materials (Plate 4-2). Areas of disturbed ground are also shown in cross sections B-B', C-C', D-D', and E-E' on Plate 4-4.

Disturbed ground is generally described as unconsolidated clay, silt, sand, gravel, and pebbles. The materials are very poorly sorted with fragments of claystone and cement rubble and display no bedding. A multitude of colors were encountered from olive to reddish brown (5 Y 5/6 - 10 R 5/4) to olive to yellow gray (5 Y 5/2 - 5 Y 8/4) and gray to yellow orange (10 YR 7/4 - 10 YR 6/6). Granitic and quartzite, angular to subangular gravels and pebbles are commonly found in areas of disturbed Rocky Flats Alluvium or disturbed colluvium. Sand, when present, varied from fine- to coarse-grained and was very poorly sorted. Thickness of the fill material ranges from 0.8 feet at well 32-86 (north of pond 207A) to greater than 21 feet at boring SP07-87 (east of Pond 207-B South).

#### 4.1.5 Artificial Fill

There are two types of artificial fill on the 881 Hillside (Plate 4-2) derived from separate sources (Rockwell International, 1988). The first is fill material derived from excavation of the Building 881 foundation, and the second is soil placed at SWMU 130 from the 1969 fire cleanup.

Material excavated for the Building 881 foundation was spread over a large area generally south of the building. The very poorly sorted and unconsolidated artificial fill was derived from Rocky Flats Alluvium, colluvium, and claystone bedrock. It is predominantly composed of sandy clay with some gravelly zones (Plate 4-4, Cross Section A-A'). The fill is generally brown to gray in color with occasional zones of moderate yellowish brown staining. A weakly cemented zone of caliche was encountered in well 54-87. The fill is underlain by colluvial and bedrock materials, and ranges from two to five feet in thickness (Rockwell International, 1988).

## 42 BEDROCK GEOLOGY

The Cretaceous Arapahoe Formation underlies surficial deposits in the Original Process Waste Lines Area. Ten wells were completed in various zones of the bedrock during the 1986 and 1987 drilling programs. The Arapahoe Formation beneath the study area consists primarily of claystone with interbedded sandstones and siltstones. The Arapahoe Formation was deposited by meandering streams flowing generally west to east off the Front Range. Sandstones were deposited as braided stream channel deposits and as overbank splays. Claystones were deposited in back swamp and floodplain areas. Leaf fossils, black organic matter, and wood fragments were encountered within the claystones during drilling near the solar ponds. Contacts between various lithologies are both gradational and sharp.

### 42.1 Arapahoe Claystones

Claystones were the most frequently encountered lithology of the Arapahoe Formation immediately below the Quaternary/Cretaceous contact (Cross Sections A-A' through E-E', Plate 4-4). Claystones are described as massive and blocky, containing occasional thin laminae and stringers of sands, silt, and coal.

Weathered bedrock was encountered directly beneath surficial materials in all of the monitor wells and borings. Weathering was noted to depths of 280 and 390 feet below ground surface in boring SP06-87 and monitor well 39-87BR, respectively. The weathered claystones generally range from pale yellowish brown (10 YR 6/2) to light olive gray (5 YR 5/6) in color and are moderately stained with iron oxide. Iron oxide stains also occurred as brown and red mottling. Calcium carbonate deposits along with iron oxide concretions are noted in the weathered zone. Fractures are

noted between 60 and 260 feet below ground surface in wells 24-86, 27-86, 22-87, 29-86, 31-86, and 33-86 associated with the weathered zone. Calcareous pockets and ironstone concretions were observed along these fractures.

Unweathered claystone is typically dark gray (N 3/0) to yellowish gray (5 Y 7/2) and has little mottling. Vertical, subvertical, horizontal, and 45 degree fractures associated with unweathered claystone are found at varying depths between approximately 30 feet (34-86) to greater than 100 feet (23-86). Fractures could not be correlated between boreholes. Many of the shallower fractures (30-60 feet) are described as calcareous, limonitic, or iron stained implying water movement. However, the fractures cannot be correlated between holes. Both weathered and unweathered claystone contains laminae of siltstone and very fine-grained sandstone. Typical siltstone and sandstone horizons range from brownish gray (5 YR 4/1) to dark yellowish orange (10 YR 6/6) in color.

#### 4.2.2 Arapahoe Formation Sandstones

Bedrock wells 14-86, 16-86, 23-86, 25-86, 27-86, 31-86, 32-86, and 39-87BR in the study area are completed in Arapahoe Formation sandstones. In addition, boreholes SP01-87, SP04-87, SP11-87 and SP12-87 encountered near surface Arapahoe sandstones. These sandstones are generally composed of moderately to well sorted, subrounded to rounded, very fine- to medium-grained, consolidated quartzose sand. The shallower (weathered) sandstones exhibited dark yellowish orange mottling (10YR 6/6), and cementation increased with depth due to a decrease in weathering. The thickness of individual sandstone layers ranged from 1.9 feet in wells 14-86 and 16-86 to a maximum of 19.8 feet in well 39-87BR. Most sandstones encountered contain thin beds or laminae of silt and clay. Bedding ranged from none apparent in well 32-

86 to convoluted bedding in well 23-86. Color of the sandstone ranged from light gray (N 6/6) to dark greenish gray (5 GY 4/1) in well 25-86 to olive gray (N 7/0) in well 32-86.

Siltstones were also encountered in the Arapahoe Formation during the drilling programs. Specifically, wells 14-86, 16-86, 23-86, and 25-86 encountered relatively homogeneous beds of unweathered siltstone. These beds ranged from less than one foot (well 14-86) to 30 feet in thickness (well 23-86). They are dark gray (N 3/0) to dark greenish gray (5 GY 4/1) in color, contain a trace of very fine-grained sand, are slightly calcareous, and contain some wood fragments.

As shown on cross sections A-A', B-B', and C-C' (Plate 4-4), sandstone/siltstone beds are present beneath the Original Process Waste Lines Area. Some beds occur at depth and others subcrop at the Quaternary/Cretaceous boundary. Cross sections A-A', B-B', and C-C' depict the siltstone and sandstone units dipping gently eastward at approximately seven degrees.

Subcropping sandstones were encountered in the vicinity of the solar ponds in wells 39-87BR, 31-86, 32-86, 22-86 and borings SP01-87, SP02-87, SP11-87, and SP04-87 (Plate 4-2). Subcropping sandstones vary in thickness from less than 30 feet at borehole SP04-87 to approximately 200 feet at well 39-87BR (Cross Sections B-B' and C-C', Plate 4-4). In well 31-86, approximately 110 feet of sand described as soft and weakly consolidated (very weathered) underlies disturbed ground. In all other cases the sandstone is consolidated and firm.

The subcropping Arapahoe sandstones are generally described as a fine- to coarse-grained (3.5 - 2.5  $\phi$ ), rounded to subrounded, weakly to moderately cemented, quartz sand. They occasionally contain small pebble horizons which are generally

moderately to well sorted. The sandstone color ranges from light gray (N 6/0) to dark gray (N 4/0) grading into yellow gray (5 Y 2/2 - 5 Y 7/2) and pale olive (10 YR 6/2). Yellow orange iron oxide staining (10 YR 6/6) is noted in several wells with the frequency of occurrence increasing toward the surface as a result of weathering.

The subcropping sandstone is generally weathered, blocky, massive, and contains lignite fragments (SP11-87) and leaf imprints (32-86). Calcium carbonate and coal stringers are noted in borehole SP03-87. Fractures are noted in core from holes 32-85, 31-86, and 22-86 at depths of 50, 68, and 144 feet, respectively. The fractures at 68 feet in hole 31-86 are infilled with calcareous deposits.

The relative vertical and horizontal location of the subcropping sandstones and the physical descriptions of the same sandstones in the solar pond area suggest that many of the subcropping sandstones are interconnected. Approximate areal extents of subcropping sandstones are shown in plan view on Plate 4-2.

One occurrence of subcropping sandstone appears at well 39-87BR where approximately 20 feet of fine-grained sandstone subcrop. Sandstone subcrop was not encountered in any adjacent wells.

The second and third occurrences of subcropping sandstones include borehole SP04-87 where approximately 30 feet of sandstone is present and borehole SP11-87 where approximately 85 feet of subcropping sandstone underlies disturbed ground. In both cases, no adjacent wells contain subcropping sandstone, suggesting that these sandstone occurrences have limited lateral extent.

A fourth and extensive area of subcropping sandstone occurs in wells 31-86, 32-86, 22-86, and boreholes SP01-87 and SP02-87. Sandstone thicknesses range from 50 feet to 155 feet in boreholes SP03-87 and 32-86, respectively. The combination of

these five holes outlines an oblong area underlying portions of Solar Evaporation Ponds 207-A and 207-C (Plate 4-2)

Finally, during the drilling of well 9-87BR, a sandstone unit was encountered at the Quaternary/Cretaceous contact, 127 feet below ground surface (Cross Section E-E', Plate 4-4). The unit was found to be 188 feet thick and ranged from very fine-grained to coarse-grained in nature. As discussed in detail in Rockwell International, 1988, the correlation between the sandstone unit found in well 9-87BR and 16-87BR which is primarily based on their similar lithologic characteristics, has set the basis for establishing a seven degree structural dip for the area.

## SECTION 5

### REFERENCES

- Boulder County Planning Commission, 1983, Boulder County Comprehensive Plan--Geology Element, Boulder County Land Use Department
- Costa, J E and S W Bilodeau, 1982, Geology of Denver, Colorado, United States of America Bulletin of the Association of Engineering Geologists, Vol XIX, No 3, pp 261-314
- Dames and Moore, 1981, Geologic and Seismologic Investigations for Rocky Flats Plant, Contract DE-AC04-80A110890
- DOE, 1980, Final Environmental Impact Statement Rocky Flats Plant Site, Golden, Jefferson County, Colorado, Volumes 1, 2, and 3, US Department of Energy Report, Washington, D C, DOE/EIS-0064
- Epis, R C and C E Chapin, 1975, "Geomorphic and Tectonic Implications of the Post-Laramide, Late Eocene Erosion Surface in the Southern Rocky Mountains", in Cenozoic History of the Southern Rocky Mountains, Curtis, B F (ed), Geologic Society of America Memoir 144, pp 45-74
- Fenneman, N M., 1931, Physiography of Western United States, McGraw Hill Book Company, New York, 534 p
- Grose, L T, 1972, Tectonics in Geologic Atlas of the Rocky Mountain Region, W W Mallory (ed), Rocky Mountain Association of Geologists, pp 35-44
- Hurr, R T, 1976, Hydrology of a Nuclear-Processing Plant Site, Rocky Flats, Jefferson County, Colorado US Geological Survey Open-File Report 76-268
- Hurr, R T, 1985, Personal Communication
- Kent, H C, 1972, Review of Phanerozoic History, in Geologic Atlas of the Rocky Mountain Region, W W Mallory (ed), Rocky Mountain Association of Geologists, pp 57-59
- Kirkham, R M. and W P Rogers, 1981, Earthquake Potential in Colorado, a Preliminary Evaluation, Colorado Geological Survey Bulletin 43
- Leroy, L W, and R J Weimer, 1971, Geology of the Interstate 70 Road Cut, Jefferson County, Colorado Colorado School of Mines Prof Contrib No 7
- Martin, C A, 1965, Denver Basin Bulletin of the American Association of Petroleum Geologists, Vol 49, No 11, pp 1908-1925
- Robinson, P, 1972, Tertiary History, in Geologic Atlas of the Rocky Mountain Region, W W Mallory (ed), Rocky Mountain Association of Geologists, pp 233-242



- Robson, S G, 1984, Bedrock Aquifers in the Denver Basin, Colorado, a Quantitative Water-Resources Appraisal US Geological Survey Open File Report 84-431, 111 p
- Rockwell International, 1986, Resource Conservation and Recovery Act Part B - Post-Closure Care Permit Application for US DOE Rocky Flats Plant, Hazardous and Radioactive Mixed Wastes, US Department of Energy, unnumbered report
- Rockwell International, 1987, Closure Plan Original Process Waste Lines, US Department of Energy, Rocky Flats Plant, Golden, Colorado, unnumbered report
- Rockwell International, 1988, Remedial Investigation Report for High Priority Sites (881 Hillside Area), US Department of Energy, Rocky Flats Plant, Golden, Colorado, March 1988
- Scott, G R, 1960, "Quaternary Sequence East of the Front Range Near Denver, Colorado", in Guide to Geology of Colorado, by Weimer, R J and J D Haun (eds), Geological Society of America, Rocky Mountain Association Geologists, Colorado Scientific Society, pp 206-211
- Scott, G R, 1963, Quaternary Geology and Geomorphic History of the Kassler Quadrangle, Colorado, US Geologic Survey Prof Paper 421-A
- Scott, G R, 1965, "Nonglacial Quaternary Geology of the Southern and Middle Rocky Mountains", in The Quaternary of the United States, Princeton University Press, pp 243-254
- Scott, G R, 1970, Quaternary Faulting and Potential Earthquakes in East-Central Colorado US Geological Survey, Prof Paper 700-C, pp C11-C18
- Scott, G R, 1975, Cenozoic Surfaces and Deposits in the Southern Rocky Mountains in Cenozoic History of the Southern Rocky Mountains, Curtis, B F (ed), Geological Society of America Memoir 144, pp 227-248
- Van Horn, R, 1976, Geology of the Golden Quadrangle, Colorado US Geological Survey Prof Paper 872, p 116
- Weimer, R J, 1973, A Guide to Uppermost Cretaceous Stratigraphy, Central Front Range, Colorado Deltaic Sedimentation, Growth Faulting and Early Laramide Crustal Movement, Mt Geol, Vol 10, No 3, pp 53-97
- Witkind, I J, 1976, Preliminary Map showing known and suspected active faults in Colorado US Geological Survey Open File Report 76-154

ID	BLDG	CONTENTS	REMARKS 2	REMARKS 3	PENDING ACTION	DRAWINGS
No	No					
125	561	T35	Old Process Waste Tank Currently	under RCRA Closure	No Action	
126	771	T37	Old Process Waste Tank Currently	under RCRA Closure	Investigation by FE	
127	779	T38	Old Process Waste Tank Currently	under RCRA Closure	No Action	
128	881	T39,1	Old Process Waste Tank Currently	under RCRA Closure	No Action	
129	881	T39,2	Old Process Waste Tank Currently	under RCRA Closure	No Action	
130	881	T39,3	Old Process Waste Tank Currently	under RCRA Closure	No Action	
131	881	T39,4	Old Process Waste Tank Currently	under RCRA Closure	No Action	

APPENDIX 4

ORIGINAL PROCESS WASTE LINES  
GEOLOGIC CHARACTERIZATION REPORT

**ORIGINAL PROCESS WASTE LINES  
GEOLOGIC CHARACTERIZATION REPORT  
ROCKY FLATS PLANT  
GOLDEN, COLORADO**

**OCTOBER 3, 1988**

Prepared for

Rockwell International  
Aerospace Operations  
Rocky Flats Plant  
Golden, Colorado 80401

Prepared by

Roy F Weston, Inc  
215 Union Boulevard  
Suite 600  
Lakewood, Colorado 80228

## TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
1	CONCLUSIONS AND RECOMMENDATIONS	1-1
2	INTRODUCTION	2-1
2 1	Report Overview	2-2
2 2	Site Location	2-3
2 2 1	Construction History	2-3
2 3	Objectives and Scope	2-6
3	REGIONAL SETTING	3-1
3 1	Climatology	3-1
3 2	Physiography	3-3
3 3	Regional Geology	3-6
3 3 1	Geologic and Stratigraphic History	3-6
3 3 2	Plant Bedrock Geology	3-12
3 3 3	Plant Surficial Geology	3-15
3 3 4	Regional Bedrock Structure	3-20
4	SITE GEOLOGY	4-1
4 1	Surficial Geology	4-1
4 1 1	Rocky Flats Alluvium	4-2
4 1 2	Colluvium	4-3
4 1 3	Valley fill Alluvium	4-4
4 1 4	Disturbed Ground	4-4
4 1 5	Artificial Fill	4-5
4 2	Bedrock Geology	4-6
4 2 1	Arapahoe Claystones	4-6
4 2 2	Arapahoe Formation Sandstones	4-7
5	REFERENCES	5-1

### APPENDIX - GEOLOGIC LOGS

## LIST OF PLATES

<u>PLATE NO</u>	<u>TITLE</u>
4-1	Monitor Well Locations
4-2	Original Process Waste Lines Monitor Well and Borehole Locations Cross Section Locations Lines and Subcropping Sandstone (Plan View) Map
4-3	Surficial Geology Map
4-4	Cross Sections A-A', B-B', C-C', D-D', and E-E'

## LIST OF FIGURES

<u>FIGURE NO</u>	<u>TITLE</u>	<u>PAGE</u>
2-1	Location of Rocky Flats Plant	2-4
2-2	Rocky Flats Plant Boundaries and Buffer Zone	2-5
3-1	1986 Annual Wind Rose for the Rocky Flats Plant	3-2
3-2	Generalized East-West Cross Section Front Range to Denver Basin	3-4
3-3	Structure of the Denver Basin	3-8
3-4	Generalized Stratigraphic Section, Golden-Morrison Area	3-9
3-5	Generalized Cross Section of Rocky Flats Plant	3-13
3-6	Surficial Alluvial Deposits in the Rocky Flats Area	3-17
3-7	Erosional Surfaces and Alluvial Deposits East of the Front Range, Colorado	3-18

## SECTION 1

### CONCLUSIONS AND RECOMMENDATIONS

The geologic information collected from the areas in the vicinity of the Original Process Waste Lines show that the system is situated within disturbed Rocky Flats Alluvium and/or disturbed colluvial materials. These overburden materials range from 0.8 to 21 feet thick and unconformably overlie Arapahoe Formation claystone or sandstone units.

The geology in the northern portion of the Original Process Waste Line system is well documented due to the drilling of numerous boreholes in 1986 and 1987 to characterize the hydrogeology of the Solar Evaporation Ponds Area. However, only limited data are available for the remainder of the study area. In addition, groundwater flow directions are poorly defined within the Plant security fence. Therefore, the following recommendations are made to characterize the hydrogeology in the vicinity of the Original Process Waste Lines.

Additional borings should be drilled along the southern and western portions of the Original Process Waste Line system. It is important to note that these proposed drilling locations are tentative and their exact placement will depend primarily upon each site's accessibility. The Original Process Waste Lines are located within the Plant and therefore the area is densely populated with buildings, parking lots, and utility lines.

Seven additional borings are proposed to characterize the geology in the Original Process Waste Lines area. These borings will be drilled to



- 1) Determine lithology and thickness of surficial materials
- 2) Determine lithology of bedrock beneath the Original Process Waste Lines
- 3) Determine thickness of subcropping sandstone units where encountered

These borings will be augered and sampled to a depth not less than ten feet into weathered bedrock. If a sandstone unit is encountered in the bedrock, the boring will extend through the entire thickness of the unit and will be terminated no less than five feet below the base of the sandstone. This method will enable the geologist to complete a detailed lithologic description of the bedrock materials.

Approximate locations for the proposed borehole locations are listed below.

- 1) 800 ft west and 150 ft south of well 23-86,
- 2) 400 ft west and 300 ft south of well 23-86,
- 3) 170 ft west and 330 ft south of location No 2,
- 4) 1,000 ft south of location No 3,
- 5) 500 ft west and 180 ft south of well 61-86,
- 6) 500 ft west of location No 6, and
- 7) 1,050 ft west of location No 6

Piezometers will be installed in the vicinity of the Original Process Waste Lines to define the extent of saturation and ground-water flow directions. Approximately 100 piezometers will be installed on 400 foot centers within the Plant security area. Another 26 piezometers will be located immediately adjacent to the Original Process Waste Lines for site-specific water level information.

Piezometers will be constructed by driving one-inch diameter PVC pipe to the anticipated top of bedrock at each location. The bottom five feet of each piezometer

will be screened. Water levels will be monitored on a monthly basis for one year following installation to provide seasonal water level information within the Plant.

Three alluvial ground-water monitor wells will also be installed adjacent to and presumably to downgradient of the Original Process Waste Lines. The approximate locations for the proposed wells are as follows:

- 1) 1,000 feet west and 40 feet south of well 10-87 (903 Pad Area),
- 2) 400 feet east and 350 feet south of well 44-86, and
- 3) 200 feet west and 400 feet south of well 23-86 (Solar Ponds Area)

These wells will be sampled quarterly as part of Interim Status ground-water monitoring for the Original Process Waste Lines. Slug tests will also be performed on these wells in order to determine the hydraulic conductivity of the Rocky Flats Alluvium in the Plant area and in further characterizing the hydrogeology in the vicinity of the Original Process Waste Lines.

## SECTION 2

### INTRODUCTION

This report presents a hydrogeologic and waste source characterization of the Original Process Waste Lines at Rocky Flats Plant. The Original Process Waste Lines were first identified as a RCRA regulated unit in the summer of 1985. Subsequently, the Original Process Waste Lines were abandoned by 1985. A closure plan for the Original Process Waste Lines is required pursuant to Part 270 and 264 of the Colorado State Hazardous Waste Regulations (6 CCR) and Title 40, Part 264 of the Code of Federal Regulations (40 CFR). The goal of the closure plan is to meet closure performance standards as follows:

- o The owner or operator must close the facility in a manner that a) minimizes the need for further maintenance, and b) controls, minimizes or eliminates, to the extent necessary to protect human health and the environment, post-closure escape of hazardous waste, constituents, leachate, contaminated rainfall, or waste decomposition products to the ground or surface waters or to the atmosphere (6 CCR and 40 CCR 264.111)
- o The owner or operator must provide a detailed description of the steps needed to remove or decontaminate all hazardous waste residues and contaminated containment system components, equipment, structures, and soils during partial and final closure including, but not limited to, procedures for cleaning equipment and removing contaminated soils, methods for sampling and testing surrounding soils, and criteria for determining the extent of decontamination necessary to satisfy the closure performance standard [6 CCR and 40 CFR 264.112 (b)(4)]
- o The owner or operator must provide a detailed description of other activities necessary during partial closure period to ensure that all partial and final closure satisfy the closure performance standards, including, but not limited to, ground-water monitoring, leachate collection, and run-on and run-off control [6 CCR and 40 CFR 264.112(b)(5)]

- o During the partial and final closure periods, all contaminated equipment, structures and soil must be properly disposed of, or decontaminated unless specified otherwise in 264 197 (6 CCR and 40 CFR 264 114)
- o If the owner or operator demonstrates that not all contaminated soils can be practically removed or decontaminated as required in paragraph 264 197(a), then the owner or operator must close the tank system and perform post-closure care in accordance with the closure and post-closure care requirements that apply to landfills (264 310)

A closure plan for the Original Process Waste Lines was submitted on November 25, 1987, as part of the Post-Closure Care Permit Application (Rockwell International, 1987) Interpretations and conclusions incorporated in this document supersede those in the November 25, 1987, plan

## 2.1 REPORT OVERVIEW

This report provides geologic results of the 1986 and 1987 site characterization investigations performed in areas adjacent to the Original Process Waste Lines There is no characterization of ground-water flow or quality presented in this report because no monitoring wells have been installed to specifically monitor the Original Process Waste Lines Additional wells and piezometers will be installed adjacent to the Original Process Waste Line during the fall and winter of 1988

The report begins with site background information Presented in this introduction are site location and description and objectives of this study The introduction is followed by a regional setting chapter (Section 3) which describes climatology, physiography and geology in the vicinity of Rocky Flats Plant Section 4, Site Geology, discusses the surficial and bedrock geology in the vicinity of the Original Process Waste Lines Appendix A contains geologic logs and well

construction summaries for the wells and boreholes in the vicinity of the Original Process Waste Lines

## 2.2 SITE LOCATION AND DESCRIPTION


The Rocky Flats Plant is located in northern Jefferson County, Colorado, approximately 16 miles northwest of Denver (Figure 2-1). The Plant consists of approximately 6,550 acres of federally owned land in Sections 1 through 4 and 9 through 15 of T2S, R70W, 6th Principal Meridian. Major buildings are located within the Plant security area of approximately 400 acres. The security area is surrounded by a buffer zone of approximately 6,150 acres (Figure 2-2).

This site characterization report addresses the Original Process Waste Lines, located within the Rocky Flats Plant security fence (Figure 2-2).

### 2.2.1 Construction History

The following information regarding the construction history and design of the Original Process Waste Lines is based on interviews with Dow Chemical and Rockwell International employees conducted by Chen and Associates personnel. In addition, previous reports and letters were reviewed.

The Original Process Waste Lines consist of a system of tanks and associated lines located within the Plant security fence. The system was constructed to transport and temporarily store process wastes from point of origin to on-site treatment points and was placed into operation in 1952. Additions to the system were made through 1975, and the original system has since been replaced. Details of the construction



history, design, past usage, and waste treatment are located in Sections 1 2 3 and 1 2 4 of this Original Process Waste Lines Closure Plan

### 2 3 OBJECTIVES AND SCOPE

The objectives of this study are to characterize the site geology in the vicinity of the Original Process Waste Lines. This information will support closure activities, post-closure care, and monitoring programs. It is also the objective of this study to make recommendations for additional data collection as needed for characterization of the geology.

It is not the intent of this study to characterize the hydrogeology and/or ground-water chemistry. No site-specific program was designed for the Original Process Waste Lines, therefore, insufficient data are available for a complete characterization. Data for this report have been taken from previous reports from areas adjacent to the Original Process Waste Lines (i.e., 881 Hillside and Solar Pond reports). Plans for ground-water investigations in accordance with 6 CCR 1007-C Part 264 and Part 265 (40 CFR Parts 264 and 265) are presented in Section E of the Post-Closure Care Permit Application.

## SECTION 3

### REGIONAL SETTING

This section presents the regional setting of Rocky Flats Plant, including discussions of climatology, physiography and geology. Site-specific discussions of the surficial and bedrock in the vicinity of the Original Process Waste Lines are presented in Section 4.


#### 3.1 CLIMATOLOGY

The area surrounding the Rocky Flats Plant has a semiarid climate typical of the Rocky Mountain region. However, the elevation of the Plant and the nearby slopes of the Front Range slightly modify the regional climate.

Winds at Rocky Flats Plant, although variable, are predominantly from the west-northwest. Stronger winds occur during the winter, and the area occasionally experiences Chinook winds with gusts up to 100 miles per hour because of its location near the Front Range (DOE, 1980). Figure 3-1 shows the wind direction, frequency, and average velocity for each direction as recorded in 1985.

Temperatures are moderate, extremely warm or cold weather is usually of short duration. On the average, daily summer temperatures range from 55 to 85 degrees Fahrenheit (F) and winter temperatures range from 20 to 45 degrees F. Temperature extremes recorded at the Plant have ranged from 102 degrees F on July 12, 1971 to -26 degrees F on January 12, 1963. The 24-year daily average maximum temperature for the period 1952 to 1976 was 76 degrees F, the daily average minimum





(after Rockwell International, 1987a)

**Figure 3-1:**  
**1986 Annual Wind Rose for the Rocky Flats Plant**


was 22 degrees F, and the average annual mean was 50 degrees F. Average relative humidity was 46 percent (DOE, 1980).

Average annual precipitation at the Plant is 15 inches. Approximately 40 percent of the precipitation falls during the spring season, much of it as snow. Thunderstorms from June to August account for an additional 30 percent of the precipitation. Autumn and winter are drier seasons, accounting for 19 and 11 percent of the annual precipitation, respectively. Snowfall averages 85 inches per year, generally occurring between October and May (DOE, 1980).

### 3.2 PHYSIOGRAPHY

The Rocky Flats Plant is located at an elevation of approximately 6,000 feet above mean sea level. The site is on the western margin of the Colorado Piedmont section of the Great Plains Physiographic Province (Fenneman, 1931). The Colorado Piedmont ranges in elevation from 4,000 feet on the east to 7,000 feet on the west. The Piedmont merges to the east with the High Plains section of the Great Plains Province and is terminated abruptly on the west by the Front Range section of the Southern Rocky Mountain Province (Figure 3-2).

The Colorado Piedmont is an area of dissected topography and denudation where Tertiary strata underlying the High Plains have been almost completely removed. In a regional context, the piedmont represents an old erosional surface along the eastern margin of the Rocky Mountains. It is underlain by gently dipping sedimentary rocks (Paleozoic to Cenozoic in age), which are abruptly upturned at the Front Range to form hogback ridges parallel to the mountain front. The piedmont surface is broadly rolling and slopes gently to the east with a topographic relief of



**Figure 3-2:**  
**Generalized East-West Cross Section**  
**Front Range to Denver Basin**

only several hundred feet. This relief is due both to resistant bedrock units that locally rise above the surrounding landscape and to the presence of incised stream valleys. Major stream valleys which transect the piedmont from west to east have their origin in the Front Range. Small local valleys have developed as tributaries to these major streams within the piedmont. In the area of the Plant, a series of Quaternary pediments have been eroded across this gently rolling surface (DOE, 1980).

The eastern margin of the Front Range a few miles west of the Plant is characterized by a narrow zone of hogback ridges and flatirons formed by steeply east-dipping Mesozoic strata (such as the Dakota Sandstone and the Fountain Formation). Less resistant sedimentary units were removed by erosion (Figure 3-2). The Front Range reaches elevations of 12,000 to 14,000 feet above mean sea level 15 miles farther west. The range itself is broad and underlain by resistant gneiss, schist and granitic rocks of Precambrian age. The resistant nature of these rocks has restricted stream erosion so that deep, narrow canyons have developed in the Front Range.

Several pediments have been eroded across both hard and soft bedrock in the area of the Plant during Quaternary time (Scott, 1963). The Rocky Flats pediment is the most extensive of these, forming a broad flat surface south of Coal Creek. The broad pediments and more narrow terraces are covered by thin alluvial deposits of ancient streams draining eastward into the Great Plains. The sequence of pediments reflects repetitive physical processes associated with cyclic changes in climate. Each erosional surface and stratigraphic sequence deposited on it probably represents a single glacial cycle. The oldest and highest pediment, the Subsummit Surface (Scott, 1960), truncates the hogback ridges of the Front Range. Three successively younger

pediments, veneered by alluvial gravels, extend eastward from the mountain front. Erosion of valleys into the pediments followed each depositional cycle so that, near the mountain front, stratigraphically younger geologic units occur at topographically lower elevations as narrow terrace deposits along the streams. From oldest to youngest, the three pre-Wisconsin deposits are the Rocky Flats Alluvium, the Verdos Alluvium and the Slocum Alluvium (Scott, 1965). A series of Wisconsin and post-Wisconsin terrace deposits are present at lower elevations along streams that have incised the older pediments (east of the Plant). These alluvial deposits are described in Section 3.3.3, Surficial Geology.

The Rocky Flats Plant is located on a relatively flat surface of Rocky Flats Alluvium. The pediment surface and overlying alluvium (generally 10 to 50 feet thick, although the alluvium is as much as 100 feet thick west of the Plant) have been eroded by Walnut Creek on the north and Woman Creek on the south so that terraces along these streams range in height from 50 to 150 feet. The grade of the gently eastward-sloping, dissected Rocky Flats Alluvium surface varies from 0.7 percent at the Plant to approximately 2 percent just east of the Plant.

### 3.3 REGIONAL GEOLOGY

#### 3.3.1 Geologic and Stratigraphic History

This section describes the regional geologic and stratigraphic history in the vicinity of the Plant, including the Denver Basin. Section 4 describes the site specific geology and stratigraphy of the Original Process Waste Lines Area.


The Rocky Flats Plant is located on the northwestern flank of the Denver Basin and is underlain by about 12,000 feet of Paleozoic and Mesozoic sedimentary

rocks (Hurr, 1976) The Denver Basin is an asymmetric syncline that formed during the Late Cretaceous Laramide Orogeny The western limb of the basin dips steeply to the east, and the eastern limb dips gently to the west (Figure 3-3)

The geologic history of northeastern Colorado involves several episodes of mountain building and oceanic transgression and regression, resulting in the deposition of thousands of feet of sedimentary rock on top of the Precambrian basement This section describes the geologic history beginning with Precambrian time Geologic descriptions of the various units are provided within this context More detailed descriptions of the units present on site are provided in Section 4


Early Precambrian tectonic, metamorphic, and plutonic igneous activity created a complex fabric in the basement rock of Colorado (Grose, 1972) The Precambrian units were covered by marine and continental sedimentation during the lower Paleozoic (carbonate and siliciclastic rock units were deposited unconformably on the Precambrian basement) Most of these units were later eroded by multiple Paleozoic diastrophisms, thus removing Cambrian to Mississippian rocks from the Denver Basin area (Kent, 1972)

Middle Pennsylvanian orogenic activity formed the Ancestral Rockies, and the Fountain Formation was deposited unconformably on the uplifted Precambrian basement (Figure 3-4) The Fountain Formation contains coarse clastics derived from the erosion of the Ancestral Rockies and deposited as alluvial fans along a continental margin (Martin, 1965) The result was nonmarine sedimentation that occurred in northeastern Colorado from the Triassic to early Cretaceous This sedimentation deposited a sequence of aeolian, fluvial-deltaic, and lacustrine units



(after Rockwell International, 1986a)

**Figure 3-3: STRUCTURE OF THE DENVER BASIN**



(after LeRoy and Weimer, 1971)

Figure 3-4: GENERALIZED STRATIGRAPHIC SECTION, Golden-Morrison Area



known as the Lyons, Lykins, Ralston Creek, Morrison, and Dakota Formations (Figure 3-4) (Kent, 1972)

The Pierre Shale, consisting of more than 5,600 feet of shales and siltstones, was deposited in the final phases of oceanic sedimentation. The sedimentation resulted from the last oceanic transgression occurring 100 million years ago during the late Cretaceous. This transgression formed an epicontinental sea called the Cretaceous Seaway that covered the eastern portions of New Mexico, Colorado, and Wyoming.

Following deposition of the Pierre, the ocean began to regress and deposition of the Upper Cretaceous Fox Hills and Laramie Formations occurred. These formations contain sandstones, siltstones, claystones, and coals deposited in fluvial-deltaic and lacustrine environments (Weimer, 1973). Deposition of the Laramie was influenced and then stopped by the Laramide Orogeny, a major mountain building event that began in the late Cretaceous and caused uplift of the Colorado Front Range Mountains and the eastward tilting of the Denver Basin.

The Upper Cretaceous Arapahoe Formation was deposited on an erosional surface marking the end of deposition of the Laramie. Major uplift of the Front Range and downwarp of the Denver Basin continued during deposition of the Arapahoe Formation. Coarse pebble conglomerate lenses deposited in alluvial fans commonly occur in the Lower Arapahoe, however, conglomerate lenses have not been found at Rocky Flats Plant. Claystone and sandstone units flank and top the alluvial fan deposits (Weimer, 1973).

The Denver Formation was deposited above the Arapahoe and is over 600 feet thick. This formation contains a variety of lithologies including siltstones, arkoses, conglomerates, and basalt flows (near Golden, Colorado) (Robson, 1984).

The Dawson Formation was deposited above the Denver in a similar geologic environment during the late Cretaceous and early Tertiary. Robinson (1972) described the Dawson Formation as a stratigraphic equivalent to the Denver Formation in southern portions of the Denver Basin. However, Robson (1984) mapped the Dawson as a separate, younger (Tertiary) formation occurring above the Denver. The Dawson is up to 600 feet thick and consists of conglomerates, sandstones, and shales (Robson, 1984).

The Tertiary Green Mountain Conglomerate was deposited unconformably on the Denver Formation, and consists of conglomerates, sandstones, siltstones, and claystones deposited by a local fluvial system that occurred only in the Golden, Colorado, area. This unit is only found capping Green Mountain, approximately 15 miles south of Rocky Flats Plant (Costa and Bilodeau, 1982).

The Rocky Flats Alluvium was deposited on top of a major erosional surface that developed in late Tertiary time. Before deposition of the Rocky Flats Alluvium, both the Dawson and Denver Formations were completely removed by erosion. The Green Mountain Conglomerate may never have been deposited at the site, but if it was, it also was removed by erosion. The Rocky Flats Alluvium contains boulders, cobbles, gravels, sands, silts, and clays deposited in alluvial fans at the base of the Colorado Front Range Mountains (Hurr, 1976).

Following deposition of the Rocky Flats Alluvium, the material was partially removed by erosion and the resulting drainages repeatedly infilled with more recent

sediments The Verdos Alluvium and the younger Slocum Alluvium are the result of drainage infilling associated with glacial activity Similar processes are occurring now with an active valley fill alluvium in the stream channels and a recent but stable terrace above the valley fill

### 3 3 2 Plant Bedrock Geology

Bedrock units mapped at the Plant consist of the Laramie and Arapahoe Formations (Rockwell International, 1986) These are shown in cross section in Figure 3-5 Because of the thickness (750 to 800 feet) and low permeability of the Upper Laramie, it is considered to be the base of the hydrologic system which could be affected by Plant operations (Hurr, 1976) The Upper Laramie and overlying Arapahoe Formations are described below

#### Laramie Formation

The Laramie Formation is a fluvial sequence of sandstones, siltstones, claystones, and coals, which is subdivided into two major lithologic units a lower sandstone unit and an upper claystone unit The lower sandstone unit is exposed in clay pits west of the Plant, and the upper claystone unit was observed in outcrop and in cores of several 1986 monitor wells west of the Plant The descriptions presented below are taken from Rockwell International (1986)

Lower Sandstone Unit The lower sandstone unit consists of light to medium gray, very fine- to medium-grained, well sorted, subrounded to subangular quartzose sand with up to 25% lithic fragments Sandstones are typically fair to poorly




Figure 3-5: GENERALIZED CROSS SECTION OF ROCKY FLATS PLANT

indurated and cemented with silica. Individual sandstone beds are 5 to 15 feet thick and are interbedded with white to light gray claystones. The claystones are organic-rich and kaolinitic and have been mined from the clay pits west of the plant. Individual claystone beds are 10 to 15 feet thick. Sedimentary structures observed in outcrop include planar, angular, and trough crossbeds, load structures, fluid escape structures, and ripple marks. Plant fossil casts and molds of branches, stems, and leaves are concentrated along bedding planes. The contact between the lower sandstone unit and the upper claystone unit is gradational and was selected where thick sandstone beds and kaolinite-rich claystones are less abundant.

Upper Claystone Unit The upper claystone unit consists primarily of dark olive gray (5 Y 2/1) (GSA Rock Color Chart), poorly indurated claystones. Upper Laramie claystones generally weather to a light olive gray (5 Y 4/1) and may have dark yellowish orange (10 YR 6/6) iron staining along bedding planes and secondary fractures. These claystones appear quite similar to Arapahoe claystones in outcrop.

Thin sandstone lenses (less than three feet thick) also occur in the upper Laramie. These sandstones are typically yellowish gray (5 Y 8/1), fine- to very fine-grained, well sorted, subangular, and calcareous. Core data (well 50-86) indicate that thin beds of white, kaolinite-rich claystone typical of the Lower Laramie occur in the Upper Laramie as well.

The contact between the Upper Laramie claystones and the Lower Arapahoe sandstones is gradational and was selected using core data. The contact was picked below the first Arapahoe sandstone greater than five feet thick (Rockwell

International, 1986) This is consistent with the stratigraphic horizon picked as the base of the Arapahoe Formation at Rocky Flats Plant by Hurr (1976, 1985)

#### Arapahoe Formation

The Arapahoe Formation consists of fluvial claystones with interbedded lenticular sandstones and siltstones. Contacts between these lithologies are both sharp and gradational. The claystones are olive gray (5 Y3/2) to dark gray (N 3/0), poorly indurated, silty, and contain up to 15 percent organic material. Weathering has penetrated from 10 to 40 feet into bedrock. The weathered claystone is light olive gray, blocky, slightly fractured, and has iron staining as mottles and along bedding planes and fractures (Rockwell International, 1986).

Sandstones in the Arapahoe Formation are light gray (N 6/0) to yellowish gray (5 YR 8/1), very fine- to medium-grained, with approximately 15 percent silt and clay. The sandstones are lenticular, discontinuous, and stratigraphically complex. The sand grains are subangular to subrounded and are predominantly quartzose with 10 percent lithic fragments. The sandstones are poorly to moderately cemented and exhibit ripple marks, load casts, and planar, angular, and trough crossbedding. Arapahoe Formation siltstones exhibit the same coloration, constituents, bedding characteristics, and sedimentary structures as the sandstones, however, they consist predominantly of silt-sized particles (Rockwell International, 1986).

#### 3.3.3 Plant Surficial Geology

There are six distinct Quaternary unconsolidated units of surficial materials in the vicinity of the Plant: Rocky Flats Alluvium, Verdos Alluvium, Slocum Alluvium, terrace alluviums, valley fill alluvium, and colluvium (Figure 3-6).

The Rocky Flats Alluvium is topographically the highest and the oldest of the alluvial deposits. The alluvium unconformably overlies the Laramie and Arapahoe Formations in the vicinity of the Plant. The deposit is a series of laterally coalescing alluvial fans deposited by streams (Hurr, 1976). The fans were deposited on an erosional surface cut into the bedrock units, including channelization around the hogbacks of the lower Laramie.

The alluvium consists of sand, clay, silt, gravel, cobble, and occasional boulder deposits. Locally, the alluvium is cemented with calcium carbonate in the form of caliche. Color of the alluvium is pale to dark yellowish brown. The sands range from very fine-grained to medium-grained and poorly to moderately sorted. The thickness of the alluvium is variable due to deposition on an erosional surface and recent erosional processes. The alluvium is thickest to the west of the Plant, where less has been eroded, and thinnest to the east of the Plant (Rockwell International, 1986).

Various alluvial deposits occur topographically below the Rocky Flats Alluvium in the drainages and include the Verdos, Slocum, terrace, and valley fill alluviums and colluvium (Figure 3-7). These deposits are primarily composed of reworked Rocky Flats Alluvium with the addition of some bedrock material. Each unit is described below.

YEARS before present	EPOCH	GLACIAL SEQUENCE	DEPOSIT			
1000	HOLOCENE	Gannett Peak Stadc ↑	"Valley Fill"	post-Piney Creek Alluvium	young alluvial fan	
2000		↓ Interstade		(Soil)		
3000		Temple Lake Stade ↓		Piney Creek Alluvium		
5000		"Altithermal Interval"		(Soil)		
12,000	PLEISTOCENE		Terrace Alluvium	pre-Piney Creek Alluvium	old alluvial fan	colluvium and landslides
				(Soil)		
		Pinedale Glaciation		Broadway Alluvium		
60,000						
		Bull Lake Glaciation		Louviers Alluvium		
130,000						
		Sangamon Interglaciation		(Soil)		
250,000				Slocum Alluvium		
		ILLINOIAN				
600,000		Yarmouth Interglaciation		(Soil)		
				Verdos Alluvium		
1,000,000		KANSAN				
		Aftonian Interglaciation		(Soil)		
				Rocky Flats Alluvium		
1,500,000		NEBRASKAN				
	Pleistocene or Pliocene			Pre-Rocky Flats Alluvium		loess and eolian sand

(after Van Horn, 1976, and Scott, 1965)


**Figure 3-6: SURFICIAL ALLUVIAL DEPOSITS IN THE ROCKY FLATS AREA**



WEST

EAST

ROCKY FLATS PLANT SITE



(after Scott, 1960)

Figure 3-7:

EROSIONAL SURFACES AND ALLUVIAL DEPOSITS EAST OF THE FRONT RANGE, COLORADO

The Verdos Alluvium occupies a topographic position about 0 to 100 feet below the adjacent top of the Rocky Flats Alluvium. The Verdos was deposited around the periphery of the present extent of the Rocky Flats Alluvium as fans and channel filling derived by erosion of the older Rocky Flats Alluvium. The maximum thickness is about 40 feet, occurring as terraces in valleys east of the Plant. The alluvium consists of unsorted gravels, sands, and clays similar to the Rocky Flats Alluvium, but the material is whitish gray in color (Rockwell International, 1986).

The Slocum Alluvium is a poorly sorted gravel deposit containing much sand, silt, and clay derived from erosion of bedrock and the older gravel deposits. The formation has a maximum thickness in the vicinity of the Plant of about 20 feet, but is commonly 5 to 10 feet thick. It occupies a topographic position of about 150 to 300 feet below the top of the Rocky Flats Alluvium, and occurs downslope of the Verdos Alluvium in valleys east of the Plant site (Rockwell International, 1986).

Locally, two Wisconsin-age terraces are associated with the present drainages. The terrace alluvium occurs 5 to 35 feet above recent valley floors. The alluvium is comprised of gravels, sands, and clays, derived from bedrock and reworking of older alluvial deposits. The terrace alluvium can rarely occur up to 30 feet in thickness, however, the thickness is usually around 5 feet. The alluvium occurs in valleys surrounding the Plant (Rockwell International, 1986).

Valley fill alluvium occurs in the bottom of the present stream valleys around the Plant. The valley fill ranges from dark-brown, sandy, clayey silt to moderately sorted cobbles and small boulders, recently reworked from previously deposited alluviums. The valley fill along streams which head on the Rocky Flats Alluvium and have not yet cut through to bedrock tends to be coarse and have little or no fine material. However, where the valley fill is deposited on bedrock, 0.5 to 2 feet of

cobbly sand and gravel commonly is overlain by several feet of sandy, clayey silt (Rockwell International, 1986) Subsequent erosion and deposition locally may have added more sand, gravel and cobbles on top of the silt, or cut through the valley fill to expose bedrock along the channel bottom (Hurr, 1976)

Colluvium, produced by mass wasting and downslope creep, collects on the sides and at the base of hills and slopes These deposits are poorly sorted mixtures of soil and debris from bedrock clay and sand mixed with gravel and cobbles derived from the older Rocky Flats Alluvium The colluvium consists predominantly of clay with common occurrences of sandy clay and gravel Color is yellowish brown to dusky brown and caliche is common locally The thickness of the colluvium ranges from 3 to 22 feet (Rockwell International, 1986)

#### 3 3 4 Regional Bedrock Structure

The general geologic structure of the area is north-striking sedimentary beds with dips to the east away from the Front Range Monocline Dips are quite steep west of the Plant in the Fox Hills Sandstone and Laramie Formation (on the order of 50 degrees or greater) These units are flanked on the west by Precambrian terrain of the Front Range Uplift and on the east by gently dipping sedimentary beds of the Denver Basin However, because the axis of the monocline onto the Front Range appears to be inclined to the east, dips become rapidly more gentle, on the order of 7 to 15 degrees beneath the Plant itself (Rockwell International, 1986) A major bounding fault between the Front Range and the Denver Basin, the Golden Fault, runs north-south several miles west of the Plant at the mountain front (Figure 3-7)

The majority of the displacement on the Golden Fault, the uplift of the Front Range and subsidence of the Denver Basin, occurred during the late Cretaceous to

early Eocene Laramide Orogeny about 40 to 70 million years ago (Martin, 1965) Erosion during the Laramide Orogeny is believed to have kept pace with uplift and the Front Range probably never stood very high above the Denver Basin during the orogeny By the late Eocene, an erosional surface of low relief covered much of the Rocky Mountain Region

The mountains west of the Rocky Flats Plant are the result of Post-Laramide tectonics and erosion About 5,000 to 10,000 feet of uplift has taken place in the Rocky Mountain Region since the early Miocene about 25 million years ago Late Tertiary block faulting is believed to have accompanied the regional uplift as indicated by apparent displacements of the late Eocene erosional surface (Scott, 1975 and Epis and Chapin, 1975) There is some evidence that block faulting has continued into the Quaternary (Scott, 1970, Whitkind, 1976, and Kirkham and Rogers, 1981)

In 1981, extensive studies were done to evaluate the Quaternary history of the Golden Fault and other faults at the Rocky Flats Plant and vicinity (Dames and Moore, 1981) The Golden Fault studies did not produce any evidence of tectonic activity along the Golden Fault within the past 500,000 years, and the fault does not have surficial expressions characteristic of geologically young fault zones

Hurr (1976) showed a fault crossing the eastern edge of the Plant, based on a series of bedding irregularities that appeared to be an extension of the previously mapped Eggleston Fault (northwest of the site) Further investigations of the feature (Dames and Moore, 1981) revealed that it is probably a penecontemporaneous growth fault attributed to slumping of the unconsolidated Arapahoe Formation before burial and lithification The Denver Basin has been tectonically stable for about 28 million years with the exception of a series of earthquakes associated with waste injection at

NOTICE

This document (or documents) is oversized for 16mm microfilming, but is available in its entirety on the 35mm fiche card referenced below:

Document # 000297

Titled: Original Process Waste Line Report Rocky Flats  
Plant Monitor Well Locations Plate 4-1

Fiche location: A-SW-M19

NOTICE

This document (or documents) is oversized for 16mm microfilming, but is available in its entirety on the 35mm fiche card referenced below:

Document # 000297

Titled: Original Process Waste Line Report Plate 4-2:  
Original Process Waste Lines, Monitor Well and Borehole Locations,  
Cross Section Location Lines, and Subcropping Sandstone (Plain View) Map

Fiche location: A-SW-M19

NOTICE

This document (or documents) is oversized for 16mm microfilming, but is available in its entirety on the 35mm fiche card referenced below:

Document # 000297

Titled: Plate 4-3: Original Process Waste Line Report  
Surficial Geology MAP

Fiche location: A-SW-M19

NOTICE

This document (or documents) is oversized for 16mm microfilming, but is available in its entirety on the 35mm fiche card referenced below:

Document # 000297

Titled: Original Process Waste Line Report Plate 4-4

Cross Sections A-A', B-B', C-C', D-D', and E-E'

Fiche location: A-SW-M20



UNITED STATES

## DEPARTMENT OF ENERGY

ALBUQUERQUE OPERATIONS OFFICE

# ROCKY FLATS AREA OFFICE

# UNDERGROUND PIPING AND TANK REMOVAL

# ROCKWELL INTERNATIONAL

# ROCKY FLATS PLANT

**GOLDEN, COLORADO 80402-0464**

## INDEX OF DRAWINGS


<u>DRAWING NO</u>	<u>TITLE</u>
37348-CX1	INDEX & TITLE SHEET
37348-C01	SITE PLAN
37348-C02	PIPING PARTIAL ABANDONMENT PLAN NO 1
37348-C03	PIPING PARTIAL ABANDONMENT PLAN NO.2
37348-C04	PIPING PARTIAL ABANDONMENT PLAN NO.3
37348-C05	PIPING PARTIAL ABANDONMENT PLAN NO.4
37348-C06	PIPING PARTIAL ABANDONMENT PLAN NO 5
37348-C07	PIPING PARTIAL ABANDONMENT PLAN -NO 6
37348-C08	PIPING PARTIAL ABANDONMENT PLAN NO 7
37348-C09	PIPING PARTIAL ABANDONMENT PLAN NO 8

[illegible]

E 17,500  
E 18,000  
E 18,500  
E 19,000  
E 19,500  
E 20,000  
E 20,500  
E 21,000  
E 21,500  
E 22,000  
E 22,500  
E 23,000  
E 23,500

NOTES

1. FOR DESCRIPTION OF TANKS SEE DWG 3748-C01



PROJECT AREA (TYPICAL)  
SEE ENLARGED PLANS OF  
EACH AREA

CONCEPTUAL  
DESIGN REPORT  
NOT FOR CONSTRUCTION

SITE PLAN

SCALE 1" = 200'

A. ORIGINAL SHEET		B. REVISIONS	
NO.	DESCRIPTION	NO.	DESCRIPTION
1	ISSUED 8-21-63		
2	REVISION 8-21-63		
3	REVISION 8-21-63		
4	REVISION 8-21-63		
5	REVISION 8-21-63		
6	REVISION 8-21-63		
7	REVISION 8-21-63		
8	REVISION 8-21-63		
9	REVISION 8-21-63		
10	REVISION 8-21-63		
11	REVISION 8-21-63		
12	REVISION 8-21-63		
13	REVISION 8-21-63		
14	REVISION 8-21-63		
15	REVISION 8-21-63		
16	REVISION 8-21-63		
17	REVISION 8-21-63		
18	REVISION 8-21-63		
19	REVISION 8-21-63		
20	REVISION 8-21-63		
21	REVISION 8-21-63		
22	REVISION 8-21-63		
23	REVISION 8-21-63		
24	REVISION 8-21-63		
25	REVISION 8-21-63		
26	REVISION 8-21-63		
27	REVISION 8-21-63		
28	REVISION 8-21-63		
29	REVISION 8-21-63		
30	REVISION 8-21-63		
31	REVISION 8-21-63		
32	REVISION 8-21-63		
33	REVISION 8-21-63		
34	REVISION 8-21-63		
35	REVISION 8-21-63		
36	REVISION 8-21-63		
37	REVISION 8-21-63		
38	REVISION 8-21-63		
39	REVISION 8-21-63		
40	REVISION 8-21-63		
41	REVISION 8-21-63		
42	REVISION 8-21-63		
43	REVISION 8-21-63		
44	REVISION 8-21-63		
45	REVISION 8-21-63		
46	REVISION 8-21-63		
47	REVISION 8-21-63		
48	REVISION 8-21-63		
49	REVISION 8-21-63		
50	REVISION 8-21-63		
51	REVISION 8-21-63		
52	REVISION 8-21-63		
53	REVISION 8-21-63		
54	REVISION 8-21-63		
55	REVISION 8-21-63		
56	REVISION 8-21-63		
57	REVISION 8-21-63		
58	REVISION 8-21-63		
59	REVISION 8-21-63		
60	REVISION 8-21-63		
61	REVISION 8-21-63		
62	REVISION 8-21-63		
63	REVISION 8-21-63		
64	REVISION 8-21-63		
65	REVISION 8-21-63		
66	REVISION 8-21-63		
67	REVISION 8-21-63		
68	REVISION 8-21-63		
69	REVISION 8-21-63		
70	REVISION 8-21-63		
71	REVISION 8-21-63		
72	REVISION 8-21-63		
73	REVISION 8-21-63		
74	REVISION 8-21-63		
75	REVISION 8-21-63		
76	REVISION 8-21-63		
77	REVISION 8-21-63		
78	REVISION 8-21-63		
79	REVISION 8-21-63		
80	REVISION 8-21-63		
81	REVISION 8-21-63		
82	REVISION 8-21-63		
83	REVISION 8-21-63		
84	REVISION 8-21-63		
85	REVISION 8-21-63		
86	REVISION 8-21-63		
87	REVISION 8-21-63		
88	REVISION 8-21-63		
89	REVISION 8-21-63		
90	REVISION 8-21-63		
91	REVISION 8-21-63		
92	REVISION 8-21-63		
93	REVISION 8-21-63		
94	REVISION 8-21-63		
95	REVISION 8-21-63		
96	REVISION 8-21-63		
97	REVISION 8-21-63		
98	REVISION 8-21-63		
99	REVISION 8-21-63		
100	REVISION 8-21-63		

SITE PLAN

3748-C01 A 2

PIPING IDENTIFICATION LEGEND

- A - DENOTES PIPING PRESENTLY ABANDONED
- T - DENOTES PIPING TEMPORARILY IN USE TO BE ABANDONED
- F - DENOTES PIPING TO BE ABANDONED WHEN SYSTEM IS UPGRADED TO AN RESPECTABLE SYSTEM IN THE FUTURE
- NOTE: NUMBERS FOLLOWING THE LETTER ABBREVIATE DENOTES PIPE SIZE IN INCHES
- DENOTES PIPING UNDERGROUND
- - - - - DENOTES PIPING ABOVE GROUND

TANK DESCRIPTION & DISPOSITION

- T - TWO 2500 GALLON BURNED TANKS, DECONTAMINATE AND USE FOR FIRE WATER RETENTION
- B - 7000 GALLON BURNED TANK UNDER BUILDING, REMOVE AFTER RESPECTABLE TANKS ARE PROVIDED
- C - TWO 14000 GALLON AND ONE 3000 GALLON BURNED TANKS, REMOVE AFTER RESPECTABLE TANKS ARE PROVIDED
- D - 300,000 GALLON ABOVE GROUND TANK, REMOVE AFTER REPLACEMENT TANK IS PROVIDED
- E - TWO 22,500 GALLON AND TWO 4500 GALLON BURNED TANKS, DECONTAMINATE AND USE FOR FIRE WATER RETENTION
- F - 3000 GALLON BURNED TANK REMOVE (SEE DWG. 3706-C07)

CONCEPTUAL  
DESIGN REPORT  
NOT FOR CONSTRUCTION


ORIGINAL ISSUE		DATE		BY		NO.	
1	DESIGN	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
2	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
3	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
4	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
5	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
6	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
7	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
8	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
9	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83
10	REVISION	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83	10/1/83



PLAN NO. 1

MERRICK

37348-C02 | A | 3



### PIPING IDENTIFICATION LEGEND

A --- DENOTES PRINTS PRESENTLY ASSIGNED.  
T --- DENOTES PRINTS TEMPORARILY IN USE.  
--- TO BE ASSIGNED.  
F --- DENOTES PRINTS TO BE ASSIGNED WHEN  
SYSTEM IS UPGRADED TO AN RESPECTABLE  
SYSTEM IN THE FUTURE.  
NOTE  
NUMBERS FOLLOWING THE LETTER ABBREY  
DENOTES THE BATCH NUMBER.  
--- DENOTES PRINTS UNDERGOING.  
--- DENOTES PRINTS ABOVE GRADED.

**CONCEPTUAL  
DESIGN REPORT  
NOT FOR CONSTRUCTION**

ORIGINAL ISSUE		369801	
REVISION	DATE	BY	REASON
1	10/1/80	WJ	REVISION
2	10/1/80	WJ	REVISION
3	10/1/80	WJ	REVISION
4	10/1/80	WJ	REVISION
5	10/1/80	WJ	REVISION
6	10/1/80	WJ	REVISION
7	10/1/80	WJ	REVISION
8	10/1/80	WJ	REVISION
9	10/1/80	WJ	REVISION
10	10/1/80	WJ	REVISION
11	10/1/80	WJ	REVISION
12	10/1/80	WJ	REVISION
13	10/1/80	WJ	REVISION
14	10/1/80	WJ	REVISION
15	10/1/80	WJ	REVISION
16	10/1/80	WJ	REVISION
17	10/1/80	WJ	REVISION
18	10/1/80	WJ	REVISION
19	10/1/80	WJ	REVISION
20	10/1/80	WJ	REVISION
21	10/1/80	WJ	REVISION
22	10/1/80	WJ	REVISION
23	10/1/80	WJ	REVISION
24	10/1/80	WJ	REVISION
25	10/1/80	WJ	REVISION
26	10/1/80	WJ	REVISION
27	10/1/80	WJ	REVISION
28	10/1/80	WJ	REVISION
29	10/1/80	WJ	REVISION
30	10/1/80	WJ	REVISION
31	10/1/80	WJ	REVISION
32	10/1/80	WJ	REVISION
33	10/1/80	WJ	REVISION
34	10/1/80	WJ	REVISION
35	10/1/80	WJ	REVISION
36	10/1/80	WJ	REVISION
37	10/1/80	WJ	REVISION
38	10/1/80	WJ	REVISION
39	10/1/80	WJ	REVISION
40	10/1/80	WJ	REVISION
41	10/1/80	WJ	REVISION
42	10/1/80	WJ	REVISION
43	10/1/80	WJ	REVISION
44	10/1/80	WJ	REVISION
45	10/1/80	WJ	REVISION
46	10/1/80	WJ	REVISION
47	10/1/80	WJ	REVISION
48	10/1/80	WJ	REVISION
49	10/1/80	WJ	REVISION
50	10/1/80	WJ	REVISION
51	10/1/80	WJ	REVISION
52	10/1/80	WJ	REVISION
53	10/1/80	WJ	REVISION
54	10/1/80	WJ	REVISION
55	10/1/80	WJ	REVISION
56	10/1/80	WJ	REVISION
57	10/1/80	WJ	REVISION
58	10/1/80	WJ	REVISION
59	10/1/80	WJ	REVISION
60	10/1/80	WJ	REVISION
61	10/1/80	WJ	REVISION
62	10/1/80	WJ	REVISION
63	10/1/80	WJ	REVISION
64	10/1/80	WJ	REVISION
65	10/1/80	WJ	REVISION
66	10/1/80	WJ	REVISION
67	10/1/80	WJ	REVISION
68	10/1/80	WJ	REVISION
69	10/1/80	WJ	REVISION
70	10/1/80	WJ	REVISION
71	10/1/80	WJ	REVISION
72	10/1/80	WJ	REVISION
73	10/1/80	WJ	REVISION
74	10/1/80	WJ	REVISION
75	10/1/80	WJ	REVISION
76	10/1/80	WJ	REVISION
77	10/1/80	WJ	REVISION
78	10/1/80	WJ	REVISION
79	10/1/80	WJ	REVISION
80	10/1/80	WJ	REVISION
81	10/1/80	WJ	REVISION
82	10/1/80	WJ	REVISION
83	10/1/80	WJ	REVISION
84	10/1/80	WJ	REVISION
85	10/1/80	WJ	REVISION
86	10/1/80	WJ	REVISION
87	10/1/80	WJ	REVISION
88	10/1/80	WJ	REVISION
89	10/1/80	WJ	REVISION
90	10/1/80	WJ	REVISION
91	10/1/80	WJ	REVISION
92	10/1/80	WJ	REVISION






**PIPING IDENTIFICATION LEGEND**  
A — DENOTES PIPING PRESENTLY ABANDONED  
T — DENOTES PIPING TEMPORARILY IN USE  
TO BE ABANDONED  
F — DENOTES PIPING TO BE ABANDONED WHEN  
SYSTEM IS UPGRADED TO AN INSPECTABLE  
SYSTEM IN THE FUTURE  
NOTE  
NUMBERS FOLLOWING THE LETTER ABREVEY  
DENOTES PIPE BRANCH NUMBER  
DENOTES PIPING UNDERGROUND  
DENOTES PIPING ABOVE GROUND



**CONCEPTUAL  
DESIGN REPORT  
NOT FOR CONSTRUCTION**

REVISION		DATE	BY	DESCRIPTION
1	ORIGINAL ISSUE			
2	REVISION			
3	REVISION			
4	REVISION			
5	REVISION			
6	REVISION			
7	REVISION			
8	REVISION			
9	REVISION			
10	REVISION			
11	REVISION			
12	REVISION			
13	REVISION			
14	REVISION			
15	REVISION			
16	REVISION			
17	REVISION			
18	REVISION			
19	REVISION			
20	REVISION			
21	REVISION			
22	REVISION			
23	REVISION			
24	REVISION			
25	REVISION			
26	REVISION			
27	REVISION			
28	REVISION			
29	REVISION			
30	REVISION			
31	REVISION			
32	REVISION			
33	REVISION			
34	REVISION			
35	REVISION			
36	REVISION			
37	REVISION			
38	REVISION			
39	REVISION			
40	REVISION			
41	REVISION			
42	REVISION			
43	REVISION			
44	REVISION			
45	REVISION			
46	REVISION			
47	REVISION			
48	REVISION			
49	REVISION			
50	REVISION			
51	REVISION			
52	REVISION			
53	REVISION			
54	REVISION			
55	REVISION			
56	REVISION			
57	REVISION			
58	REVISION			
59	REVISION			
60	REVISION			
61	REVISION			
62	REVISION			
63	REVISION			
64	REVISION			
65	REVISION			
66	REVISION			
67	REVISION			
68	REVISION			
69	REVISION			
70	REVISION			
71	REVISION			
72	REVISION			
73	REVISION			
74	REVISION			
75	REVISION			
76	REVISION			
77	REVISION			
78	REVISION			
79	REVISION			
80	REVISION			
81	REVISION			
82	REVISION			
83	REVISION			
84	REVISION			
85	REVISION			
86	REVISION			
87	REVISION			
88	REVISION			
89	REVISION			
90	REVISION			
91	REVISION			
92	REVISION			
93	REVISION			
94	REVISION			
95	REVISION			
96	REVISION			
97	REVISION			
98	REVISION			
99	REVISION			
100	REVISION			

REVISION



**PLAN NO 5**  
SCALE 1" = 40'  
20 0 20 40 60 80  
N  
Z











A --- DENOTES PRING PRESENTLY ABANDONED.  
T --- DENOTES PRING TEMPORARILY IN USE  
TO BE ABANDONED.  
F --- DENOTES PRING TO BE ABANDONED WHEN  
SYSTEM IS UPGRADED TO AN ACCEPTABLE  
STANDARD IN THE FUTURE.  
NOTE: NUMBERS FOLLOWING THE LETTER ABBREY  
DENOTES PURE BRANCH NUMBER.  
--- DENOTES PRING UNDERGROUND.  
--- DENOTES PRING ABOVE GROUND.








**CONCEPTUAL  
DESIGN REPORT  
NOT FOR CONSTRUCTION**

[illegible]








**EXPLANATION**

SCALE:	Well Identification	QUATERNARY	Clay
50 feet	Ground Surface Elevation (Surveyed)	Colluvium	Clayey Sand or Sandy Clay
0	Water level (Measured 4/11/89)	Disturbed Ground	Sand and/or Sandstone
50 feet	Geologic Contact (dashed where inferred)	Rocky Flats Alluvium	Sand and/or Gravel
No Vertical Exaggeration	Screened Interval	Valley Fill Alluvium	Silt and/or Siltstone
	Total Depth Drilled	CRETACEOUS	Claystone
		Arapahoe Formation (Claystone)	
		Arapahoe Formation (Sandstone & Siltstone)	

NOTE: Cross Section B-B' scale is 1"=100' both Vertically and Horizontally.  
All other scales are 1"=500'.  
THERE IS NO VERTICAL EXAGGERATION ON ANY CROSS SECTION.





**WESTON**  
SURFICIAL GEOLOGY MAP

ROCKWELL INTERNATIONAL  
Rocky Flats Plant  
Golden, Colorado  
Plate 4-3:  
Original Process Waste Line Report  
SURFICIAL GEOLOGY MAP

715 Union Boulevard  
Suite 400  
Golden, Colorado 80639  
(303) 986-8900

200' 0 200'

Graphic Interval: 2"  
Scale: 1" = 200'

N

EXPLANATION	
Artificial Fill	Terrace Alluvium
Disturbed Ground	Rocky Flats Alluvium
Recent Valley Fill	Vados Alluvium
Landslide	Arapahoe Formation (Sandstone)
Colluvium	Arapahoe Formation (Claystone)
Pseudophytes	Contact (dashed where inferred)





2.5 Union Boulevard  
Lawrence, Colorado 80028  
(303) 966-8800

**WESTON**  
ENGINEERS

ROCKWELL INTERNATIONAL  
Rocky Flats Plant  
Golden, Colorado

Original Process Waste Line Report  
Plate 4-2:  
ORIGINAL PROCESS WASTE LINES, MONITOR WELL AND  
BOREHOLE LOCATIONS, CROSS SECTION  
LOCATION LINES, AND SUBCROPPING SANDSTONE  
(Plan View) MAP

October, 1988

Approximate Location of  
Original Process Waste Lines

Alluvial Monitor Well  
9-87  
Bedrock Monitor Well  
BH23-87  
Borehole  
Line of Section  
Sandstone Subcropping

Scale: 1" = 200'  
0 200'

North Arrow



